Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
BR-0035	X-1A

Station	Uncl. Exc.	Embt
L Stage 1	(cu. yd.)	(cu. yd.)
14+00.00	0	0
14+50.00	361	0
15+00.00	353	1
15+50.00	429	1
16+00.00	439	0
16+50.00	356	55
17+00.00	261	148
17+50.00	79	231
18+00.00	5	555
18+50.00	9	1006
19+00.00	11	1137
19+50.00	11	1090
20+00.00	9	1125
20+50.00	9	1146
21+00.00	15	1053
21+50.00	19	917
22+00.00	17	762
22+50.00	14	631
23+00.00	6	814
23+50.00	8	754
24+00.00	16	454
24+50.00	7	409
25+00.00	0	281
25+50.00	0	125
26+00.00	0	53
26+50.00	6	38

Station	Uncl. Exc.	Embt
L Stage 2	(cu. yd.)	(cu. yd.)
24+00.00	20	193
24+50.00	9	74
25+00.00	18	49
25+50.00	40	59
26+00.00	49	11
26+50.00	55	1
27+00.00	63	40
27+50.00	382	58
28+00.00	742	37
28+50.00	569	26
29+00.00	188	7

Station	Uncl. Exc.	Embt
DR1	(cu. yd.)	(cu. yd.)
10+40.00	0	0
10+50.00	2	0
11+00.00	20	0
11+50.52	24	0

Station	Uncl. Exc.	Embt
DR2	(cu. yd.)	(cu. yd.)
10+12.00	0	0
10+50.00	0	5
11+00.00	4	6

Station	Uncl. Exc.	Embt
L Stage 2	(cu. yd.)	(cu. yd.)
11+80.00	0	0
12+00.00	7	0
12+50.00	95	5
13+00.00	231	5
13+50.00	333	0
14+00.00	413	0
14+50.00	274	0
15+00.00	51	6
15+50.00	11	26
16+00.00	26	63
16+50.00	26	44
18+00.00	0	7
18+50.00	0	26
19+00.00	0	43
19+50.00	0	53
20+00.00	0	56
20+50.00	1	56
21+00.00	3	116
21+50.00	4	201
22+00.00	3	261
22+50.00	1	290
23+00.00	0	390
23+50.00	11	366

Station	Uncl. Exc.	Embt
DR3	(cu. yd.)	(cu. yd.)
10+00.00	0	0
10+50.00	12	1
11+00.00	7	13
11+50.00	0	25
12+00.40	0	26