PROJECT NO.	SHEET NO.	TOTAL NO.
PT.08.06.10761, 2022CPT.08.06	14	

THERMOPLASTIC AND PAINT QUANTITIES

										4413000000-E	4457000000-N	4510000000-N	4685000000-E		4695000000-E	4700000000-E	4725000000-E			4810000000-E		4820000000-E	4825000000-E	4835000000-E	4840000000-N	4845000000-N			4891000000-E	4895000000-N	
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	LAW ENFORCEMENT	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	12" X 90 M YELLOW THERMO	THERMO LT ARROW 90 M	THERMO RT ARROW 90 M	THERMO STR ARROW 90 M	4" WHITE PAINT	4" YELLOW PAINT	8" WHITE PAINT	12" YELLOW PAINT	24" WHITE PAINT	PAINT MSG SCHOOL	PAINT LT ARROW	PAINT RT ARROW	PAINT STR ARROW	GENERIC PAVEMENT MARKING ITEM - 24" X 90 M WHITE THERMO	GENERIC PAVEMENT MARKING ITEM - NON-CAST IRON SNOWPLOWABLE (Y & Y)	GENERIC PAVEMENT MARKING ITEM - NON-CAST IRON SNOWPLOWABLE (C & R)
								MI	FT	SF	LS	HR	LF	LF	LF	LF	EA	EA	EA	LF	LF	LF	LF	LF	EA	EA	EA	EA	LF	EA	EA
2022CPT.08.06.10761	Randolph	1	NC-22	(FROM: SR 2235 ANDREW HUNTER RD. TO: SR 2226 CEDAR FALLS RD.)	1	2	2WU	0.81	23	91			8,554	8,554						8,554	8,554									54	
TOTAL FOR MAP NO. 1								**0.81**		**91**			**8,554**	**8,554**						**8,554**	**8,554**									**54**	
2022CPT.08.06.10761	Randolph	2	NC-22	(FROM: SR 2226 CEDAR FALLS RD. TO: SR 2261 OLD LIBERTY RD.)	2	2	2WU	4.95	23	555			52,242	52,242														58	327	
TOTAL FOR MAP NO. 2								**4.95**		**555**			**52,242**	**52,242**														**58**	**327**	
2022CPT.08.06.10761	Randolph	3	NC-159	(FROM: CJ NEAR ZOO CONNECTOR TO: CJ AT US 64 BYPASS)	1	2	2WU	0.35	23	40			3,696	3,696						3,696	3,696									24	
TOTAL FOR MAP NO. 3								**0.35**		**40**	*		**3,696**	**3,696**						**3,696**	**3,696**									**24**	
2022CPT.08.06.10761	Randolph	4	US-220 BUS	(FROM: MM 15.13 NEAR SR 1961 RANDLEMAN LAKE RD TO: MM 16.35 PAST SR 2284 ARCADIA RD.)	3	2	2WU	1.22	24	137			12,884	12,884						12,884	12,884								94	81	
TOTAL FOR MAP NO. 4								**1.22**		**137**			**12,884**	**12,884**						**12,884**	**12,884**								**94**	**81**	
2022CPT.08.06.10761	Randolph	5	NC-42 E	(FROM: U.S. 64 E. DIXIE DR. TO: ASHEBORO BYPASS TIE-IN)	2,4,5	2	2WU	1.65	25	185		40	17,530	17,530	50	75	8	3	4	1,646		50	75	70		8	3	4	70	109	42
TOTAL FOR MAP NO. 5								**1.65**		**185**		**40**	**17,530**	**17,530**	**50**	**75**	**8**	**3**	**4**	**1,646**		**50**	**75**	**70**		**8**	**3**	**4**	**70**	**109**	**42**
2022CPT.08.06.10761	Randolph	6	NC-42 E	(FROM: ASHEBORO BYPASS TIE-IN TO: SR 2830 OLD HUMBLE MILL RD.)	2	2	2WU	1.56	25	174			16,474	16,474															103	
TOTAL FOR MAP NO. 6								**1.56**		**174**			**16,474**	**16,474**															**103**	
TOTAL FOR PROJ NO. 2022CPT.08.06.10761								**10.54**		**1,182**	**1.0000**	**40**	**111,380**	**111,380**	**50**	**75**	**8**	**3**	**4**	**26,780**	**25,134**	**50**	**75**	**70**		**8**	**3**	**4**	**222**	**698**	**42**
													222,760				**15**			**51,914**						**15**				**740**	
2022CPT.08.06.20761	Randolph	7	SR 2495 MULBERRY ACADEMY ST.	(FROM: SR 2491 PATTERSON GROVE RD. TO: SR 2500 ACADEMY RD. EXT.)	6	2	2WU	2.53	20	284																						
TOTAL FOR MAP NO. 7								**2.53**		**284**																						
2022CPT.08.06.20761	Randolph	8	SR 1681 BALFOUR DR.	(FROM:SR-1009 N MAIN ST. TO: SR 1577 ARCHDALE RD.)	6,7,8	2	2WU	0.82	24	92																						
TOTAL FOR MAP NO. 8								**0.82**		**92**	*																					
2022CPT.08.06.20761	Randolph	9	SR 1599 MENDENHALL RD EXT.	(FROM: SR 1595 SURRETT DR. TO: NC HWY 62)	9,10	2	2WU	0.61	21	70										3,221	3,221			50	6							
TOTAL FOR MAP NO. 9								**0.61**		**70**										**3,221**	**3,221**			**50**	**6**							
2022CPT.08.06.20761	Randolph	10	SR 2216 OLD CEDAR FALLS RD	(FROM: SR 2345 E. PRESNELL ST. TO SR 2215 HENLEY COUNTRY RD.)	6,7,8	2	2WU	2.15	21																							
TOTAL FOR MAP NO. 10								**2.15**																								
TOTAL FOR PROJ NO. 2022CPT.08.06.20761								**6.11**		**446**	**1**									**3,221**	**3,221**			**50**	**6**							
																				6,442												
GRAND TOTAL								**16.65**		**1,628**	**1**	**40**	**111,380**	**111,380**	**50**	**75**	**8**	**3**	**4**	**30,001**	**28,355**	**50**	**75**	**120**	**6**	**8**	**3**	**4**	**222**	**698**	**42**
													222,760				**15**			**58,356**						**15**				**740**	