PROJECT NO.	SHEET NO.
2022CPT.05.09.20931.1	8

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW	0264000000-E SHOULDER GRADING	1220000000-E INCIDENTAL STONE BASE	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1.25" MILLING	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE	6084000000-E SEED & MULCHING	6117000000-N RESPONSE FOR EROSION CONTROL
										MI	FT	CY	SMI	TON	TON	SY	SY	TONS	TON	TONS	LF	LF	AC	EA
2022CPT.05.09.20931.1	Warren	1	SLICK WILLIAMS RD. (SR 1502)	FROM SR 1332 TO SR 1500	1	2	2WU	NO	NO	1.753	20	42	3.50	10	970		358	1,430	100	180	10	12	0.10	1
TOTAL FOR MAP NO. 1										**1.753**		**42**	**3.50**	**10**	**970**		**358**	**1,430**	**100**	**180**	**10**	**12**	**0.10**	**1**
2022CPT.05.09.20931.1	Warren	2	BALTIMORE RD. (SR 1600)	SR 1625 TO ECL WARRENTON	1	2	2WU	NO	NO	6.024	21	147	12.06	30	3,330	800	778	5,380	370	654	35	42	0.10	1
TOTAL FOR MAP NO. 2										**6.024**		**147**	**12.06**	**30**	**3,330**	**800**	**778**	**5,380**	**370**	**654**	**35**	**42**	**0.10**	**1**
2022CPT.05.09.20931.1	Warren	3	PARKTOWN RD. (SR 1625)	NC 58 TO US 401	1	2	2WU	NO	NO	8.561	22	210	17.20	25	4,745		1,148	7,780	525	940	50	60	0.10	1
TOTAL FOR MAP NO. 3										**8.561**		**210**	**17.20**	**25**	**4,745**		**1,148**	**7,780**	**525**	**940**	**50**	**60**	**0.10**	**1**
2022CPT.05.09.20931.1	Warren	4	PARKTOWN RD. EXT. (SR 1610)	FM PARKTOWN RD. TO BALTIMORE RD.	1	2	2WU	NO	NO	0.12	22	21	0.24		70			100	10	13	10	10		
TOTAL FOR MAP NO. 4										**0.12**		**21**	**0.24**		**70**			**100**	**10**	**13**	**10**	**10**		
TOTAL FOR PROJ NO. 2022CPT.05.09.20931.1										**16.458**		**420**	**33.00**	**65**	**9,115**	**800**	**2,284**	**14,690**	**1,005**	**1,787**	**105**	**124**	**0.30**	**3**
GRAND TOTAL										**16.458**		**420**	**33**	**65**	**9,115**	**800**	**2,284**	**14,690**	**1,005**	**1,787**	**105**	**124**	**0.30**	**3**