


BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETER-MINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.


NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

TEMPORARY DRAINAGE AT END BENT


DRAWN BY: NMW DATE: 3/19
CHECKED BY: RAR DATE: 6/19
DESIGN ENGINEER OF RECORD: TBE DATE: 6/19



PILE SPLICE DETAILS



SECTION THRU CAP



R-2566BA PROJECT NO.___ WATAUGA COUNTY 164+30.00-L-

UPPER PART OF WING

HP 14 X 73 STEEL PILES

PILE EXCAVATION NOT IN SOIL 18.18 L.F

LIN.FT.= 120

TOTAL CLASS A CONCRETE

PILE EXCAVATION IN SOIL

44.7 C.Y.

56.73 L.F

STATION: SHEET 5 OF 10

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION SUBSTRUCTURE

END BENT 2 STAGE I DETAILS

5FBCC2F3A4DC413 9/30/2021 1:43 PM EDT							
CUMENT NOT CONSIDERED FINAL LESS ALL SIGNATURES COMPLETED	REVISIONS						SHEET N
TGS ENGINEERS 804–C N. LAFAYETTE ST	NO.	BY:	DATE:	NO.	BY:	DATE:	S-69
SHELBY, NC 28150	1			3			TOTAL SHEETS
PH (704) 476–0003 CORP. LICENSE NO.: C–0275	2	·		4			79