PROJECT REFERENCE NO. SHEET NO. R-5021 Sig. 46.5

ALTERNATE PHASING ACTIVATION DETAIL

TO RUN ALT. PHASING DURING <u>COORDINATION</u> - SELECT ALL PAGE CHANGES (AS SHOWN BELOW) WITHIN COORDINATION PLAN PROGRAMMING.

TO RUN ALT. PHASING DURING <u>FREE RUN</u> - PROGRAM PAGE CHANGES (SHOWN BELOW) IN SEPARATE TIME OF DAY

EVENTS. IF PAGE 1 IS USED, NO EVENT PROGRAMMING IS NECESSARY

FOR THAT PARTICULAR PAGE.

PHASING	INPUTS PAGE	OVERLAPS PAGE
ACTIVE PAGES REQUIRED TO RUN DEFAULT PHASING	1	1
ACTIVE PAGES REQUIRED TO RUN ALTERNATE PHASING	2	2

NOTE: PAGES NOT SHOWN (i.e. sequence, phase control, etc.) SHOULD REMAIN AS '1', OR AS DEFINED BY TIMING ENGINEER.

IMPORTANT: IF ALT. PHASING IS USED DURING FREE RUN AND COORDINATION, DO NOT OPERATE TIME OF DAY PAGE CHANGE EVENTS CONCURRENTLY WITH COORDINATION PLAN EVENTS IN THE EVENT SCHEDULER. (EX. FREE RUN PAGE CHANGE EVENT SHOULD END BEFORE COORDINATION PLAN EVENT STARTS AND VICE-VERSA).

ALTERNATE PHASING PAGE CHANGE SUMMARY

THE FOLLOWING IS A SUMMARY OF WHAT TAKES PLACE WHEN THESE OVERLAP/INPUT PAGE CHANGES ACTIVATE TO CALL THE "ALTERNATE PHASING":

OVERLAPS PAGE 2: Modifies overlap parent phase for heads 71,72 to run protected

turn only.


INPUTS PAGE 2: Reduces delay time for phase 7

call on loop 7A to 0 seconds.

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 03-1177
DESIGNED: June 2017
SEALED: 10/29/2021
REVISED: N/A

Electrical Detail - Sheet 5 of 5 New Installation

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



NC 211 (Southport-Supply Road) at NC 906 (Midway Road) Ramp

Division 03 Brunswick Co. Southport

PLAN DATE: June 2017 REVIEWED BY: A.D. Klinksiek

PREPARED BY: N.K. Vlanich REVIEWED BY: N.R. Simmons

REVISIONS INIT. DATE

Natasha Simmons 10/29/2021

E6DA88DE3AD445A
SIGNATURE

DATE

SIG. INVENTORY NO. 03-1177

031464

TH CARO

HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997