DMS-1/DMS-2NC 211 (SOUTHPORT-SUPPLY RD) AT STA 156+00

LEGEND COLOR CODE TIA/EIA 598-C X = NEW FUSION SPLICE INDIVIDUAL FIBER • = EXISTING FUSION SPLICE C = CAP AND SEALEXPRESS ENTIRE BUFFER TUBE THROUGH WITHOUT CUTTING BUFFER SPLICE = SPLICE ALL FIBERS IN BUFFER (12) AQUA TUBE COLOR TO COLOR

PROJECT REFERENCE NO.

R-5021


NEW **DROP** CABLE TO DMS-1/ **NEW SPLICE ENCLOSURE** DMS-2 NEW SPLICE TRAY CAP AND SEAL STRANDS 5-12 EXPRESS FIBERS 1 - 8 AND 11 - 12 STRAIGHT THROUGH NEW NEW BLUE BUFFER TUBE BLUE BUFFER TUBE **EXPRESS** FROM SPLICE ENCLOSURE BUFFER TUBE **BUFFER TUBE** FROM SPLICE ENCLOSURE FOR 03-0977 GREEN BUFFER TUBE NC 211 (SOUTHPORT-SUPPLY RD) EXPRESS CCTV_1 **|** BUFFER TUBE BUFFER TUBE ST. JAMES DR **EXPRESS** 48 FIBERS IN 4 BUFFER TUBES 48 FIBERS IN 4 BUFFER TUBES

NOTES:

- 1. UNUSED FIBERS LEFT COILED AND STORED IN SPLICE TRAY.
- 2. UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPLICE TRAY.
- 3. INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"
 - (1) SPLICE
- (2) DATE
- (3) COMPANY NAME
- (4) NAME OF INDIVIDUAL PERFORMING THE SPLICING


PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY, TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1–4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.

4. SIX (6) WEEKS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM, CONTACT THE DIVISION 3 DEPUTY TRAFFIC ENGINEER, STONEWALL (STONEY) MATHIS, AT 910–341–2200 TO ARRANGE FOR THE DIVISION TO PROGRAM THE NEW FIELD ETHERNET SWITCHES WITH THE NECESSARY NETWORK CONFIGURATION DATA, INCLUDING BUT NOT LIMITED TO THE PROJECT IP ADDRESS, DEFAULT GATEWAY, SUBNET MASK, AND VLAN ID INFORMATION. NOTIFY THE DEPUTY TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND FUNCTIONAL.



NC 211 (SOUTHPORT-SUPPLY RD / HOWE ST) SPLICE DETAIL Brunswick Co. Division 3 Southport

NONE



Natasha Simmons 10/29/202 CADD Filename: R5021 scp-46.dgn

CONTROLLER CABINET DMS-1

DROP CABLE TO DMS-1/DMS-2 FROM SPLICE **ENCLOSURE**

1 2 3 4 5 6

999999

DOCUMENT NOT CONSIDERED FINAL

UNLESS ALL SIGNATURES COMPLETED

FOR FUTURE

> CAP AND SEAL STRANDS 1-12

> > 031464