PROJ. REFERENCE NO.	SHEET NO.
R-5021	X-1C

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station LREV, LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)	Station LREV, LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)	Station LREV, LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)	Station LREV, LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
250+50.00	0	517	0	275+00.00	0	523	0	299+50.00	0	615	0	324+00.00	149	115	0
251+00.00	0	541	0	275+50.00	0	528	0	300+00.00	0	629	0	324+50.00	76	167	0
251+50.00	0	575	0	276+00.00	0	635	0	300+50.00	0	635	0	325+00.00	8	122	0
252+00.00	0	546	0	276+50.00	0	741	0	301+00.00	0	655	0	325+50.00	8	20	0
252+50.00	0	566	0	277+00.00	0	754	0	301+50.00	0	684	91	326+00.00	71	65	0
253+00.00	0	661	0	277+50.00	0	761	0	302+00.00	0	684	267	326+50.00	133	114	0
253+50.00	0	680	0	278+00.00	0	785	12	302+50.00	0	678	291	327+00.00	130	111	0
254+00.00	0	783	96	278+50.00	0	823	56	303+00.00	0	674	178	327+50.00	123	105	0
254+50.00	0	915	199	279+00.00	0	822	44	303+50.00	0	658	105	328+00.00	119	94	0
255+00.00	0	955	207	279+50.00	0	810	0	304+00.00	0	636	57	328+50.00	120	82	0
255+50.00	0	1108	235	280+00.00	0	804	0	304+50.00	0	635	22	329+00.00	119	72	0
256+00.00	0	1500	376	280+50.00	0	786	0	305+00.00	58	632	19	329+50.00	118	66	0
256+50.00	0	1505	391	281+00.00	0	906	105	305+50.00	58	554	19	330+00.00	76	52	0
257+00.00	0	1003	146	281+50.00	0	1105	308	306+00.00	0	362	95	330+50.00	152	19	0
257+50.00	0	374	0	282+00.00	0	1235	457	306+50.00	47	483	108	331+00.00	140	13	0
				282+50.00	0	1257	457	307+00.00	111	742	0	331+50.00	8	33	0
Station LREV, LT	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**	**UnderCut (cu. yd.)**	283+00.00	0	1184	340	307+50.00	125	719	0	332+00.00	20	23	0
				283+50.00	0	1098	246	308+00.00	129	673	0	332+50.00	36	2	0
				284+00.00	0	1035	194	308+50.00	144	688	0	333+00.00	36	0	0
258+00.00	0	359	0	284+50.00	0	1024	206	309+00.00	172	724	0	333+50.00	38	0	0
258+50.00	0	720	0	285+00.00	0	1044	241	309+50.00	162	766	0	334+00.00	30	0	0
259+00.00	0	737	0	285+50.00	0	1049	250	310+00.00	177	745	0	334+50.00	15	1	0
259+50.00	0	861	113	286+00.00	0	964	189	310+50.00	228	647	1	335+00.00	12	2	0
260+00.00	0	996	245	286+50.00	0	933	163	311+00.00	197	574	4	335+50.00	33	2	0
260+50.00	0	1027	273	287+00.00	0	961	224	311+50.00	121	634	0	336+00.00	34	11	0
261+00.00	0	1033	295	287+50.00	0	469	115	312+00.00	70	709	0	336+50.00	13	16	0
261+50.00	0	1026	289					312+50.00	54	693	0	337+00.00	12	5	0
262+00.00	0	991	252	**Station LREV, LT**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**	**UnderCut (cu. yd.)**	313+00.00	44	643	0	337+50.00	12	2	0
262+50.00	0	912	198					313+50.00	40	540	0	338+00.00	13	6	0
263+00.00	0	768	80					314+00.00	49	478	0	338+50.00	14	4	0
263+50.00	0	657	0	288+00.00	0	343	0	314+50.00	57	462	0	339+00.00	12	16	0
264+00.00	0	640	0	288+50.00	0	702	95	315+00.00	65	443	0	339+50.00	54	16	0
264+50.00	0	640	0	289+00.00	0	710	211	315+50.00	94	438	0	340+00.00	96	0	0
265+00.00	0	669	0	289+50.00	0	713	228	316+00.00	108	478	101	340+50.00	84	0	0
265+50.00	0	662	0	290+00.00	0	736	201	316+50.00	113	620	0	341+00.00	70	0	0
266+00.00	0	597	0	290+50.00	0	773	155	317+00.00	150	525	0	341+50.00	37	9	0
266+50.00	0	612	0	291+00.00	0	773	67	317+50.00	86	161	0	342+00.00	8	23	0
267+00.00	0	626	0	291+50.00	0	734	0					342+50.00	9	21	0
267+50.00	0	575	0	292+00.00	0	716	0	**Station LREV, LT**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**	**UnderCut (cu. yd.)**	343+00.00	45	8	0
268+00.00	0	569	0	292+50.00	0	708	0					343+50.00	85	8	0
268+50.00	0	558	0	293+00.00	0	680	0					344+00.00	86	22	0
269+00.00	0	507	0	293+50.00	0	663	0	318+00.00	0	86	0	344+50.00	61	25	0
269+50.00	0	450	0	294+00.00	0	667	0	318+50.00	1	101	0	345+00.00	29	20	0
270+00.00	0	499	0	294+50.00	0	651	0	319+00.00	5	111	0	345+50.00	20	19	0
270+50.00	0	567	0	295+00.00	0	627	0	319+50.00	147	169	0	346+00.00	22	22	0
271+00.00	0	662	0	295+50.00	0	612	0	320+00.00	293	157	0	346+50.00	34	30	0
271+50.00	0	842	10	296+00.00	0	600	0	320+50.00	217	91	0	347+00.00	44	17	0
272+00.00	0	802	48	296+50.00	0	594	0	321+00.00	84	103	0	347+50.00	20	0	0
272+50.00	0	770	200	297+00.00	0	578	0	321+50.00	29	195	0				
273+00.00	0	871	343	297+50.00	0	561	0	322+00.00	25	116	0				
273+50.00	0	835	291	298+00.00	0	563	0	322+50.00	31	20	0				
274+00.00	0	717	172	298+50.00	0	577	0	323+00.00	159	5	0				
274+50.00	0	593	62	299+00.00	0	598	0	323+50.00	218	57	0				