PROJ. REFERENCE NO.	SHEET NO.
R-5021	X-1E

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
69+00.00	0	785	0
69+50.00	0	757	0
70+00.00	0	706	0
70+50.00	0	586	0
71+00.00	0	428	0
71+50.00	0	513	0
72+00.00	0	546	0
72+50.00	0	517	0
73+00.00	0	603	0
73+50.00	0	591	0
74+00.00	0	588	0
74+50.00	0	574	0
75+00.00	0	592	0
75+50.00	0	505	0
76+00.00	24	411	0
76+50.00	24	441	0
77+00.00	0	442	0
77+50.00	0	482	0

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
78+00.00	0	266	0
78+50.00	8	144	0
79+00.00	5	197	0
79+50.00	0	259	0
80+00.00	0	266	0
80+50.00	7	236	0
81+00.00	26	199	0
81+50.00	75	177	0
82+00.00	87	172	0
82+50.00	67	178	0
83+00.00	78	165	0
83+50.00	79	163	0
84+00.00	71	151	0
84+50.00	87	117	0
85+00.00	104	94	0
85+50.00	100	77	0
86+00.00	97	67	0
86+50.00	117	61	0
87+00.00	102	61	0
87+50.00	72	62	0
88+00.00	76	60	0
88+50.00	81	60	0
89+00.00	89	69	0
89+50.00	100	73	0
90+00.00	106	69	0
90+50.00	98	51	0
91+00.00	80	38	0
91+50.00	64	43	0
92+00.00	34	40	0
92+50.00	22	40	0
93+00.00	35	42	0

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
93+50.00	43	39	0
94+00.00	49	61	0
94+50.00	66	81	0
95+00.00	87	82	0
95+50.00	99	87	0
96+00.00	97	77	0
96+50.00	83	74	0
97+00.00	64	98	0
97+50.00	52	135	0
98+00.00	66	165	0
98+50.00	85	206	0
99+00.00	98	259	0
99+50.00	84	298	0
100+00.00	60	360	0
100+50.00	49	453	0
101+00.00	52	480	0
101+50.00	39	490	0
102+00.00	19	533	0
102+50.00	19	536	0
103+00.00	14	552	0
103+50.00	5	460	0
104+00.00	26	367	0
104+50.00	38	406	0
105+00.00	30	427	0
105+50.00	89	404	0
106+00.00	70	416	0
106+50.00	0	455	0
107+00.00	0	479	0
107+50.00	0	250	0

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
108+00.00	0	278	0
108+50.00	0	534	0
109+00.00	0	508	0
109+50.00	0	533	0
110+00.00	0	559	0
110+50.00	0	556	0
111+00.00	0	563	0
111+50.00	0	573	0
112+00.00	0	580	0
112+50.00	0	580	0
113+00.00	0	579	0
113+50.00	0	571	0
114+00.00	0	557	0
114+50.00	0	548	0
115+00.00	0	533	0
115+50.00	0	524	0
116+00.00	0	535	1
116+50.00	0	557	1
117+00.00	0	600	15
117+50.00	0	613	28

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
118+00.00	0	547	14
118+50.00	0	491	5
119+00.00	0	479	9
119+50.00	0	514	13
120+00.00	0	537	17
120+50.00	0	475	8
121+00.00	0	411	0
121+50.00	0	410	0
122+00.00	0	447	0
122+50.00	0	468	0
123+00.00	0	460	0
123+50.00	0	815	0
124+00.00	0	589	0
125+50.00	0	654	0
126+00.00	0	654	0
126+50.00	0	294	0
127+00.00	0	600	0
127+50.00	0	624	0
128+00.00	0	647	0
128+50.00	0	663	0
129+00.00	0	672	0
129+50.00	0	699	0
130+00.00	0	743	0
130+50.00	0	774	0
131+00.00	0	817	0
131+50.00	0	864	11
132+00.00	0	911	21
132+50.00	0	960	20
133+00.00	0	970	21
133+50.00	0	951	21
134+00.00	0	916	21
134+50.00	0	860	17
135+00.00	0	808	15
135+50.00	0	773	23
136+00.00	0	744	15
136+50.00	0	717	11
137+00.00	0	677	21
137+50.00	0	326	10

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
138+00.00	0	345	23
138+50.00	0	709	49
139+00.00	0	720	51
139+50.00	0	678	42
140+00.00	0	602	17
140+50.00	0	543	0
141+00.00	0	498	0
141+50.00	0	443	0
142+00.00	0	401	0
142+50.00	0	379	0
143+00.00	0	354	0

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
143+50.00	0	321	0
144+00.00	0	281	0
144+50.00	0	221	0
145+00.00	0	163	0
145+50.00	0	95	0
146+00.00	53	45	0
146+50.00	120	37	0
147+00.00	134	48	0
147+50.00	137	71	0
148+00.00	130	86	0
148+50.00	118	149	0
149+00.00	115	256	0
149+50.00	116	347	0
150+00.00	57	401	0
150+50.00	40	454	0
151+00.00	84	517	0
151+50.00	86	450	0
152+00.00	43	284	0
152+50.00	0	218	0
153+00.00	0	357	0
153+50.00	0	450	0
154+00.00	0	495	0
154+50.00	0	568	0
155+00.00	0	557	0
155+50.00	0	544	0
156+00.00	0	516	0
156+50.00	0	492	0
157+00.00	0	484	0
157+50.00	0	492	0
158+00.00	0	497	0
158+50.00	0	505	0
159+00.00	0	521	0
159+50.00	0	539	0
160+00.00	0	558	0
160+50.00	0	573	0
161+00.00	0	581	0
161+50.00	0	596	0
162+00.00	0	612	0
162+50.00	0	623	0
163+00.00	0	631	0
163+50.00	0	635	0
164+00.00	0	636	0
164+50.00	0	638	3
165+00.00	0	642	6
165+50.00	0	657	8
166+00.00	0	662	8
166+50.00	0	656	5
167+00.00	0	656	9
167+50.00	0	328	6