PROJ. REFERENCE NO.	SHEET NO.
R-5021	X-1H

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
371+00.00	0	121	0
371+50.00	0	252	6
372+00.00	0	261	10
372+50.00	0	241	3
373+00.00	0	199	0
373+50.00	6	173	0
374+00.00	28	156	0
374+50.00	59	116	0
375+00.00	81	96	0
375+50.00	88	100	0
376+00.00	119	71	0
376+50.00	162	26	0
377+00.00	192	14	0
377+50.00	230	9	0
378+00.00	252	4	0
378+50.00	200	16	0
379+00.00	71	31	0
379+50.00	0	43	0
380+00.00	27	74	0
380+50.00	42	109	0
381+00.00	31	85	0
381+50.00	38	45	0
382+00.00	37	38	0
382+50.00	23	142	0
383+00.00	34	215	0
383+50.00	37	205	0
384+00.00	19	229	0
384+50.00	18	226	0
385+00.00	18	188	0
385+50.00	27	126	0
386+00.00	34	92	0
386+50.00	37	98	0
387+00.00	45	107	0
387+50.00	61	99	0
388+00.00	33	83	0
388+50.00	0	43	0

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
392+50.00	92	33	0
393+00.00	189	64	0
393+50.00	133	68	0
394+00.00	71	60	0
394+50.00	76	42	0
395+00.00	76	63	0
395+50.00	98	69	0
396+00.00	92	61	0
396+50.00	64	130	0
397+00.00	63	194	0
397+50.00	54	138	0
398+00.00	28	62	0
398+50.00	6	53	0

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
399+00.00	7	56	0
399+50.00	5	80	0
400+00.00	4	99	0
400+50.00	16	100	0
401+00.00	25	109	0
401+50.00	31	117	0
402+00.00	32	123	0
402+50.00	26	127	0
403+00.00	35	123	0
403+50.00	44	87	0
404+00.00	29	48	0
404+50.00	16	19	0
405+00.00	17	8	0
405+50.00	12	8	0
406+00.00	23	0	0
406+50.00	35	0	0
407+00.00	31	8	0
407+50.00	26	13	0
408+00.00	28	14	0
408+50.00	32	70	0
409+00.00	33	76	0
409+50.00	56	64	0
410+00.00	57	94	0
410+50.00	32	96	0
411+00.00	19	118	10
411+50.00	10	140	100
412+00.00	14	91	138
412+50.00	16	108	103
413+00.00	9	140	0
413+50.00	5	143	0
414+00.00	11	193	0
414+50.00	11	199	0
415+00.00	9	184	0
415+50.00	18	164	0
416+00.00	18	142	0
416+50.00	9	134	0
417+00.00	0	120	0
417+50.00	0	98	0
418+00.00	1	73	0
418+50.00	3	40	0
419+00.00	0	85	0
419+50.00	0	144	0
420+00.00	0	110	0
420+50.00	13	46	0
421+00.00	17	82	0
421+50.00	9	140	0
422+00.00	5	70	0
422+50.00	1	1	0
423+00.00	14	9	0
423+50.00	35	11	0

Station LREV, RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
424+00.00	47	4	0
424+50.00	33	0	0
425+00.00	8	0	0
425+50.00	3	33	0
426+00.00	7	40	0
426+50.00	8	19	0
427+00.00	9	21	0
427+50.00	10	12	0
428+00.00	10	10	0
428+50.00	9	12	0
429+00.00	12	23	0
429+50.00	15	21	0
430+00.00	23	3	0
430+50.00	15	0	0

Station YREV	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
8+00.00	0	0	0
8+50.00	4	3	0
9+00.00	11	4	0
9+50.00	31	3	0
10+00.00	221	7	0
10+50.00	296	21	0
11+00.00	221	34	0
11+50.00	249	45	0
12+00.00	225	46	0
12+50.00	180	76	0
13+00.00	148	141	0
13+50.00	129	196	0
14+00.00	115	242	0
14+50.00	136	265	0
15+00.00	187	255	0
15+50.00	217	259	0
16+00.00	244	262	0
16+50.00	294	223	0
17+00.00	336	257	71
17+50.00	346	301	126
18+00.00	305	233	137
18+50.00	265	207	171
19+00.00	245	234	181
19+50.00	208	282	190
20+00.00	185	345	196
20+50.00	186	410	171
21+00.00	187	439	0
21+50.00	191	474	0
22+00.00	98	558	8
22+50.00	0	540	10
23+00.00	98	768	0
23+50.00	191	1185	0
24+00.00	165	1461	0
24+50.00	124	1871	0
25+00.00	52	2392	0

Station YREV	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
25+00.00	0	2660	0
26+00.00	0	3209	0
26+50.00	23	4178	0
27+00.00	104	5107	0
27+50.00	81	6081	0
28+00.00	0	7062	0
28+50.00	0	8049	0
29+00.00	0	8896	0
29+50.00	0	9430	0
30+00.00	1	7291	0
30+50.00	2	4983	0

Station YREV	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
32+50.00	0	0	0
33+00.00	1	5212	0
33+50.00	1	6269	0
34+00.00	0	7784	0
34+50.00	0	7709	0
35+00.00	0	6592	0
35+50.00	10	5409	0
36+00.00	42	4346	0
36+50.00	235	3473	0
37+00.00	480	2810	0
37+50.00	612	2386	0
38+00.00	763	1980	0
38+50.00	913	1660	0
39+00.00	1013	1493	0
39+50.00	1072	1287	0
40+00.00	1079	1143	0
40+50.00	1092	1034	0
41+00.00	1040	892	0
41+50.00	980	756	162
42+00.00	931	636	300
42+50.00	865	545	242
43+00.00	793	453	252
43+50.00	688	380	0
44+00.00	602	339	0
44+50.00	510	298	0
45+00.00	429	266	0
45+50.00	336	232	0
46+00.00	192	183	0
46+50.00	80	155	0
47+00.00	85	105	0
47+50.00	88	69	0
48+00.00	42	222	0
48+50.00	25	373	0
49+00.00	24	409	0
49+50.00	21	420	0
50+00.00	14	392	0
50+50.00	14	335	0
51+00.00	15	262	0