

# Estimates Summary for TIP Project # B-5642

NCTProject #:  
FA-Project#:  
WBS Number 45597.1.1  
County: Brunswick

Date of Estimate: 1/7/2020  
Prepared By: Jocelyn Adorno, EI

Description: Replace Bridge No. 65 Over Batarora Branch on NC 87 (Maco Road)

---

## STATIONARY WORK ZONE SIGNS

ADV TURN ARROW (M5-1)	1 signs	2 SF
ADV TURN ARROW 45 (M5-2)	3 signs	7 SF
DETOUR (M4-8)	17 signs	34 SF
DETOUR (W20-2)	2 signs	32 SF
END DETOUR (M4-8a)	2 signs	6 SF
NC ROUTE MARKER (M1-5)	19 signs	76 SF
NEXT LT (SP-4)	4 signs	14 SF
NEXT RT (SP-4)	4 signs	14 SF
NORTH (M3-1)	9 signs	18 SF
RD CLSD (W20-3)	14 signs	224 SF
RD CLSD 1000 FT (W20-3)	4 signs	64 SF
RD CLSD 500 FT(W20-3)	4 signs	64 SF
RT TURN 45 ARROW (M6-2)	3 signs	7 SF
RT TURN ARROW (M6-1)	3 signs	7 SF
SOUTH (M3-3)	8 signs	16 SF
STRAIGHT ARROW (M6-3)	7 signs	15 SF

---

**TOTAL STATIONARY WORK ZONE SIGNS 600 SF**

---

# Estimates Summary for TIP Project # B-5642

NCPProject #:  
FA-Project#:  
WBS Number 45597.1.1  
County: Brunswick

Date of Estimate: 1/7/2020  
Prepared By: Jocelyn Adorno, EI

Description: Replace Bridge No. 65 Over Batarora Branch on NC 87 (Maco Road)

<b>BARRICADE MOUNTED WORK ZONE SIGNS</b>		
DETOUR ARROW (M4-10R/L)	4 signs	24 SF
RD CLSD (R11-2)	2 signs	20 SF
RD CLSD 2 MI, LOC TRAFFIC ONLY (R11-3)	2 signs	25 SF
RD CLSD 3 MI, LOC TRAFFIC ONLY (R11-3)	4 signs	50 SF
RD CLSD 7 MI, LOC TRAFFIC ONLY (R11-3)	2 signs	25 SF
<b>TOTAL BARRICADE MOUNTED WORK ZONE SIGNS</b>		<b>144 SF</b>
<b>BARRICADES (TYPE III)</b>		
12 Barricades		96 LF
<b>THERMOPLASTIC (4", 90 MILS)</b>		
T13 (4") YELLOW DOUBLE CENTER From Sta.14+00 -L- to Sta. 22+50 -L-		1700 LF
T1 (4") WHITE EDGELINE From Sta.14+00 (LT) -L- to Sta. 22+50 (LT) -L-		850 LF
T1 (4") WHITE EDGELINE From Sta.14+00 (RT) -L- to Sta. 22+50 (RT) -L-		850 LF
<b>TOTAL (4", 90 MILS)</b>		<b>3400 LF</b>
<b>SNOWPLOWABLE RAISED PAVEMENT MARKERS</b>		
ME - YELLOW & YELLOW From Sta.14+00 -L- to Sta.22+50 -L-, (@ 80 FT spacing, w/4 extra)		15 EA