



|                  |   |           |              |
|------------------|---|-----------|--------------|
| STATE            | PROJECT NO.   | SHEET NO. | TOTAL SHEETS |
| N.C.             | 2022CPT.10.09.10131<br>2022CPT.10.09.20131<br>2022CPT.10.09.20132 | 18        |              |
| F.A. PROJECT NO. |   |           |              |


| PAVEMENT SCHEDULE |  |
|-------------------|--|
| C1                | PROP. APPROX. 1.25" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 138 LBS. PER SQ. YDS.                 |
| C2                | PROP. APPROX. 1.50" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YDS.                 |
| C3                | PROP. APPROX. 2.00" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 220 LBS. PER SQ. YDS.                 |
| E1                | PROP. APPROX. 8.00" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 456 LBS. PER SY'S IN EACH OF TWO LAYERS |
| F1                | ASPHALT SURFACE TREATMENT, DOUBLE SEAL   |
| T1                | SHOULDER RECONSTRUCTION  |
| V1                | MILLING OF EXISTING PAVEMENT, 1.25"  |
| V2                | MILLING OF EXISTING PAVEMENT, 1.50"  |
| V3                | PROFILE MILLING OF EXISTING ASPHALT, 0"-1.25" (8' WIDTH)   |
| V4                | PROFILE MILLING OF EXISTING ASPHALT, 0"-1.50" (8' WIDTH)   |
| Z                 | FULL DEPTH RECLAMATION   |



- MAP 1 - NC 3 (CONCORD LAKE ROAD)
- MAP 2 - SR 1138 (HICKORY RIDGE ROAD)
- MAP 3 - SR 1139 (ROCKY RIVER ROAD)
- MAP 4 - SR 1139 (ROCKY RIVER ROAD)
- MAP 10 - SR 2202 (CHINA GROVE ROAD)
- MAP 22 - SR 2411 (IRISH POTATO ROAD)
- MAP 35 - SR 1155 (ZION CHURCH ROAD) - OVER PIPE CULVERT ONLY



- MAP 1 - NC 3 (CONCORD LAKE ROAD)
- MAP 2 - SR 1138 (HICKORY RIDGE ROAD)
- MAP 3 - SR 1139 (ROCKY RIVER ROAD)



- MAP 1 - NC 3 (CONCORD LAKE ROAD)
- MAP 2 - SR 1138 (HICKORY RIDGE ROAD)

NOTES:  
1. LEVELING COURSE TO BE PLACED AS DIRECTED BY THE ENGINEER

CABARRUS COUNTY  
RESURFACING SPRING 2022

|           |       |  |           |
|-----------|-------|--|-----------|
| SCALE     | NA    |  | REVISIONS |
| DATE      | 10/21 |  |           |
| DWG. BY   | JWH   |  |           |
| DESIGN BY | JWH   |  |           |
| APPROVED  |       |  |           |