

DocuSign Envelope ID: 32153407-4015-4EC9-8D43-CA1E8DD6E7EF

PROJ. REFERENCE NO. SHEET NO. U-2579AB TMP-2B HDR Engineering, Inc. of the Carolinas 555 Fayetteville St, Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116



## NOTES:

- 1. RELOCATE MEDIAN ACCESS POINTS, AS NEEDED, TO COMPLETE MEDIAN CONSTRUCTION AS APPROVED BY THE ENGINEER.
- 2. PLACE YELLOW DIAGONAL PAVEMENT MARKINGS THROUGHOUT ACCESS LANE. SPACING FOR UPSTREAM HALF OF LANE SHALL BE 100', AND 55' FOR DOWNSTREAM HALF OF LANE.
- 3. WHEN NOT IN USE FOR MORE THAN 72 HOURS, DRUMS SHALL BE USED ALONG THE SHOULDER TO CLOSE THE PARALLEL ACCELERATION/DECELERATION AREA.
- 4. ALL WORK VEHICLES ATTEMPTING TO RE-ENTER AN OPEN TRAVEL LANE SHALL PASS THROUGH THE DETECTION AREA. WORK VEHICLES SHALL NOT LEAVE THE WORK AREA USING THE INGRESS POINT AT ANY TIME.
- 5. NO MATERIALS OR EQUIPMENT SHALL BE STORED IN THE CRASH AREA **DURING NON-WORKING HOURS.**
- 6. REFER TO TMP-2C THRU TMP-2D FOR SPECIAL SIGN DESIGNS.



TYPICAL MEDIAN ACCESS DETAIL

**VEHICLE** 

**SPECIAL** 

48" X 48"

TRUCKS

**ENTERING/** 

EXITING

DO NOT FOLLOW

**SPECIAL** 

36" X 30"

ACCESS

1/2 MILE

LEFT

**INSTALL ON** 

BOTH SHOULDERS

TRUCKS

**ENTERING** 

HIGHWAY

FLASHING

**SPECIAL** 

48" X 48"

**SPECIAL** 

36" X 30"

**INSTALL ON** 

BOTH SHOULDERS

**INSTALL ON** 

LEFT SHOULDER ONLY

W14-12

48" X 48"

W16-13

30" X 24"