DocuSign Envelope ID: 681F20C9-7C9A-4373-8C09-5EBEC9A704FC

ON THIS PLAN SHEET, THE ESTIMATED QUANTITY OF SANITARY SEWER CLEANOUTS IS 1 EACH, AND THE ESTIMATED QUANTITY OF SEWER SERVICE LINE IS 30 L.F. THE ACTUAL QUANTITIES WILL VARY BASED ON FIELD CONDITIONS.

PARCELS WHERE SEWER SERVICES MAY NEED RELOCATION:
PARCEL 74 – 221 OAK GROVE CHURCH ROAD (SHORT SERVICE INTO MANHOLE)

PROP. -2 - RELOCATE WM'S, 16 LF - WATER SERVICE LINE

PROP. 1 - FIRE HYDRANT, 1 - 6" VALVE, 7 L.F. FIRE HYD. LEG (SET F.H. 1' INSIDE R/W)

PROP. 1 - RELOCATE WATER METER, 8 L.F. - WATER SERVICE LINE

THE ESTIMATED QUANTITY OF D.I. WATER PIPE FITTINGS ON THIS PLAN SHEET IS 720 POUNDS. THE ACTUAL QUANTITY AND TYPE OF FITTINGS WILL VARY BASED ON FIELD CONDITIONS.

A TOTAL OF 34 WATER METERS ARE SHOWN TO BE REMOVED ON THIS SHEET.

A TOTAL OF 4 FIRE HYDRANTS ARE SHOWN TO BE REMOVED ON THIS SHEET.

PROP. - 767 LF 6" WATER LINE

PROP. 1 - FIRE HYDRANT, 1 - 6" VALVE, 7 LF FIRE HYD. LEG

PROP. 2 - RELOCATE WATER METERS, 10 L.F. - WATER SERVICE LINE

END CONSTRUCTION -SR1- Sta. 29+00.00

(NOTE: THERE IS NO PROP. SEWER LINE PS300.)

PROP. MH 12 (4' DIA.) STA. 0+00.00, LINE PS200 -L- STA. 758+57.30, 366.8' LT.

PROP. MH 12A (5' DIA.) STA. 1+25.80, LINE PS200 -L- STA. 757+34.96, 337.5' LT.

PROP. MH 13 (5' DIA.) STA. 2+36.02, LINE PS200 -L- STA. 757+60.67, 230.3' LT.

PROP. - 15 LF 6" WATER LINE

PROP. - 126 LF 8" SAN. GRAV. SEWER

PROP. - 110 LF 8" SAN. GRAV. SEWER

PROP. - 75 L.F. OF 8" SAN. GRAV. SEWER

PROP. MH 14 (4' DIA.) STA. 3+11.10, LINE PS200 -L- STA. 757+45.60, 156.7' LT.

1 - ABANDON UTILITY MH

ABANDON 91 LF 8" UTIL. PIPE

1 - ABANDON UTILITY MH

ABANDON 1 UTIL. MH, ABANDON 227 L.F. 8" UTILITY PIPE

ABANDON 2 UTILITY MH'S, ABANDON 297 LF 8" UTIL. PIPE

ABANDON 2 UTILITY MH'S, ABANDON 409 LF, 8" UTIL. PIPE

ABANDON 269 LF 8" UTIL. PIPE

PROP. - 369 L.F. OF 8" SAN. GRAV. SEWER, 260 L.F. OF 18" ENCASEMENT (STEEL, MIN. W.T.=0.250")

ABANDON 1 UTILITY MH, ABANDON 118 LF, 8" UTIL. PIPE

ABANDON 1 UTILITY MH, ABANDON 65 LF, 8" UTIL. PIPE

PROP. 1 - FIRE HYD., 1 - 6" VALVE, 17 LF F.H. LEG

PROP. - 116 L.F. 8" SAN. GRAV. SEW.

PROP. - 227 L.F. 8" SAN. GRAV. SEW.

PROP. MH 16 (4' DIA.) STA. 9+07.37, LINE PS200 -L- STA. 754+42.01, 208.7' RT.

PROP. - 227 L.F. 8" SAN. GRAV. SEW.

1 - REMOVE UTILITY MH

NO CLAIM

PROP. MH 17 (4' DIA.) STA. 11+34.34, LINE PS200 -L- STA. 752+06.96, 202.1' RT.

REMOVE 1 UTIL. MH & INSTALL PROP. MH 15 (6' DIA.) STA. 6+80.37, LINE PS200 -L- STA. 756+71.48, 205.0' RT.

PROP. - 301 L.F. 8" SAN. GRAV. SEW.

PROP. MH 18 (4' DIA.) STA. 12+50.28, LINE PS200 -L- STA. 750+86.79, 201.1' RT.

PROP. 1 - FIRE HYD., 1 - 6" VALVE, 17 LF F.H. LEG

PROP. - 15 LF 6" WATER LINE, 1 - 6" VALVE

MATCHLINE SHEET UC-6 -L- STA. 746+50.00

MATCHLINE SHEET UC-8 -L- STA. 759+50.00

REVISIONS

PROJECT REFERENCE NO.	SHEET NO.
U-2579AB	UC-7

DESIGNED BY: DMP
DRAWN BY: DMP
CHECKED BY: DMP
APPROVED BY:
REVISED:

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
UTILITIES ENGINEERING SEC.
PHONE:(919)707-6690
FAX:(919)250-4151

NORTH CAROLINA PROFESSIONAL SEAL 26457 ENGINEER ANDREW P. LARRICK
7/13/2021

UTILITY CONSTRUCTION PLANS ONLY

UTILITY CONSTRUCTION

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

UTILITY CONSTRUCTION PLANS PREPARED BY:
DAVIS • MARTIN • POWELL ENGINEERS & SURVEYORS
6415 OLD PLANK RD. HIGH POINT, NC 27265
PHONE: (336)886-4821 FAX: (336)886-4458
WWW.DMP-INC.COM LICENSE: F-0245