PROJ. REFERENCE NO.	SHEET NO.
U-2579AB	X-0G

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station	Uncl. Exc.	Embt
Y15XOVR1	(cu. yd.)	(cu. yd.)
13+50.00	15	16
14+00.00	14	28
14+50.00	14	31
15+00.00	19	29
15+50.00	18	28
16+00.00	13	26
16+50.00	15	25
17+00.00	18	29
17+50.00	18	32
18+00.00	17	31
18+50.00	16	28
19+00.00	16	22
19+50.00	16	15
20+00.00	16	7
20+50.00	17	1
21+00.00	16	0
21+50.00	15	0
21+89.81	11	0

Station	Uncl. Exc.	Embt
Y15XOVR2	(cu. yd.)	(cu. yd.)
10+00.00	0	0
10+50.00	15	0
11+00.00	16	0
11+50.00	15	1
12+00.00	14	3
12+50.00	15	11
13+00.00	14	16
13+50.00	13	20
14+00.00	13	32
14+50.00	14	40
15+00.00	14	43
15+50.00	14	41
16+00.00	13	36
16+50.00	12	35
17+00.00	15	37
17+50.00	16	38
18+00.00	15	36
18+50.00	15	28
19+00.00	16	19
19+50.00	16	13
20+00.00	15	10
20+50.00	15	5
21+00.00	15	1
21+50.00	15	0
21+89.81	12	0

Station	Uncl. Exc.	Embt
Y16	(cu. yd.)	(cu. yd.)
16+00.00	0	0
16+50.00	38	16
17+00.00	38	13
17+50.00	40	37
18+00.00	36	79
18+50.00	21	135
19+00.00	11	198
19+50.00	4	241
20+00.00	374	319
20+50.00	376	388
20+73.53	2	188
25+49.53	0	0
25+50.00	0	3
26+00.00	51	305
26+50.00	51	254
27+00.00	0	220
27+50.00	3	217
28+00.00	3	157
28+50.00	0	104
29+00.00	5	55
29+50.00	25	21

Station	Uncl. Exc.	Embt
Y16DET	(cu. yd.)	(cu. yd.)
13+00.00	0	0
13+50.00	4	12
14+00.00	4	16
14+50.00	4	36
15+00.00	6	92
15+50.00	4	177
16+00.00	0	198
16+50.00	0	171
17+00.00	0	137
17+50.00	5	69
18+00.00	24	19
18+50.00	71	3
19+00.00	126	0
19+50.00	120	4
20+00.00	49	48
20+50.00	2	212
21+00.00	0	260
21+50.00	0	182
22+00.00	0	185
22+50.00	0	235
23+00.00	0	239
23+50.00	0	158
24+00.00	0	98
24+50.00	0	90
25+00.00	0	132
25+50.00	0	195

Station	Uncl. Exc.	Embt
Y16DET	(cu. yd.)	(cu. yd.)
26+00.00	0	373
26+50.00	0	513
27+00.00	0	624
27+50.00	0	696
28+00.00	0	787
28+50.00	0	881
29+00.00	0	981
29+50.00	0	1019
30+00.00	0	835
30+50.00	0	590
31+00.00	0	276
31+50.00	3	71
32+00.00	36	8
32+50.00	57	0
33+00.00	42	0
33+50.00	29	0
33+76.97	9	0

Station	Uncl. Exc.	Embt
Y16B	(cu. yd.)	(cu. yd.)
12+00.00	0	0
12+50.00	25	0
13+00.00	52	0
13+50.00	55	0
14+00.00	41	10

Station	Uncl. Exc.	Embt
Y16B DET	(cu. yd.)	(cu. yd.)
14+25.00	0	0
14+50.00	22	76
14+75.00	0	188
15+00.00	0	290

Station	Uncl. Exc.	Embt
UXRPB	(cu. yd.)	(cu. yd.)
16+00.00	0	0
16+50.00	67	77
17+00.00	92	37
17+50.00	111	40
18+00.00	138	30
18+50.00	143	25
19+00.00	128	23
19+50.00	118	30
20+00.00	104	47
20+50.00	84	66
21+00.00	85	96
21+50.00	84	122
22+00.00	87	118
22+50.00	93	106
22+70.00	35	35

Station	Uncl. Exc.	Embt
UXRPC	(cu. yd.)	(cu. yd.)
19+50.00	0	0
20+00.00	79	227
20+50.00	80	161
21+00.00	83	66