

LOCATION SKETCH —

LUMP SUM

NOTES

ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.

THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE REQUIREMENTS OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.

THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.

PRESTRESSED CONCRETE DECK PANELS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.

REMOVABLE FORMS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.

NEEDLE BEAMS WILL NOT BE ALLOWED UNLESS OTHERWISE CALLED FOR ON THE PLANS OR APPROVED BY THE ENGINEER.

THE CLASS AA CONCRETE IN THE BRIDGE DECK SHALL CONTAIN FLY ASH OR GROUND GRANULATED BLAST FURNACE SLAG AT THE SUBSTITUTION RATE SPECIFIED IN ARTICLE 1024-1 AND IN ACCORDANCE WITH THE ARTICLES 1024-5 AND 1024-6 OF THE STANDARD SPECIFICATIONS. NO PAYMENT WILL BE MADE FOR THIS SUBSTITUTION AS IT IS CONSIDERED INCIDENTAL TO THE COST OF THE REINFORCED CONCRETE DECK SLAB.

WORK SHALL NOT BE STARTED ON THIS BRIDGE UNTIL ROADWAY SECTION HAS BEEN EXCAVATED.


THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPLICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.

• , , , , , , ,	PLE BAR ACEMENT
SIZE	LENGTH
#3	6'-2"
# 4	7′-4″
#5	8'-6"
#6	9'-8"
#7	10'-10"
#8	12'-0"
#9	13'-2"
#10	14′-6″
#11	15′-10″

NOTE: SAMPLE BAR REPLACEMENT LENGTHS BASED ON 30" (SAMPLE LENGTH) PLUS TWO SPLICE LENGTHS AND Fy = 60 KSI.

> PROJECT NO. U-2579AB FORSYTH COUNTY STATION: 30+67.66 -Y4-

SHEET 3 OF 3



North Carolina License Nos. 50073 \* F-0493 \* C-28

GENERAL DRAWING

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

RALEIGH

FOR BRIDGE ON SR 4315 VER WINSTON-SALEM NORTHERN BELTWAY BETWEEN SR 2662

AND SR 2632 RS&H Architects-Engineers-Planners, Inc. SHEET NO REVISIONS 8521 Six Forks Road, Suite 400 S2-3 BY: DATE: DATE: NO. BY: 919-926-4100 FAX 919-846-9080 TOTAL SHEETS www.rsandh.com

	TOTAL BILL OF MATERIALS															
EXC	PILE AVATION N SOIL	PILE EXCAVATION NOT IN SOIL	4'-0"∅ DRILLED PIER IN SOIL	4'-0" Ø DRILLED PIER NOT IN SOIL	SID INSPECTION	CSL TESTING	REINFORCED CONCRETE DECK SLAB	GROOVING BRIDGE FLOORS	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	SPIRAL COLUMN REINFORCING STEEL		"PRESTRESSED CRETE GIRDERS	PILE DRIVING EQUIPMENT SETUP FOR HP 12X53 STEEL PILES	
L	IN. FT.	LIN.FT.	LIN.FT.	LIN. FT.	EACH	EACH	SQ.FT.	SQ.FT.	CU. YDS.	LUMP SUM	LBS.	LBS.	NO.	LIN.FT.	EACH	1
							18,804	19,887		LUMP SUM			22	1763.7		
	90	90							86.6		18,913				18	

57.0

71.4

86.6

301.6

LUMP SUM

15,558

18,938

18,907

72,316

3,085

3,311

6,396

	LIN. FT.	LIN. FT.	LIN. FT.	LI	N. FT.	EACH	+	EACH	SQ.FT.	SI
SUPERSTRUCTURE									18,804	1'
END BENT NO.1	90	90								
BENT NO.1A			28.5		39.0					
BENT NO.1B			0.0		56.0					
END BENT NO.2	25	95								
TOTAL	115	185	28.5		95.0	1		1	18,804	1
	STEEL PILE POINTS	CONCRETE BARRIER RAIL	VERTICAL CONCRETE BARRIER			_OPE CTION		STOMERIC EARINGS	EXPANSION JOINT SEALS	
	LIN.FT.	LIN.FT.	LIN.FT.		SQ.	YDS	Ll	JMP SUM	LUMP SUM	
SUPERSTRUCTURE		363.5	423.5				Ll	JMP SUM	LUMP SUM	
END BENT NO.1	6				5	7				
BENT NO.1A										
BENT NO.1B										
END BENT NO.2	6				5	7				

423.5

DRAWN BY :	MRA		DATE	0	10/2019
CHECKED BY :	JMR	<b>\</b>	DATE		_10/2019_
DESIGN ENGINEER	of RECORD:	JMR	DATE	0	10/2019

TOTAL

363.5

OCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

HP 12X53

STEEL PILES

NO. LIN.FT

18

1763.7

540

540

1080

LUMP SUM