BENCH MARK #3:R/R SPIKE SET IN ROOT OF 54"WILLOW OAK, 724.4'LT. OF STA. 808+94.85 -L-, EL. 925.47 UNNAMED TRIBUTARY المنتخبين المالية TO FIDDLERS CREEK TO SR 2679 (GLENN HI RD) € CULVERT CLASS 'I' RIP RAP SINGLE -6'x7' RCBC (ROADWAY PAY ITEM)--Y15FLYBD-<u>FLOW</u> └─CLASS 'I'RIP RAP (ROADWAY PAY ITEM) ¥STA.792+88.12 -L--Y15FLYAC- $\frac{7}{2}$  woods  $\frac{7}{2}$ ROADWAY DATA GRADE POINT ELEV. @ STATION 792+88.12 = 873.57 BED ELEV. @ STATION 792+88.12 = 848.20 ROADWAY SLOPES = 4:1 LOCATION SKETCH

FOR UTILITY INFORMATION, SEE UTILITY PLANS AND SPECIAL PROVISIONS

DWG BY: T. MCALEENAN

CHK BY: R. TURNAGE

DATE : 11/19

\_ DATE : 11/19

\_ DATE : <u>11/19</u>

DATE : 11/19

T. MCALEENAN

DES CHK: R. TURNAGE

HYDRAULIC DATA

DESIGN DISCHARGE = 180 CFS FREQUENCY OF DESIGN FLOOD = 50 YR. DESIGN HIGH WATER ELEVATION = 857.3

= 0.09 SQ.MI DRAINAGE AREA BASE DISCHARGE (Q100) = 200 CFS BASE HIGH WATER ELEVATION = 857.6

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE = 490 CFS FREQUENCY OF OVERTOPPING FLOOD = >500 YR. OVERTOPPING FLOOD ELEVATION = 871.0

TOTAL STRUCTURE QUANTITIES

CLASS A CONCRETE BARREL @ 0.949 C.Y./FT. 304.0 C.Y. WINGS ETC.\_\_ 56.8 C.Y. SILLS/BAFFLES 3.8 C.Y. TOTAL 364.6 C.Y.

REINFORCING STEEL BARREL, HEADWALLS, SILLS,

& BAFFLES 60,518 LBS. WINGS <u>5,323</u> LBS. TOTAL 65,841 LBS.

CULVERT EXCAVATION LUMP SUM FOUNDATION CONDITIONING MATERIAL 260 TONS GEOTEXTILE FOR DRAINAGE 1020 SY


> SAMPLE BAR REPLACEMENT SIZE LENGTH #3 6'-2" #4 7'-4" #5 8'-6" #6 9′-8″ 10'-10" 12'-0" 13'-2"

> > #11

SAMPLE BAR REPLACEMENT LENGTHS BASED ON 30" (SAMPLE LENGTH) PLUS TWO SPLICE LENGTHS AND fy = 60 ksi.

14'-6"

15′-10″



PROFILE ALONG & CULVERT

NOTES

ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.

DESIGN FILL = 19.76'

FOR OTHER DESIGN DATA AND NOTES, SEE STANDARD NOTE SHEET.

3"Ø WEEP HOLES INDICATED TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.

CONCRETE IN THE CULVERTS TO BE POURED IN THE FOLLOWING ORDER:

1. WING FOOTINGS AND FLOOR SLAB INCLUDING 4"OF ALL VERTICAL WALLS.

2. THE REMAINING PORTIONS OF THE WALLS AND WINGS FULL HEIGHT FOLLOWED BY ROOF SLAB AND HEADWALLS.

THE RESIDENT ENGINEER SHALL CHECK THE LENGTH OF CULVERT BEFORE STAKING IT OUT TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.

DIMENSIONS FOR WING LAYOUT AS WELL AS ADDITIONAL REINFORCING STEEL EMBEDDED IN BARREL ARE SHOWN ON THE WING SHEETS.

TRANSVERSE CONSTRUCTION JOINTS SHALL BE USED IN THE BARREL, SPACED TO LIMIT THE POURS TO A MAXIMUM OF 70 FEET.LOCATION OF THE JOINTS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER.

AT THE CONTRACTOR'S OPTION HE MAY SUBMIT, TO THE ENGINEER FOR APPROVAL, DESIGN AND DETAIL DRAWINGS FOR A PRECAST REINFORCED CONCRETE BOX CULVERT IN LIEU OF THE CAST-IN-PLACE CULVERT SHOWN ON PLANS. THE DESIGN SHALL PROVIDE THE SAME SIZE AND NUMBER OF BARRELS AS USED ON THE CAST-IN-PLACE DESIGN. FOR OPTIONAL PRECAST REINFORCING CONCRETE BOX CULVERT, SEE SPECIAL PROVISIONS.

A 3 FOOT STRIP OF GEOTEXTILE SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.

THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPLICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO THE VARIOUS PAY ITEMS.

FOR CULVERT DIVERSION DETAILS AND PAY ITEM, SEE EROSION CONTROL PLANS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

**UNLESS ALL SIGNATURES COMPLETE** 

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

AT THE CONTRACTOR'S OPTION, HE MAY SPLICE THE VERTICAL REINFORCING STEEL IN THE INTERIOR FACE OF EXTERIOR WALL ABOVE LOWER WALL CONSTRUCTION JOINT. THE SPLICE LENGTH SHALL BE AS PROVIDED IN THE SPLICE LENGTH CHART SHOWN ON THE PLANS.EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY THE CONTRACTOR.

FOR BOX CULVERT EXCAVATION, SEE SECTION 414 OF THE STANDARD SPECIFICATIONS.

THE REINFORCED CONCRETE BOX CULVERT SHALL BE PLACED ON THE STANDARD 1.0 FOOT BLANKET OF THE FOUNDATION CONDITIONING MATERIAL.

INSTALL TYPE 2 GEOTEXTILE ON THE SIDES AND TOP OF THE CULVERT FOR ITS ENTIRE LENGTH. OVERLAP GEOTEXTILES A MINIMUM OF 18 INCHES. ESTIMATED TYPE 2 GEOTEXTILE QUANTITY - 1,020 SYDS.

THE REINFORCED CONCRETE BOX CULVERT SHALL BE CONSTRUCTED WITH 3 INCHES OF CAMBER TO ACCOUNT FOR ANTICIPATED SETTLEMENT.

> U-2579AB PROJECT NO.\_\_\_ FORSYTH COUNTY

792+88.12 -L-STATION:

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SINGLE BARREL 6 FT. X 7 FT. CONCRETE BOX CULVERI

89°/65°45′00″ SKEW REVISIONS NO. BY: BY: DATE: C2-1 TOTAL SHEETS **DOCUMENT NOT CONSIDERED FINAL** 

HDR Engineering, Inc. of the Carolinas 555 Fayetteville St., Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116