

PROPOSED ALIGNMENT CONTROL SHEET

6/2/99

REVISIONS

L1

TYPE	STATION	NORTH	EAST
POT	10+11.74	659190.4660	815411.2395
PC	12+51.05	659368.3426	815571.3361
PT	16+00.00	659685.3662	815699.3917
POT	16+00.00	659685.3662	815699.3917

Y2

TYPE	STATION	NORTH	EAST
POT	10+00.00	659964.5649	815286.0890
PC	13+77.45	659665.8412	815516.8070
PCC	15+30.16	659546.1362	815611.6216
PT	17+41.48	659394.9878	815758.9002
POT	17+90.24	659363.2770	815795.9390

L2

TYPE	STATION	NORTH	EAST
PC	16+00.00	659665.7400	815725.8409
PT	19+42.65	659719.2702	816062.5885
POT	24+18.56	659712.7592	816538.4565

Y3

TYPE	STATION	NORTH	EAST
PC	10+00.00	659951.5789	815751.6288
PRC	11+80.48	659813.4842	815635.6500
PT	12+22.19	659782.5294	815607.7095
POT	12+77.52	659740.2418	815572.0217

Y1

TYPE	STATION	NORTH	EAST
POT	10+00.00	659439.5322	815442.7870
POT	11+64.88	659410.0537	815605.0114

Y4

TYPE	STATION	NORTH	EAST
POT	10+00.00	659804.7395	815109.9000
PC	10+33.47	659808.5299	815143.1549
PCC	11+78.72	659803.8291	815287.8113
PT	13+18.92	659775.1700	815425.0387
POT	16+26.21	659704.1257	815724.0035

DR1

TYPE	STATION	NORTH	EAST
POT	10+00.00	659457.1386	815691.8036
PC	10+25.09	659474.8660	815709.5611
PRC	10+93.24	659528.9543	815750.6744
PT	11+53.97	659577.7196	815786.6116
POT	13+35.67	659709.8553	815911.3340

Y5

TYPE	STATION	NORTH	EAST
PC	10+00.00	660303.3885	815900.8785
PCC	10+46.68	660258.4233	815888.3622
PRC	12+01.09	660106.3740	815862.8251
PRC	14+50.54	659867.1428	815797.9618
PT	16+45.95	659681.5933	815739.1419

RAB

TYPE	STATION	NORTH	EAST
PC	10+00.00	659746.8273	815700.3754
PT	14+08.41	659746.8273	815700.3754

Y6

TYPE	STATION	NORTH	EAST
POT	10+00.00	659934.0529	815993.4471
PC	10+85.25	659858.3554	815954.2363
PT	12+20.83	659817.3400	815838.1486
POT	12+78.33	659840.4474	815785.5039

NOTES:

1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
2. THE PROPOSED ALIGNMENT CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATINO REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

6/2/99
 WETHERILL ENGINEERING
 1223 JONES FRANKLIN RD
 RALEIGH, NC 27606