\$ \$ \$ \$ \$ \$ \$ () () ↔ ↔ \$\$\$\$\$\$\$\$YSTIME\$\$\$\$\$ \$\$\$\$\$\$\$\$\$\$\$\$\$\$\$ \$\$\$\$USERNAME\$\$\$

## 000 ら ••

00

### う 40 $\sim$ •• Z K

#### ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.50	ARROWS AND SHIELDS
901.70	SIGN STRINGERS AND SUPPOR
904.10	ORIENTATION OF GROUND MOU
904.50	MOUNTING OF TYPE 'D', 'E' A
910.40	SINGLE LANE ROUNDABOUT SI
1264.01	OBJECT MARKERS - TYPES
1264.02	OBJECT MARKERS - INSTALLA

#### GENERAL NOTES

- . SIGNS FURNISHED BY CONTRACTOR.
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER.
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

PLAN PREPARED BY:		🕥 Sta
BETSY L. WATSON, P.E. SENIOR ROSI R. HENNEIN TRANSP	TRANSPORTATION ENGINEER ORTATION DESIGNER	Stantec Consulting 801 Jones Franklir Suite 300 Raleigh, NC 2760 Tel. (919) 851-686 Fax. (919) 851-702 www.stantec.com License No. F-067

### STATE OF NORTH CAROLINA **DEPARTMENT OF TRANSPORTATION**

# SIGNING PLAN HAYWOOD COUNTY

#### LOCATION: WAYNESVILLE – INTERSECTION OF US 23 BUSINESS (N MAIN ST) AND WALNUT ST

ORT SPACING UNTED SIGNS AND 'F' SIGNS ON 'U' CHANNEL POSTS GIGNING, WITH PEDESTRIANS (SHEET 1 OF 2)

ATION

		SUMMARY OF QUANTITIES	1	
( ITEM N	0.	Sommin of gomminico		
DESC. NO.	SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4025000000	901	CONTRACTOR FURNISHED, TYPE D SIGN	48	SF
4025000000	901	CONTRACTOR FURNISHED, TYPE E SIGN		SF
4025000000	901	CONTRACTOR FURNISHED, TYPE F SIGN	89.50	SF
4072000000	903	SUPPORTS, 3-LB STEEL U-CHANNEL	900	LF
4096000000	904	SIGN ERECTION, TYPE D	6	EA
4102000000	904	SIGN ERECTION, TYPE E	47	EA
4108000000	904	SIGN ERECTION, TYPE F	8	EA
4116100000	904	SIGN ERECTION, RELOCATE TYPE E	2	EA
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	19	EA
4192000000	907	DISPOSAL OF SUPPORT, U-CHANNEL	1	EA
4915000000	1264	7' U-CHANNEL POSTS	. 7	EA
4955000000	1264			EA
4957000000	1264	OBJECT MARKERS (TYPE 1)	4	EA

antec

g Services Inc. n Road 024

TIP NO.	SHEET NO.
U–5888	SIGN-1
APPROVED: Betsy L. Watson 35E67BB34F8743F	
DATE: 9/23/2021	
SEAL	
SEAL SEAL OFESSION SEAL 29449 NGINEER SEAL 29449	
DOCUMENT NOT CONSIL UNLESS ALL SIGNATURES	

	INDEX
SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2-2A	TYPE 'D' SIGNS
SIGN-3	TYPE 'E' SIGNS
SIGN-3A	TYPE 'F' SIGNS
SIGN-4-5	SIGNING PLAN SHEETS