

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

HDR HDR Engineering, Inc. of the Carolinas
555 Fayetteville St, Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116

PROJECT REFERENCE NO. <i>R-2233BB</i>	SHEET NO. <i>EC-3E</i>
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

SOIL STABILIZATION TIMEFRAMES

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

PLOT DRIVER: NCDOT_pdf_color_eng.100.plt
 USER: DWAGNER DATE: 3/12/2020
 PENTABLE: NCDOT_TSH.tbl
 TIME: 3:51:05 PM SCALE: 1:398.182
 FILE: NCDOT\2015-2017-Erosion_On-Call\NCDOT-R2233BB-Erosion_Control\6.0-CAD_BIM\6.2-WIP\Erosion_Control\R2233BB-EC-MATTING.dgn