PROJECT NO.	SHEET NO.	TOTAL NO.
PT.08.18.10191, 2022CPT.08.18.	24	

S U M M A R Y O F Q U A N T I T I E S

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1.5" MILLING	1297000000-E 2" MILLING	1297000000-E 3" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1524200000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5D	1575000000-E ASPHALT BINDER FOR PLANT MIX	1577000000-E POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, #78 STONE	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	1838500000-N VACUUM TRUCK	1840000000-E MILLED RUMBLE STRIPS	2600000000-N RETROFIT EXISTING CURB RAMP	2605000000-N CONCRETE CURB RAMP	2613000000-N REMOVE AND REPLACE CURB RAMPS	2759000000-N GENERIC PAVING ITEM - REMOVE CONCRETE CURB RAMP	2815000000-N ADJUST DROP INLET	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	5255000000-N PORTABLE LIGHTING	7444000000-E INDUCTIVE LOOP SAWCUT	7456000000-E LEAD-IN CABLE (14-2 PAIR)
										MI	FT	TONS	SMI	TON	SY	SY	SY	SY	TONS	TONS	TON	TONS	TONS	TONS	SY	GAL	WK	LF	EA	EA	EA	EA	EA	EA	EA	LS	LF	LF
2022CPT.08.18.10191	Chatham	1	US 421 NB	FROM PVT JT 570FT N OF SR 2210 CARTER BROOKS RD TO US 64 (INCLUDES RAMPS EXIT 171)	1, 2	2	MD	NO	NO	3.66	28		0.93	130.00	61,072						6,328		361	200				38,650								1		
TOTAL FOR MAP NO. 1										**3.66**			**0.93**	**130.00**	**61,072**						**6,328**		**361**	**200**				**38,650**								**1**		
2022CPT.08.18.10191	Chatham	2	US 421 SB	FROM US 64 TO PVT JT 560FT N OF SR 2210 CARTER BROOKS RD (INCLUDES RAMPS EXIT 171)	1, 2	2	MD	NO	NO	3.35	28		0.80	110.00	57,029						8,915		508	140				35,376										
TOTAL FOR MAP NO. 2										**3.35**			**0.80**	**110.00**	**57,029**						**8,915**		**508**	**140**				**35,376**										
TOTAL FOR PROJ NO. 2022CPT.08.18.10191										**7.01**			**1.73**	**240.00**	**118,101**						**15,243**		**869**	**340**				**74,026**								**1**		
															118,101																							
2022CPT.08.18.20191	Chatham	3	SR 1107 (W. THIRD ST)	FROM PVT. JT. 178 LF E OF US 64 TO SR 1102 (COLERIDGE RD)	4	2	2WU	NO	NO	1.3	24	65			19,990					1,670		112		50														
TOTAL FOR MAP NO. 3										**1.3**		**65**			**19,990**					**1,670**		**112**		**50**														
2022CPT.08.18.20191	Chatham	4	SR 1107 (W. THIRD ST)	FROM SR 1102 (COLERIDGE RD) TO SR 1194 (N. IVEY AVE)	5	2	2WU	NO	NO	1.5	24		3.00	420.00	213			1,347		1,927		129		100									1	2	4			
TOTAL FOR MAP NO. 4										**1.5**			**3.00**	**420.00**	**213**			**1,347**		**1,927**		**129**		**100**									**1**	**2**	**4**			
2022CPT.08.18.20191	Chatham	5	SR 1107 (W. THIRD ST)	FROM SR 1194 (N. IVEY AVE) TO 250 LF E OF SR 1006 (N. SECOND AVE) - END C&G	9,10,11,12	2	2WU	NO	NO	0.72	30					13,000				1,320		88		50							7	1		13	10		5,200	5,200
TOTAL FOR MAP NO. 5										**0.72**						**13,000**				**1,320**		**88**		**50**							**7**	**1**		**13**	**10**		**5,200**	**5,200**
2022CPT.08.18.20191	Chatham	6	SR 1107 (E. THIRD ST)	FROM END C&G 250 LF E OF SR 1006 (N. SECOND AVE) TO PVT. JT. W OF N. TENTH AVE (NON-SYSTEM)	3	2	2WU	NO	NO	0.68	26		1.36	190.00				1,444		2,332		156		75	10,500.00	3,675	1.00							9	3			
TOTAL FOR MAP NO. 6										**0.68**			**1.36**	**190.00**				**1,444**		**2,332**		**156**		**75**	**10,500.00**	**3,675**	**1.00**							**9**	**3**			
2022CPT.08.18.20191	Chatham	7	SR 1006 (W. RALEIGH ST)	FROM SR 2113 (S. SECOND AVE) TO LAKEWOOD DR (NON-SYSTEM)	13,14,15	2	2WU	NO	NO	0.72	41				3,400		13,000			1,576		106							3		1			20	13		5,100	5,100
TOTAL FOR MAP NO. 7										**0.72**					**3,400**		**13,000**			**1,576**		**106**							**3**		**1**			**20**	**13**		**5,100**	**5,100**
2022CPT.08.18.20191	Chatham	8	SR 1006 (W. RALEIGH ST)	FROM LAKEWOOD DR (NON-SYSTEM) TO SR 1119 (WADE PASCHAL RD)	4	2	2WU	NO	NO	0.59	22				7,775					750		50		75										1	1			
TOTAL FOR MAP NO. 8										**0.59**					**7,775**					**750**		**50**		**75**										**1**	**1**			
2022CPT.08.18.20191	Chatham	9	SR 1180 (DOGWOOD AVE)	FROM SR 1107 (W. THIRD ST) TO SR 1006 (W. RALEIGH ST)	8	2	2WU	NO	NO	0.08	20	10	0.16	22.00				444		126		8		25	940.00	330	0.20						4	4	2			
TOTAL FOR MAP NO. 9										**0.08**		**10**	**0.16**	**22.00**				**444**		**126**		**8**		**25**	**940.00**	**330**	**0.20**						**4**	**4**	**2**			
2022CPT.08.18.20191	Chatham	10	SR 1006 (N. SECOND AVE)	FROM PVT JT S OF SR 1317 (N. GREENSBORO AVE) TO PVT JT S OF SILER BUSINESS DR	5	2	2WU	NO	NO	0.104	24		0.21	29.00				533		134		9		25														
TOTAL FOR MAP NO. 10										**0.104**			**0.21**	**29.00**				**533**		**134**		**9**		**25**														
2022CPT.08.18.20191	Chatham	11	SR 1006 (N. SECOND AVE)	FROM CONC. PVT. JT S OF COTTAGE GROVE AVE (NON-SYSTEM) TO SR 2103 (E RALEIGH ST)	16	2	2WU	NO	NO	0.53	64				21,100					2,112		141								4				12	7			
TOTAL FOR MAP NO. 11										**0.53**					**21,100**					**2,112**		**141**								**4**				**12**	**7**			
2022CPT.08.18.20191	Chatham	12	SR 2202 (N 5TH AVE)	FROM SR 2100 (MLK JR BLVD) TO E 9TH ST (END MAINT)	17	2	2WU	NO	NO	0.16	20	25						444		170		11		50											3			
TOTAL FOR MAP NO. 12										**0.16**		**25**						**444**		**170**		**11**		**50**											**3**			
2022CPT.08.18.20191	Chatham	13	SR 2170 (RIVES CHAPEL CH RD)	FROM SR 2168 (CAROLINA HILL RD) TO SR 2120 (IKE BROOKS RD)	17	2	2WU	NO	NO	1.39	22	25						978		1,398		94		150														
TOTAL FOR MAP NO. 13										**1.39**		**25**						**978**		**1,398**		**94**		**150**														
2022CPT.08.18.20191	Chatham	14	SR 2106 (CHESTNUT ST/S 6TH ST/E. CARDINAL ST)	FROM SR 2113 (S. SECOND AVE) TO SR 2223 (MATTHEWS ST)	8	2	2WU	NO	NO	0.5	18	25	1.00	140.00				800		787		53		75	5,850.00	2,050	0.50							5				
TOTAL FOR MAP NO. 14										**0.5**		**25**	**1.00**	**140.00**				**800**		**787**		**53**		**75**	**5,850.00**	**2,050**	**0.50**							**5**				
2022CPT.08.18.20191	Chatham	15	SR 2106 (E. CARDINAL ST)	FROM SR 2223 (MATTHEWS ST) TO END C&G @ 350LF E OF CENTRAL AVE (NON-SYSTEM)	16	2	2WU	NO	NO	0.23	44				5,937					650		44												6				
TOTAL FOR MAP NO. 15										**0.23**					**5,937**					**650**		**44**												**6**				
2022CPT.08.18.20191	Chatham	16	SR 2106 (E. CARDINAL ST)	FROM END C&G @ 350LF E OF CENTRAL AVE (NON-SYSTEM) TO STATE MAINTENANCE ENDS SIGN	8	2	2WU	NO	NO	0.072	20		0.14	20.00				111		64		4		10	850.00	300	0.20											
TOTAL FOR MAP NO. 16										**0.072**			**0.14**	**20.00**				**111**		**64**		**4**		**10**	**850.00**	**300**	**0.20**											
2022CPT.08.18.20191	Chatham	17	SR 2204 (MATTHEWS ST [LOOPS])	FROM SR 2106 (E. CARDINAL ST) TO SR 2106 (E. CARDINAL ST)	17	2	2WU	NO	NO	0.07	20	25						111		62		4		40														
TOTAL FOR MAP NO. 17										**0.07**		**25**						**111**		**62**		**4**		**40**														
2022CPT.08.18.20191	Chatham	18	SR 2223 (MATTHEWS ST)	FROM SR 2106 E. CARDINAL ST TO DEAD END	6	2	2WU	NO	NO	0.06	22	25	0.12	20.00				133	225	109		17		25														
TOTAL FOR MAP NO. 18										**0.06**		**25**	**0.12**	**20.00**				**133**	**225**	**109**		**17**		**25**														
2022CPT.08.18.20191	Chatham	19	SR 1106 (ELLINGTON RD)	FROM SR 1107 (W. THIRD ST) TO PVT. JT. 200LF N OF US 64	5	2	2WU	NO	NO	0.83	22		1.66	232.00				244		978		66		110														
TOTAL FOR MAP NO. 19										**0.83**			**1.66**	**232.00**				**244**		**978**		**66**		**110**														
2022CPT.08.18.20191	Chatham	20	SR 1318 (ROLAND MARSH RD)	FROM SR 1316 (HAROLD ANDREWS RD) TO SR 1317 GREENSBORO AVE	17	2	2WU	NO	NO	0.5	18	25						100		402		27		50														
TOTAL FOR MAP NO. 20										**0.5**		**25**						**100**		**402**		**27**		**50**														
2022CPT.08.18.20191	Chatham	21	SR 1182 (AUBRY DAVIS RD)	FROM SR 1108 (HAMP STONE RD) TO SR 1183 (MESSER RD)	7	2	2WU	NO	NO	0.09	18		0.18	25.00				950		72		5		20														
TOTAL FOR MAP NO. 21										**0.09**			**0.18**	**25.00**				**950**		**72**		**5**		**20**														
2022CPT.08.18.20191	Chatham	22	SR 1183 (MESSER DR)	FROM DEAD END TO DEAD END	7	2	2WU	NO	NO	0.24	18		0.48	67.00				2,534		193		13		50														
TOTAL FOR MAP NO. 22										**0.24**			**0.48**	**67.00**				**2,534**		**193**		**13**		**50**														
2022CPT.08.18.20191	Chatham	23	SR 1191 W. (SHANNON RD)	FROM US 64 TO DEAD END	7	2	2WU	NO	NO	0.19	18		0.38	53.00				100		153		10		40														
TOTAL FOR MAP NO. 23										**0.19**			**0.38**	**53.00**				**100**		**153**		**10**		**40**														
2022CPT.08.18.20191	Chatham	24	SR 1186 (PARKWOOD DR)	FROM SR 1187 (CLIFTWOOD DR) TO END MAINT (DRIFTWOOD RD - NON-SYSTEM)	17	2	2WU	NO	NO	0.11	20							111		98		7		20														
TOTAL FOR MAP NO. 24										**0.11**								**111**		**98**		**7**		**20**														
2022CPT.08.18.20191	Chatham	25	SR 1187 (CLIFTWOOD DR)	FROM CUL-DE-SAC TO SR 1186 (PARKWOOD DR)	17	2	2WU	NO	NO	0.2	20							111		178		12		20														
TOTAL FOR MAP NO. 25										**0.2**								**111**		**178**		**12**		**20**														
2022CPT.08.18.20191	Chatham	26	SR 1374 (FLETCHER SILER RD) - LOOPS	FROM SR 1316 (HAROLD ANDREWS RD) TO SR 1316 (HAROLD ANDREWS RD)	7	2	2WU	NO	NO	0.3	20		0.60	84.00				167		268		18		50														
TOTAL FOR MAP NO. 26										**0.3**			**0.60**	**84.00**				**167**		**268**		**18**		**50**														
TOTAL FOR PROJ NO. 2022CPT.08.18.20191										**11.166**		**225**	**9.29**	**1,302.00**	**58,415**	**13,000**	**13,000**	**10,662**	**225**	**17,529**		**1,184**		**1,110**	**18,140.00**	**6,355**	**1.90**		**3**	**4**	**8**	**1**	**5**	**72**	**43**		**10,300**	**10,300**
GRAND TOTAL										**18.176**		**225**	**11.02**	**1,542.00**	**176,516**	**13,000**	**13,000**	**10,662**	**225**	**17,529**	**15,243**	**1,184**	**869**	**1,450**	**18,140.00**	**6,355**	**1.90**	**74,026**	**3**	**4**	**8**	**1**	**5**	**72**	**43**	**1**	**10,300**	**10,300**