

**ECONOLITE ASC/3-2070 OVERLAP PROGRAMMING DETAIL**  
*(program controller as shown)*

1. From Main Menu select 2. CONTROLLER
2. From CONTROLLER Submenu select 2. VEHICLE OVERLAPS  
Toggle Twice

*OVERLAP C*

Select TMG VEH OVLP [C] and 'PPLT FYA'

TMG VEH OVLP...[C] TYPE: ....PPLT FYA

PROTECTED LEFT TURN.... PHASE 5  
 OPPOSING THROUGH..... PHASE 6


FLASHING ARROW OUTPUT.....CH11 ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0  
 ACTION PLAN SF BIT DISABLE..... 0

END PROGRAMMING

THIS ELECTRICAL DETAIL IS FOR  
 THE SIGNAL DESIGN: 07-1637T  
 DESIGNED: May 2021  
 SEALED:  
 REVISED:


**DOCUMENT NOT CONSIDERED  
 FINAL UNLESS ALL  
 SIGNATURES COMPLETED**



**MOTT  
MACDONALD**  
 7621 Purfoy Road  
 Suite 115  
 Fuquay-Varina, NC 27526  
 www.mottmac.com  
 License No. F-0669

ELECTRICAL AND PROGRAMMING  
 DETAILS FOR:


Prepared for the Offices of:



750 N. Greenfield Pkwy, Corner, NC 27529

SR 1009 (S. Main Street) at US 29 NB Ramps	
Division 7	Guilford County High Point
PLAN DATE: May 2021	REVIEWED BY: RW Thompson
PREPARED BY: DE Fowler	REVIEWED BY:
REVISIONS	INIT. DATE

SEAL



Brendan A. Lehan  
 DATE

SIG. INVENTORY NO. 07-1637T

\$\$\$\$\$SYTIME\$\$\$\$\$  
 \$\$\$SYTIME\$\$\$\$\$  
 \$\$\$SYTIME\$\$\$\$\$