

08-0CT-2021 09:05 X:\15BPR21\Structures\FinalPlans\401_035_15BPR21_SMU_B3D_018_610006.DGN ksedai


AS-BUILT REPAIR QUANTITY TABLE									
BENT 3 SPAN D FACE	QUANTITIES								
	ESTI	ΜΑΤΕ	ACTUAL						
SHOTCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.					
САР	0.0	0.0							
COLUMN	0.0	0.0							
CONCRETE REPAIRS	AREA SQ.FT.	VOLUME AREA CU.FT. SQ.FT.		VOLUME CU.FT.					
САР	0.0	0.0	0.0						
COLUMN	0.0	0.0							
EPOXY RESIN INJECTION		LIN.FT.	LIN.FT.						
САР	0.0								
COLUMN	0.0								
ALLIES TH CHART REPRESENT ESTIMATER REPAIR TOTALS AFTER									

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MINIMUM OF 1"BEHIND REBAR AND MINIMUM 2"CLEARANCE TO SAWCUT. SEE ``TYPICAL CAP AND COLUMN REPAIR DETAILS'' SHEET.

NOTES:

REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE GIVEN BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER SHALL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATION AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

CONCRETE REPAIRS MAYBE SUBSTITUTED IN LIEU OF SHOTCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.



SHOTCRETE REPAIR AREA

CONCRETE REPAIR AREA



ERI - EPOXY RESIN INJECTION

PROJECT NO. <u>15BPR.21</u> <u>MONTGOMERY</u> COUNTY BRIDGE NO. <u>610006</u>

DocuSigned by: Krishna P. Sedai EAGF79415000000000000000000000000000000000000	DEPA	RTMENT	OF R	ALEIGH	SPORTA	TION		
	REVISIONS SHEET NO.							
DOCUMENT NOT CONSIDERED	NO. BY:	DATE:	NO.	BY:	DATE:	S1-18		
FINAL UNLESS ALL	1		3			TOTAL SHEETS		
SIGNATURES COMPLETED	2		4			34		