PROJECT NO.	SHEET NO.	TOTAL NO.
2022CPT.05.16.20921.1, 2022CPT.05.16.20922.1	26	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW	0264000000-E SHOULDER GRADING	1220000000-E INCIDENTAL STONE BASE	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1½" MILLING	1308000000-E 0" TO 1.5" MILLING	1308000000-E 0" TO 1.25" MILLING	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2549000000-E 2'-6" CURB & GUTTER	2591000000-E 4" CONCRETE SIDEWALK	2600000000-N RETROFIT EXISTING CURB RAMP	2605000000-N CONCRETE CURB RAMP	2613000000-N REMOVE AND REPLACE CURB RAMPS	2738000000-E GENERIC PAVING ITEM, SIDEWALK REMOVAL	2759000000-N GENERIC PAVING ITEM, REMOVE CURB RAMPS	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE	6084000000-E SEED & MULCHING	6117000000-N RESPONSE FOR EROSION CONTROL	7444000000-E INDUCTIVE LOOP SAWCUT
									MI	FT	CY	SMI	TONS	TON	SY	SY	SY	SY	TONS	TONS	TON	TONS	LF	SY	EA	EA	EA	SY	EA	EA	EA	LF	LF	AC	EA	LF
2022CPT.05.16.20921.1	Wake	1	TEN TEN RD SR 1010	US 401 TO N. SALEM ST.	1	2-5	NO	NO	10.088	26-70	564	18.80	470	695	246,043			1,500		24,845	1,491	980	302	148	7	1	47	21	17	6	7	820	2,060	8.20	1	7,760
		2	PENNY RD SR 1379	SR1010 (TEN TEN RD.) TO SR1300 (KILDAIRE FARM RD)	2	2	NO	NO	1.298	31-76	52	2.59	65	144	41,980			1,167	3,142		211	735	32	26	1		13	4	2		5	75	190	0.75	1	975
		3	JUAQUIN LN SR 4025	SR 1503 (DONNY BROOK RD). TO CDS	3	2	NO	NO	0.201	18-30	20	0.40	10					60	200		13	310									1	29	80	0.29		
		4	NEW WINDSOR PL SR 4026	SR 4025 (JUAQUIN LN). TO CDS	3	2	NO	NO	0.095	18-29	9	0.19	5						120		8	95									1	14	40	0.14		
		5	REIGATE LN SR 4027	SR1503 (DONNY BROOK RD) TO CDS	3	2	NO	NO	0.141	18-34	14	0.28	7					100	153		10	150										20	60	0.20		
		6	RANSDELL RD SR 1392	BACK OF RADIUS JOINT AT US 401 TO BACK OF RADISU JOINT AT SR 1503 (DONNY BROOK RD.)	4	2	NO	NO	1.163	21-24	116	2.32	58					510	1,323		89	440										169	430	1.69	1	
		7	CROSS LAKE DR. - SR 4749	SR1543 (MILL CREEK DR.) TO SR1543 (MILL CREEK DR.)	4	2	NO	NO	0.759	20-47	76	1.52	38						861		58	525										110	280	1.10		
		8	ROLLING CREEK - SR 4751	SR 4749 (CROSS LAKE DR.) TO CDS	3	2	NO	NO	0.03	18-41	3	0.06	2						66		4	3										4	20	0.04		
		9	HILLSHIRE COURT - SR 4750	SR 4749 (CROSS LAKE DR.) TO CDS	3	2	NO	NO	0.125	20-33	13	0.25	6						157		11	35										18	50	0.18		
		10	MILL CREEK DR. - SR 1543	SR1404 (EP TO END MAINTENANCE/END RADIUS) SR4749 (CROSS LAKE DR.)	4	2	NO	NO	0.639	20-36	64	1.28	32					290	705		47	120										93	240	0.93		
		11	AIR PARK RD SR 2752	BACK OF RADIUS JOINT AT US 401 TO EOM	4	2	NO	NO	1.055	20-27	105	2.11	53			1,053		210	1,167		78	1,240										154	390	1.53	1	
		12	DUNALLIE DR SR 3786	SR 2752 (AIR PARK RD.) TO CDS	3	2	NO	NO	0.246	20-46	25	0.49	12				30	109	285		19	2								1		36	90	0.36		
		13	WIND HAVEN DR SR 3716	SR 2752 (AIR PARK RD.) TO SR 3717 (APRIL WIND DR.)	3	2	NO	NO	0.205	20-48	20	0.41	10						205		14	105										30	80	0.30		
		14	APRIL WIND DR SR 3717	DEAD END TO CDS	3	2	NO	NO	0.219	20-28	22	0.44	11						230		15	75										32	80	0.32		
		15	SOFT WIND DR SR 3755	SR 2752 (AIR PARK RD.) TO SR 3757 (LORENA LYNN CT.)	3	2	NO	NO	0.611	20-55	61	1.22	31						562		38	760										89	230	0.89		
		16	LAURA ASHLEY CIR. SR 3756	CDS TO CDS	3	2	NO	NO	0.231	20-47	23	0.46	12						274		18	510										34	90	0.34		
		17	LORENA LYNN CT SR 3757	CDS TO CDS	3	2	NO	NO	0.184	20-25	18	0.37	9						221		15	225										27	70	0.27		
		18	DWIGHT ROWLAND RD SR 2755	BACK OF RADIUS JOINT AT US 401 TO BACK OF RADIUS JOINT BEHIND RAILROAD TRACKS R 2754 (KENNEBEC RD.)	4	2	NO	NO	1.434	20-37	143	2.87	72			550		400	1,625		109	1,020										208	530	2.08	1	
		19	JOE LEACH RD SR 2730	SR1010 (TEN TEN RD.) TO DEAD END	3	2	NO	NO	0.861	20	86	1.72	43					181	768		51	585										125	320	1.25		
		20	HUNTWYCK DR SR 3858	SR 2730 (JOE LEACH RD.) TO CDS	3	2	NO	NO	0.341	20-45	34	0.68	17						349		23	345										49	130	0.49		
		21	FINAL TRIAL CT SR 3859	SR2730 (JOE LEACH RD.) TO CDS	3	2	NO	NO	0.093	20-47	9	0.18	5						121		8	2										13	40	0.13		
		22	BOWLING FARM CT SR 3860	CDS TO CDS	3	2	NO	NO	0.18	20-49	18	0.36	9						230		15	120										26	70	0.26		
		23	HUNTER FARM DR SR 3861	CDS TO CDS	3	2	NO	NO	0.328	20-56	33	0.65	16						356		24	90										48	120	0.48		
		24	BRITT FARM DR SR 5553	SR 3861 (HUNTER FARM DR.) TO CDS	3	2	NO	NO	0.075	20-41	7	0.15	4						105		7	35										11	30	0.11		
		25	LASSITER FARM RD SR3878	SR 2730 (JOE LEACH RD.) TO CDS	3	2	NO	NO	0.08	20-51	8	0.16	4						115		8	80										12	30	0.12		
		26	SHANNONDALE DR SR 3758	SR 2730 (JOE LEACH RD.) TO CDS	3	2	NO	NO	0.444	20-49	44	0.89	22						397		27	375										64	170	0.64		
		27	AQUA LN SR 3759	SR 3758 (LASSITER FARM RD.) TO CDS	3	2	NO	NO	0.126	17-42	13	0.25	6						136		9	85										18	50	0.18		
		28	MARKAY CIR SR 3760	SR 3759 (AQUA LN.) TO CDS	3	2	NO	NO	0.121	17-23	12	0.24	6						131		9	110										17	50	0.17		
		29	BLUE RIVER FARM RD SR 5552	SR 3861 (HUNTER FARM DR.) TO CDS	3	2	NO	NO	0.271	20-45	27	0.54	14						280		19	55										39	100	0.39		
		30	BRITT RIDGE CT SR 5554	SR 5552 (BLUE RIVER FARM RD.) TO CDS	3	2	NO	NO	0.053	20-40	5	0.11	3						85		6	55										8	20	0.08		
		31	HUNTERFOX CT SR 5555	SR 5552 (BLUE RIVER FARM RD.) TO CDS	3	2	NO	NO	0.023	20-36	2	0.05	1						59		4	2										3	10	0.03		
		32	GUFFY DR SR2875	SR 2731 (JORDAN RD..) TO CDS	3	2	NO	NO	0.285	20-28	28	0.57	14					200	291		19	195										41	110	0.41		
		33	ROY AVERETTE DR SR3719	SR 2731 (JORDAN RD.) TO CDS	3	2	NO	NO	0.207	20-31	21	0.41	10					180	220		15	65										30	80	0.30		
TOTAL FOR PROJ NO. 2022CPT.05.16.20921.1									**22.212**		**1,695**	**43.02**	**1,077**	**839**	**288,023**	**1,603**	**30**	**4,907**	**14,939**	**24,845**	**2,492**	**9,529**	**334**	**174**	**8**	**1**	**60**	**25**	**19**	**7**	**14**	**2,466**	**6,340**	**24.65**	**5**	**8,735**
2022CPT.05.16.20922.1	Wake	34	RIVER DOWN DR SR 3731	SR 2736 (ROCK SERVICE STATION RD.) TO CDS	5	2	NO	NO	0.16	20-31								112	151		10	150														
		35	RIBBON TROUGH CT SR 3732	SR 3731 (RIVER DOWN DR.) TO CDS	5	2	NO	NO	0.174	21-34									160		11	360														
		36	JORDAN RIDGE LN SR 4910	SR 2731 (JORDAN RD.) TO CDS	5	2	NO	NO	0.391	20-44								480	325		22	960														
		37	TRUNECEK CIR SR 4911	CDS TO CDS	5	2	NO	NO	0.224	20-41									191		13	510														
		38	BLANNIE FARMS LN. SR 5523	NC 42 TO CDS	5	2	NO	NO	0.438	20-27								122	350		23	30														
		39	IVY LEAF CT SR 5524	SR 5523 (BLANNIE FARMS LN.) TO EOM	5	2	NO	NO	0.1	20-25								61	83		6	2														
		40	BRITTANY WOOD DR SR 5525	SR 5523 (BLANNIE FARMS LN.) TO CDS	5	2	NO	NO	0.06	18-25									75		5	2														
		41	JUSTIN OAKS CT SR 5526	CDS TO SR 5528 (MESSENGER DR.)	5	2	NO	NO	0.145	19-54									133		9	105														
		42	JENNY RIDGE LN SR 5527	SR 5523 (BLANNIE FARMS LN.) TO CDS	5	2	NO	NO	0.085	19-30									80		5	15														
		43	MESSENGER DR SR 5528	CDS TO CDS	5	2	NO	NO	0.332	20-30									282		19	375														
		44	ASPEN FALLS CT SR 5529	SR 5528 (MESSENGER DR.) TO CDS	5	2	NO	NO	0.034	20-34									62		4	35														
TOTAL FOR PROJ NO. 2022CPT.05.16.20922.1									**2.143**									**775**	**1,892**		**127**	**2,544**														
GRAND TOTAL									**24.355**		**1,695**	**43.02**	**1,077**	**839**	**288,023**	**1,603**	**30**	**5,682**	**16,831**	**24,845**	**2,619**	**12,073**	**334**	**174**	**8**	**1**	**60**	**25**	**19**	**7**	**14**	**2,466**	**6,340**	**24.65**	**5**	**8,735**