## **GENERAL NOTES:**

**1. THE PROPOSED UTILITY CONSTRUCTION** SHALL MEET THE APPLICABLE REQUIREMENTS OF THE NC DEPARTMENT OF **TRANSPORTATION'S "STANDARD** SPECIFICATIONS FOR ROADS AND STRUCTURES" DATED JANUARY 2018 AND THE SPECIAL PROVISIONS TO NCDOT PROVIDED BY PWC

2. FAYETTEVILLE PWC OWNS AND OPERATES THE EXISTING WATER AND SEWER UTILITIES.

3. ALL WATER LINES TO BE INSTALLED WITHIN COMPLIANCE OF THE RULES AND **REGULATIONS OF THE NORTH CAROLINA** DEPARTMENT OF ENVIRONMENTAL QUALITY, DIVISION OF WATER RESOURCES, PUBLIC WATER SUPPLY SECTION. ALL SEWER LINES TO BE INSTALLED WITHIN COMPLIANCE OF THE RULES AND REGULATIONS OF THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT QUALITY, DIVISION OF WATER RESOURCES, WATER QUALITY SECTION. PERFORM ALL WORK IN ACCORDANCE WITH THE APPLICABLE PLUMBING CODES.

4. FAYETTEVILLE PWC OWNS THE EXISTING UTILITY FACILITIES AND WILL OWN THE NEW UTILITY FACILITIES AFTER ACCEPTANCE BY THE DEPARTMENT. THE DEPARTMENT OWNS THE CONSTRUCTION CONTRACT AND HAS ADMINISTRATIVE AUTHORITY. COMMUNICATIONS AND DECISIONS BETWEEN THE CONTRACTOR AND UTILITY OWNER ARE NOT BINDING UPON THE DEPARTMENT OR THIS CONTRACT UNLESS AUTHORIZED BY THE ENGINEER. AGREEMENTS BETWEEN THE UTILITY OWNER AND CONTRACTOR FOR THE WORK THAT IS NOT PART OF THIS CONTRACT OR IS SECONDARY TO THIS CONTRACT ARE ALLOWED, BUT ARE NOT BINDING UPON THE DEPARTMENT.

5. PROVIDE ACCESS FOR THE DEPARTMENT PERSONNEL AND THE OWNER'S REPRESENTATIVES TO ALL PHASES OF CONSTRUCTION. NOTIFY DEPARTMENT PERSONNEL AND THE UTILITY OWNER TWO WEEKS PRIOR TO COMMENCEMENT OF ANY WORK AND ONE WEEK PRIOR TO SERVICE **INTERRUPTION. KEEP UTILITY OWNERS'** REPRESENTATIVES INFORMED OF WORK PROGRESS AND PROVIDE OPPORTUNITY FOR **INSPECTION OF CONSTRUCTION AND TESTING.** 

6. THE PLANS DEPICT THE BEST AVAILABLE INFORMATION FOR THE LOCATION, SIZE, AND TYPE OF MATERIAL FOR ALL EXISTING UTILITIES. MAKE INVESTIGATIONS FOR DETERMINING THE EXACT LOCATION, SIZE, AND TYPE MATERIAL OF THE EXISTING FACILITIES AS NECESSARY FOR THE CONSTRUCTION OF THE PROPOSED UTILITIES AND FOR AVOIDING DAMAGE TO EXISTING FACILITIES. REPAIR ANY DAMAGE INCURRED TO EXISTING FACILITIES TO THE ORIGINAL OR BETTER CONDITION AT NO ADDITIONAL COST TO THE DEPARTMENT.

7. MAKE FINAL CONNECTIONS OF THE NEW WORK TO THE EXISTING SYSTEM WHERE INDICATED ON THE PLANS, AS REQUIRED TO FIT THE ACTUAL CONDITIONS, OR AS DIRECTED.

8. MAKE CONNECTIONS BETWEEN EXISTING AND PROPOSED UTILITIES AT TIMES MOST CONVENIENT TO THE PUBLIC, WITHOUT ENDANGERING THE UTILITY SERVICE, AND IN ACCORDANCE WITH THE UTILITY OWNER'S REQUIREMENTS, MAKE CONNECTIONS ON WEEKENDS, AT NIGHT, AND ON HOLIDAYS IF NECESSARY.

9. ALL UTILITY MATERIALS SHALL BE APPROVED PRIOR TO DELIVERY TO THE PROJECT. SEE 1500-7, "SUBMITTALS AND RECORDS" IN SECTION 1500 OF THE STANDARD SPECIFICATIONS.

10. PRIOR TO PLACEMENT OF PROPOSED WATERLINE THE CONTRACTOR SHALL LOCATE ALL EXISTING WATER SERVICE LATERALS (DEPTH AND PIPE DIAMETER) AND NOTIFY THE RESIDENT ENGINEER IF THERE ARE COMPLICATIONS WITH CONNECTING TO THE PROPOSED WATERLINE. THE CONTRACTOR'S COST FOR ALL WORK ASSOCIATED WITH WATER SERVICES, IS INCIDENTAL TO WATER SERVICE PAYMENT ITEM.

11. THE CONTRACTOR SHALL REFER TO THE **"UTILITIES BY OTHERS" PLANS FOR** PROPOSED GAS, TELECOMMUNICATIONS, AQUA AMERICA WATER, AND POWER UTILITY **RELOCATIONS.** 

## UTILITY CONSTRUCTION

## **PROJECT SPECIFIC NOTES:**

1. ALL PROPOSED WATER LINE 2" IN DIAMETER SHALL BE SDR21, PRESSURE CLASS 200 IN ACCORDANCE WITH ASTM D 2241 OR SDR-17 WITH A PRESSURE RATING OF 250 PSI, IN ACCORDANCE WITH ASTM D-224. ALL PROPOSED WATER LINE 6"-12" IN DIAMETER SHALL BE DI (DUCTILE IRON PUSH-ON) PC 350 PIPE. ALL PROPOSED WATERLINE LINE 16" IN DIAMETER SHALL BE DI (DUCTILE IRON PUSH-ON) PC 250 PIPE.

2. ALL PROPOSED GRAVITY SEWER LINES 12" IN DIAMETER AND SMALLER SHALL BE CERAMIC EPOXY LINED DI (DUCTILE IRON PUSH ON) PC 350 PIPE. ALL PROPOSED GRAVITY SEWER LINES 16" IN DIAMETER AND GREATER SHALL BE CERAMIC EPOXY LINED DI (DUCTILE IRON PUSH ON) PC 250, UNLESS OTHERWISE SPECIFIED.

**3. CONTRACTOR'S ATTENTION IS DIRECTED** TO SECTIONS 102, 107, AND 1550 OF THE STANDARD SPECIFICATIONS CONCERNING TRENCHLESS INSTALLATION. IT IS CONTRACTOR'S RESPONSIBILITY TO HAVE BORE DESIGNED AND SEALED BY A LICENSED NORTH CAROLINA PROFESSIONAL ENGINEER. NO DAMAGE IS ALLOWED TO RIVER, WETLANDS, OR BUFFER ZONES.

4. IF HDPE PIPE IS INSTALLED BY HORIZONTAL DIRECTIONAL DRILL (HDD), IT SHALL BE FILLED WITH WATER AND NOT BE CONNECTED TO ANY OTHER PIPE OR FITTINGS FOR ONE WEEK FROM THE TIME OF INSTALLATION.

5. ALL CONSTRUCTION TO BE IN ACCORDANCE WITH ALL FAYETTEVILLE PWC AND/OR NCDOT STANDARDS AND SPECIFICATIONS.

6. UTILITY CONSTRUCTION NOTE SHEETS PROVIDE GENERAL SEQUENCE OPTIONS FOR INSTALLATION OF THE PROPOSED WATER AND SEWER LINES. CONTRACTOR SHALL PROVIDE A CONSTRUCTION SEQUENCE FOR ALL WATER LINE AND SEWER LINE SEGMENTS AND **KILLOUTS PRIOR TO INSTALLATION FOR REVIEW AND APPROVAL BY ENGINEER.** CONTRACTOR SHALL UPDATE CONSTRUCTION SEQUENCES WHERE ACTUAL CONDITIONS **REQUIRE AJDUSTMENTS OR ALTERATIONS TO** THE PLANNED WORK. CONSTRUCTION SEQUENCE OPTIONS THAT ARE PROVIDED ARE INTENDED TO MINIMIZE IMPACTS TO WATER AND SEWER **OPERATIONS. INSTALLATION SHALL NOT** BEGIN UNTIL AN APPROVED SEQUENCE PLAN IS IN PLACE.

