TOTAL BILL OF MATERIALS																
BRIDGE NO.	GROOVING BRIDGE FLOORS	POLLUTION CONTROL	CLASS III SURFACE PREPARATION	CONCRETE REPAIRS	SHOTCRETE REPAIRS	EPOXY RESIN INJECTION	CLEANING AND PAINTING EXISTING WEATHERING STEEL FOR BRIDGE NO	CLEANING AND REPAINTING OF BRIDGE NO	PAINTING CONTAINMENT FOR BRIDGE NO	VOLUMETRIC MIXER	FOAM JOINT SEALS FOR PRESERVATION	POURABLE SILICONE JOINT SEALANT	LATEX MODIFIED CONCRETE OVERLAY- EARLY STRENGTH	LATEX MODIFIED CONCRETE OVERLAY- VERY EARLY STRENGTH	ELASTOMERIC CONCRETE FOR PRESERVATION	REPAIRS TO PRESTRESSED CONCRETE GIRDERS
	SQ.FT.	LUMP SUM	SQ. YDS.	CU.FT.	CU.FT.	LIN.FT.	LUMP SUM	LUMPSUM	LUMP SUM	LUMP SUM	LIN.FT.	LIN.FT.	CU. YDS.	CU. YDS.	CU.FT.	CU.FT.
330078	-	LUMP SUM	-	30.5	312.8	75.0	-	LUMPSUM	LUMP SUM	-	270.0	180.0	-	-	112.5	-
330227	26,714	LUMP SUM	90.2	9.9	302 . 5	91.1	-	-	LUMP SUM	LUMP SUM	449.2	224.6	-	247.2	165.0	23.4
330392	26,354	LUMP SUM	-	-	56.9	56.5	LUMP SUM	-	LUMP SUM	-	282.0	188.0	171.3	-	70.5	-
TOTAL	53,068	LUMP SUM	90.2	40.4	672.2	222.6	LUMP SUM	LUMPSUM	LUMP SUM	LUMP SUM	1001.2	592.6	171.3	247.2	348.0	23.4

	TOTAL BILL OF MATERIALS														
BRIDGE NO.	BEAM REPAIR PLATING	BRIDGE JOINT DEMOLITION	CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT	EPOXY COATING	EPOXY COATING CONCRETE GIRDER ENDS	HYDRO- DEMOLITION OF BRIDGE DECK	PLACING & FINISHING OF LATEX MODIFIED CONCRETE OVERLAY- EARLY STRENGTH	PLACING & FINISHING OF LATEX MODIFIED CONCRETE OVERLAY- VERY EARLY STRENGTH	SCARIFYING BRIDGE DECK	SHOTBLASTING BRIDGE DECK	SILANE DECK TREATMENT	BEARING REPLACEMENT	CLEANING & PAINTING EXISTING BEARINGS WITH HIGH RATIO CALCIUM SULFONATE	STEEL BEARING KEEPER ANGLE ASSEMBLY	TYPE I BRIDGE JACKING BRIDGE NO
	LBS.	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	SQ. YDS.	SQ. YDS.	SQ. YDS.	SQ. YDS.	SQ. YDS.	SQ. YDS.	EA.	EA.	EA.	EA.
330078	98.1	450.0	6.3	981.5	-	-	-	-	-	2,309	2,309	-	-	2	5
330227	-	660.0	-	1311.6	3098.0	3,245	-	3,245	3,245	-	-	6	168	-	6
330392		470.0	-	1269.0	-	3,084	3,084	-	3,084	-	-	-	-	8	-
TOTAL	98.1	1580.0	6.3	3562.1	3098.0	6,329	3,084	3,245	6,329	2,309	2,309	6	168	10	11

PROJECT NO. 15BPR.55

FORSYTH COUNTY

BRIDGE NO. 330078, 330227,
330392



STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

RALEIGH

TOTAL BILL OF MATERIAL

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED 2 A SHEET NO.

REVISIONS

SHEET NO.

BY: DATE: NO. BY: DATE: S-2

TOTAL SHEETS

79

 DRAWN BY :
 M. G. SHAIKH
 DATE :
 10/2021

 CHECKED BY :
 A. SORSENGINH
 DATE :
 11/2021