


BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETER-MINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

## TEMPORARY DRAINAGE AT END BENT

DRAWN BY :	N. ROHRBAUGH		DATE : _	06/2021
CHECKED BY : _	A.FORFA		DATE :	06/2021
DESIGN ENGINE	ER OF RECORD :	A. FORFA	DATE : .	09/2021



PILE SPLICE DETAILS

3'-3" 1'-0" , 8" , 11" , FILL — FACE 2" CL. (MIN.) 5-#4B4-5-#9B2 — SECTION THRU B-B

Suite 175 Cary, NC 27518 984-275-2490 NC License No. F-1320

042449 Olexander Forja 11/23/2021 8000 Regency Parkway DOCUMENT NOT CONSIDERED FINAL UNLESS ALL

SIGNATURES COMPLETED

BR-0033 PROJECT NO.\_\_ McDOWELL COUNTY STATION: 16+11.51 -L-

SHEET 3 OF 3

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION SUBSTRUCTURE

END BENT 2

SHEET NO. **REVISIONS** S-28 NO. BY: DATE: DATE: BY: TOTAL SHEETS