



**NOTES:**

- 1) NOTIFY THE CITY OF GREENVILLE ASSISTANT TRAFFIC ENGINEER, STACEY PIGFORD, AT (252) 329-4678 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE ASSISTANT TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2) CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENTS FOR USE IN THE CASE THAT THE EXISTING SIGNAL SYSTEM CABLE IS DISCONNECTED OR DAMAGED DURING SIGNAL CABINET CHANGE OUT. REPLACE ANY DAMAGED CABLE WITH NEW 12-FIBER CABLE AND RESPLICE ACCORDING TO THE RECORDED SPLICE ARRANGEMENTS. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 3) DO NOT DISTURB EXISTING CONDUIT OR COMMUNICATIONS CABLE. DO NOT DISTURB OR DISCONNECT INTERCONNECT CENTER DURING SIGNAL CABINET CHANGE OUT.

**TMP PHASE 1**

DOCUMENT NOT CONSIDERED FINAL  
UNLESS ALL SIGNATURES COMPLETED

	<p><b>COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS</b></p>							
	<p>DIVISION 02 PITT COUNTY GREENVILLE</p> <p>PLAN DATE: FEBRUARY 2018 REVIEWED BY: <i>L. N. Avery</i></p> <p>PREPARED BY: H. T. BERGGREN, EI</p>	<p>REVISIONS</p> <table border="1"> <tr> <th>NO.</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </table>		NO.	DATE	DESCRIPTION		
NO.	DATE	DESCRIPTION						
<p>750 N. Greenfield Pkwy., Garner, NC 27529</p> <p>SCALE 0 50 1" = 50'</p>	<p>INIT. DATE</p> <p><i>Mohd Islami</i> 3/5/2018</p>		<p>DATE</p>					