PROJECT REFERENCE NO.	SHEET NO.
B-5737	EC-3

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

STRAW MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-DET-	19+50	20+20	RT	275
				SUBTOTAL	275
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					7300
				TOTAL	7575
				SAY	8000 SY

EXCELSIOR MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-DET-	18+50	19+50	RT	215
				SUBTOTAL	215
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					100
				TOTAL	315
				SAY	500 SY

8/17/99
Q:\RA\10011-103\B5737\Roadside\Sheets\B5737_REU_EC03_PSH_03.dgn