

Revised Preliminary Site Assessment Report

**Parcel 85
US 17 North of NC 171 to Multi-lanes South of Williamston
9985 U.S. Highway 17 North
Beaufort County, North Carolina
WBS Number 35494.1.1
TIP Number R-2511
NCDOT Parcel No. 85
Beaufort County PIN 5771-02-1103**

Prepared for


**North Carolina Department of Transportation
Geotechnical Engineering Unit
GeoEnvironmental Section
Raleigh, North Carolina**

Prepared by

**Duncklee & Dunham, P.C.
Cary, North Carolina**

June 14, 2019





DUNCKLEE
& DUNHAM

ENVIRONMENTAL GEOLOGISTS & ENGINEERS
511 KEISLER DRIVE – SUITE 102
CARY, NORTH CAROLINA 27518
OFFICE: (919) 858-9898
WWW.DUNCKLEEDUNHAM.COM

VIA EMAIL TO: dgli@ncdot.gov

June 14, 2019

Mr. Dennis Li, L.G., PhD
North Carolina Department of Transportation
Geotechnical Engineering Unit
GeoEnvironmental Section
1589 Mail Service Center
Raleigh, North Carolina 27699-1589

Reference: **Revised Preliminary Site Assessment Report
Parcel 85
US 17 North of NC 171 to Multi-lanes South of Williamston
9985 U.S. Highway 17 North
Beaufort County, North Carolina
TIP Number R-2511
WBS Number 35494.1.1
NCDOT Parcel No. 85
Beaufort County PIN 5771-02-1103**

Dear Mr. Li:

Duncklee & Dunham, P.C. (Duncklee & Dunham) is pleased to submit this *Revised Preliminary Site Assessment Report* for the referenced site. The objective of our services was to assist the North Carolina Department of Transportation (NCDOT) – Geotechnical Engineering Unit with identifying potential environmental concerns within the rights-of-way and/or easements of the above-referenced site. This work is consistent with the NCDOT's Request for Technical and Cost Proposal dated March 5, 2019 and our *Revised Technical and Cost Proposal for Preliminary Site Assessment* dated May 14, 2019. Based on the findings from this work, Duncklee & Dunham recommends submitting this report to the Washington Regional Office of the North Carolina Department of Environmental Quality.


Please contact Rick Kolb at rkolb@dunckleedunham.com or (919) 858-9898, ext. 111 if you have any questions or require additional information.

Sincerely,

Duncklee & Dunham, P.C.




Alec N. Dziwanowski, G.I.T.
Staff Geologist II



Richard A. Kolb, L.G.
Senior Geologist
North Carolina License No. 1153



Senior Peer Review



Andrew M. Rodak, P.E.
Senior Engineer/Director of Engineering
North Carolina No. 24576

Attachment: Revised Preliminary Site Assessment Report



Table of Contents

1	Introduction	1
2	History	1
3	Methods	1
3.1	Geophysics	2
3.2	Soil Borings	2
3.3	Groundwater	3
4	Results	3
4.1	Geophysics	3
4.2	Soil Borings	3
4.3	Groundwater	3
5	Conclusions	4
5.1	Geophysics	4
5.2	Soil Sampling	4
5.3	Groundwater Sampling.....	4
6	Recommendations	4

Tables

1	Coordinates of Soil Borings
2	Summary of Soil Screening and Soil Test Results
3	Summary of Groundwater Test Results

Figures

1	Site Topographic Map
2	Site Map
3	Site Map with Results
4	Legend for Plan Sheet Figures

Appendices

A	Photographic Log
B	Boring Logs
C	Geophysical Survey Report
D	Laboratory Reports



Revised Preliminary Site Assessment Report
Parcel 85
US 17 North of NC 171 to Multi-lanes South of Williamston
9985 U.S. Highway 17 North
Beaufort County, North Carolina
TIP Number R-2511
WBS Number 35494.1.1
NCDOT Parcel No. 85
Beaufort County PIN 5771-02-1103
June 14, 2019

1 Introduction

Duncklee & Dunham, P.C. (Duncklee & Dunham) conducted a Preliminary Site Assessment (PSA) on the referenced site located on the western side of U.S. Highway 17 (US 17) north of Washington in Beaufort County, North Carolina (Figures 1 and 2). The North Carolina Department of Transportation (NCDOT) plans to widen the two-lane portion of US 17 between Washington and Williamston, North Carolina. Our work is consistent with the NCDOT's *Request for Technical and Cost Proposal* dated March 5, 2019 and our *Revised Technical and Cost Proposal* dated May 14, 2019. The objective of this work was to assist the NCDOT – Geotechnical Engineering Unit with identifying potential environmental concerns within the rights-of-way and/or easements of the above-referenced site. Our services included a geophysical survey to identify subsurface metallic features such as underground storage tank (UST) systems, and the advancement of six soil borings to test for the presence of contaminants in the areas where the new roadway will be constructed, along rights-of-way for NCDOT, and at new utility easements.

2 History

The NCDOT prepared a Hazardous Materials Report dated November 14, 2011 that identified the site as a former gasoline station, which is now vacant. After review of the incident list of the UST Section of the North Carolina Department of Environment and Natural Resources (NCDENR, now the North Carolina Department of Environmental Quality – NCDEQ), the NCDOT determined that there were no known incidents associated with the site.

3 Methods

Duncklee & Dunham called NC811 on March 26, 2019 and requested utilities to be marked in the areas of investigation. NC811 notified the Beaufort County Water Department, USIC Locating Services, CenturyLink, MCNC, Piedmont Natural Gas, Suddenlink Communications, and the City of Washington. The clearance was valid through April 16, 2019.

Duncklee & Dunham reviewed regulatory records on NCDEQ's Laserfiche website and did not find records for this parcel. However, ECS Southeast, LLP (ECS), under contract with NCDOT, prepared a PSA report on June 18, 2018 for 10052 US 17, a parcel that adjoins Parcel 85 to the east. ECS determined that a leak from the UST system at the site had likely occurred, based on a groundwater sample collected from a monitoring well installed near the former dispensing island on the western side of the property that exhibited volatile organic compounds (VOCs) at concentrations that exceeded the North Carolina groundwater quality standards promulgated in Title 15A, Subchapter 2L, Section .0202 of the North Carolina Administrative Code (15A NCAC 2L .0202; the "2L standards").



During site reconnaissance, Duncklee & Dunham interviewed Rusty Roberson, a relative of the owner of the subject site. Mr. Roberson stated that two USTs used to store high-test and regular gasoline were formerly located near the southeastern corner of the building. He was not aware of when the tanks were installed or closed out. Mr. Roberson also stated that the store was formerly located closer the intersection of West Bear Grass Road and US 17 prior to the 1950s. Duncklee & Dunham did not observe unusual features or features indicative of a UST at this intersection or on the northern portion of the parcel.

3.1 Geophysics

ESP Associates (ESP), under contract to Duncklee & Dunham, conducted a geophysical survey at the site on April 1, 5, and 6, 2019. ESP used a Geonics EM61 MK2[®] metal detector equipment with a DGPS instrument to locate buried metal objects, and then used a Sensors and Software Noggin[®] GPR instrument with a 250 MHz antenna to image selected anomalies.

3.2 Soil Borings

Troxler Geologic Services, Inc. (Troxler), under contract to Duncklee & Dunham, used a Geoprobe[®] equipped with direct-push technology to advance six soil borings, nos. B-10 through B-15 on April 8, 2019. The locations of these borings are shown on Figure 2. Troxler advanced B-10 through B-12 near the former pump islands on the eastern side of the building (Photograph No. 1 in Appendix A), and B-13 through B-15 at the former location of the UST pit near the southeastern corner of the building (Photograph No. 2). Troxler advanced B-10 to a depth of 8 feet below land surface (bls) and the remaining borings to a depth of 4 feet bls. We encountered the water table at a depth of 3.25 feet bls. Duncklee & Dunham used a Trimble Geo 7x[®] handheld data collector to determine the location of each boring. Approximate Northings, Eastings, and elevations above sea level for these borings are in Table 1.

Troxler collected soil samples in new acetate sleeves, each 4 feet long. A majority of the soil samples were comprised of dark gray to black, sandy, silty clay. Boring logs are provided in Appendix B. Duncklee & Dunham collected representative samples of native material at selected intervals in each soil boring and stored the samples in twin Ziploc[®] bags. After allowing one of the bags to sit untouched in the sun and the other in the shade for approximately 15 minutes, we used a photoionization detector (PID) to screen the headspace in each bag left in the sun for volatile organic compounds (VOCs). We recorded the soil-screening results in the field log. Table 2 summarizes the screening results. The soil samples collected above the water table were not stained and did not exhibit petroleum odors except for the sample collected from B-10 at 2.5 feet bls, which exhibited a petroleum odor and a PID reading of 2.9 parts per million (ppm). The PID readings of the other soil samples ranged from 0.2 to 5.2 ppm, indicative of background concentrations. The PID readings of the samples collected from 4 to 8 feet bls did not exceed 5.2 ppm, except the readings taken from B-14 and B-15 at 4 feet bls, which were 72.6 ppm and 563 ppm, respectively. These samples exhibited a petroleum odor.

Duncklee & Dunham collected a soil sample from B-15 at 2.5 feet bls to be tested in the laboratory because of all the samples above the water table, this sample exhibited the highest concentration of VOCs on the PID. We placed the soil sample in the other twin bag in a laboratory-supplied container, placed the container in a cooler with ice, and shipped the cooler under chain of custody to RED Lab, LLC (RED Lab) in Wilmington, North Carolina. The laboratory received the cooler and tested the samples for total petroleum hydrocarbons (TPH) – diesel range organics (DRO) and TPH – gasoline range organics (GRO) using Ultraviolet Fluorescence methodology.



3.3 Groundwater

The sample from boring B-15 collected below the water table exhibited the highest anomalous response on the PID. Therefore, Troxler constructed temporary monitoring well TW-2 in boring B-15 to a depth of 4 feet bls using Screen Point 16 groundwater sampling rods. Troxler screened the well from 0 to 4 feet bls. Duncklee & Dunham purged groundwater from the well using a peristaltic pump with a new length of low-density polyethylene tubing and silicon tubing for the pump head. Once the purge water appeared clear, Duncklee & Dunham sampled TW-2 with a peristaltic pump. We placed the groundwater sample in laboratory-supplied containers, placed the containers in a cooler with ice, and brought the cooler back to our office under chain of custody. A courier for Pace National Laboratory (Pace) shipped the cooler by overnight express mail to their laboratory in Mt. Juliet, Tennessee. The laboratory tested the groundwater samples for VOCs according to EPA Method 6200B, semivolatile organic compounds (SVOCs) according to EPA Method 625, and volatile petroleum hydrocarbons (VPH) according to the method of the Massachusetts Department of Environmental Protection (MADEP). In accordance with NCDEQ guidance, Duncklee & Dunham discharged the purge water on the ground around TW-2 once the groundwater sample was collected.

4 Results

4.1 Geophysics

ESP's *Geophysical Survey* report dated May 9, 2019 is provided in Appendix C. ESP identified six magnetic anomalies that they attributed to cultural features on the ground surface or buried, metallic debris and/or utilities. The ground penetrating radar (GPR) survey confirmed the electromagnetic (EM) anomalies were associated with unknown buried metallic features and not USTs.

4.2 Soil Borings

Table 2 and Figure 3 summarize the laboratory results for the soil sample collected from soil boring B-15. The laboratory report is in Appendix E. RED Lab did not detect TPH-GRO in the sample and detected TPH-DRO at a concentration of 1.8 milligrams per kilogram (mg/kg). This concentration does not exceed the action level of 100 mg/kg established by NCDEQ. RED Lab identified the hydrocarbon fingerprint of the TPH-DRO in B-6 as "very degraded petroleum hydrocarbons (PHC)," which is indicative of a petroleum product that had a substantial amount of time to degrade.

4.3 Groundwater

Table 3 and Figure 3 summarize the laboratory results for the sample collected from TW-2. Pace detected 18 petroleum constituents in this groundwater sample; the concentrations of 13 analytes exceeded the respective 2L Standards but did not the respective Gross Contamination Levels. The laboratory report is in Appendix D.



5 Conclusions

5.1 Geophysics

ESP identified six magnetic anomalies on Parcel 85 and attributed each to cultural features on the ground surface or buried, metallic debris and/or utilities. ESP did not identify anomalies indicative of abandoned USTs or buried metal drums. The GPR survey confirmed the remaining EM anomalies to be associated with suspected, buried, metallic debris, and/or utilities, and not USTs.

5.2 Soil Sampling

The soil sample from B-15 did not exhibit TPH-DRO at a concentration that exceeded NCDEQ's action level. Duncklee & Dunham did not detect petroleum odors or observe stains in the other soil samples collected above the water table. These results suggest the fuel dispensers formerly used at the site were not a contaminant source. We do not have evidence that soil on the site exhibits petroleum constituents at concentrations that exceed the action levels established by NCDEQ.

5.3 Groundwater Sampling

Most of the analytes detected in the groundwater sample were VOCs and VPH fractions, which suggests that a majority of the contaminants were derived from a low boiling point fuel such as gasoline. The estimated extent of contamination is shown on Figure 3. The shape of the plume reflects what we estimate is the direction of groundwater flow. These test results show the USTs formerly at the site were the probable source of the contamination.

The PSA conducted by ECS at 10052 US 17 reported similar analytes at similar concentrations to those detected in the groundwater sample collected from the subject site. Thus, the plumes at these two sites may be comingled. Additional assessment is required to determine if these two plumes have comingled, and to determine the extent of groundwater contamination.

6 Recommendations

Duncklee & Dunham recommends submitting this report to the Washington Regional Office of the NCDEQ.



Tables

Table 1
Coordinates of Soil Borings
Parcel 85
Beaufort County, North Carolina
TIP No. R-2511; WBS No. 35494.1.1

Boring Identification	Northing (feet)	Easting (feet)	Elevation (feet asl)
B-10	711903.004	2570149.754	61.467
B-11	711890.585	2570144.408	61.340
B-12	711893.902	2570154.213	61.909
B-13	711887.620	2570124.680	60.231
B-14	711890.506	2570115.267	61.287
B-15	711884.039	2570118.400	61.782

Notes:

Coordinate system NAD83 NC State Plane - Survey Feet

GPS data collected using a Trimble Geo 7x handheld data collector

GPS data are approximate

Table 2
Summary of Soil Screening and Soil Test Results
Parcel 85
Beaufort County, North Carolina
TIP Number R-2511; WBS No. 35494.1.1

Soil Screening Results		
Boring Identification	Depth (feet bls)	PID Reading (ppm)
B-10	1.5	0.3
	2.5	2.9
	6	0.6
B-11	1	1.1
	2	0.5
B-12	1.5	0.2
	2.5	0.5
B-13	1	0.6
	2.5	0.2
	4	5.2
B-14	1.5	0.2
	2.5	2.6
	4	72.6
B-15	1	1.1
	2.5*	5.2
	4	563

Soil Test Results		
Sample Identification	TPH-GRO (mg/kg)	TPH-DRO (mg/kg)
B-15	<0.63	1.8

Notes:

Soil sample and PID data collected on April 8, 2019

** - Sample selected from this interval for laboratory testing*

TPH-GRO - Total Petroleum Hydrocarbons-Gasoline Range Organics

TPH-DRO - Total Petroleum Hydrocarbons-Diesel Range Organics

NCDEQ Action Level for TPH-GRO - 50 mg/kg

NCDEQ Action Level for TPH-DRO - 100 mg/kg

mg/kg - Milligrams per kilogram

bls - Feet below land surface

ppm - Parts per million

PID - Photoionization detector

Result in bold exceeds the report limit

Results shaded in blue were collected from below the water table

<# - Analyte not detected at a concentration that exceeds the reporting limit shown

Table 3
Summary of Groundwater Test Results
Parcel 85
Beaufort County, North Carolina
TIP No. R-2511; WBS No. 35494.1.1

Sample Identification →			TW-2	
Analyte	2L Standard	GCL	Value	Q
<i>Volatile Organic Compounds by EPA Method 6200B</i>				
Benzene	1	5,000	1,770	
n-Butylbenzene	70	6,900	36.2	
sec-Butylbenzene	70	8,500	21.9	J
Ethylbenzene	600	84,500	2,060	
Isopropylbenzene	70	25,000	106	
p-Isopropyltoluene	NE	NE	9.76	J
Naphthalene	6	6,000	446	
n-Propylbenzene	70	30,000	319	
Toluene	600	260,000	14,000	
1,2,4-Trimethylbenzene	400	28,500	2,260	
1,3,5-Trimethylbenzene	400	25,000	551	
Xylenes-total	500	85,500	9,490	
<i>Semivolatile Organic Compounds by EPA Method 625.1</i>				
Naphthalene	6	6,000	124	
Diethyl phthalate	NE	NE	14.6	
Phenol	30	30,000	2.63	J
<i>Volatile Petroleum Hydrocarbons by MADEP Method</i>				
C5-C8 Aliphatics	400	NE	42,200	
C9-C12 Aliphatics	700	NE	25,200	
C9-C10 Aromatics	200	NE	10,100	

Notes:

Units are μ g/L

Sample collected on April 8, 2019

2L Standard - North Carolina Groundwater Quality Standard (15A NCAC 2L .0202)

GCL - North Carolina Gross Contamination Levels for groundwater

Result in bold exceeds the reported detection limit

Result with shaded cell exceeds the 2L Standard


MADEP - Massachusetts Department of Environmental Protection

NE - Not Established

Q - Qualifier

J - Estimated concentration above the method detection limit and below the reported detection limit

Figures



Parcel 85

DUNCKLEE & DUNHAM
ENVIRONMENTAL GEOLOGISTS & ENGINEERS


511 Keisler Drive Suite 102 (919) 858-9898
Cary, North Carolina 27518 www.dunckleedunham.com
NC Eng. License No. C-3559 NC Geo. License No. C-261

Site Topographic Map
NCDOT Parcel 85
Beaufort County, North Carolina

Drawn By: SBM	Checked By: EDB	Project Number: R-2511	Date: 4/30/2019	References: USGS US TOPO 7.5 Minute Old Fort Quadrangle
Scale: (Original) 1" = 24,000'	Size: 8.5" x 11"	Layers: N/A	Filename: R:\Projects\0171040.300 (Duncklee and Dunham R-2511 NCDOT Geophysics)\CADD\R2511_Geo_TopoMap_85	

Figure

1



Site Map			
9985 US 17 N Washington, Beaufort County, NC 27899			
Drawn By:	Checked By:	Project Number:	Date:
SBM	EDB	R-2511	5/3/19
Scale:	Size:	Layers:	Filename:
1" = 20'	11" x 17"	N/A	R:\Projects\H\11040_300 (Duncklee and Dunham R2511 NCDOT Geophysics)\CADD\R2511_Geo_SiteMap_85
References:	R2511_NCDOT_FS.dgn R2511_Top.dwg		

Figure
 2

TW-2 (ug/L)	
Benzene	1,770
n-Butylbenzene	36.2
sec-Butylbenzene	21.9 J
Ethylbenzene	2,060
Isopropylbenzene	106
p-Isopropyltoluene	9.76 J
Naphthalene (6200B)	446
n-Propylbenzene	319
Toluene	14,000
1,2,4-Trimethylbenzene	2,260
1,3,5-Trimethylbenzene	551
Xylenes, total	9,490
Naphthalene (625.1)	124
Diethyl phthalate	14.6
Phenol	2.63 J
C5-C8 Aliphatics	42,200
C9-C12 Aliphatics	25,200
C9-C10 Aromatics	10,100


Note:

TPH-DRO - Total Petroleum Hydrocarbons-Diesel Range Organics

2L Standard - North Carolina Groundwater Quality Standard (15A NCAC 2L.0202)

Shaded Result - Exceeds the 2L Standard

J - Estimated concentration above the method detection limit and below the reported detection limit



DUNCKLEE & DUNHAM
 ENVIRONMENTAL GEOLOGISTS & ENGINEERS

511 Keisler Drive Suite 102
 Cary, North Carolina 27518
 NC Eng. License No. C-3559

(919) 858-9898
 www.dunckleedunham.com
 NC Geo. License No. C-261

Site Map with Results			
9985 US 17 N Washington, Beaufort County, NC 27899			
Drawn By:	Checked By:	Project Number:	Date:
SBM	EDB	R-2511	5/3/19
Scale:	Size:	Layers:	Filename:
1" = 20'	11" x 17"	N/A	R:\Projects\H\11040_300\DWG\Map\K2511_Geo_SiteMapK2511.ncdgeo

Figure
3

STATE OF NORTH CAROLINA, DIVISION OF HIGHWAYS CONVENTIONAL PLAN SHEET SYMBOLS

Note: Not to Scale *S.U.E. = *Subsurface Utility Engineering*

BOUNDARIES AND PROPERTY:

State Line	-----
County Line	-----
Township Line	-----
City Line	-----
Reservation Line	-----
Property Line	-----
Existing Iron Pin	○
Computed Property Corner	⊗
Property Monument	⊠
Parcel/Sequence Number	②③
Existing Fence Line	-x-x-x-
Proposed Woven Wire Fence	○
Proposed Chain Link Fence	□
Proposed Barbed Wire Fence	◇
Existing Wetland Boundary	-----
Proposed Wetland Boundary	-----
Existing Endangered Animal Boundary	-----
Existing Endangered Plant Boundary	-----
Existing Historic Property Boundary	-----
Known Contamination Area: Soil	⊗-s-⊗
Potential Contamination Area: Soil	⊗-s-⊗
Known Contamination Area: Water	⊗-w-⊗
Potential Contamination Area: Water	⊗-w-⊗
Contaminated Site: Known or Potential	⊗

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	○
Sign	○
Well	⊕
Small Mine	⊗
Foundation	⊠
Area Outline	⊠
Cemetery	⊠
Building	⊠
School	⊠
Church	⊠
Dam	⊠

HYDROLOGY:

Stream or Body of Water	-----
Hydro, Pool or Reservoir	-----
Jurisdictional Stream	-----
Buffer Zone 1	-----
Buffer Zone 2	-----
Flow Arrow	-----
Disappearing Stream	-----
Spring	-----
Wetland	-----
Proposed Lateral, Tail, Head Ditch	-----
False Sump	-----

RAILROADS:

Standard Gauge	-----
RR Signal Milepost	-----
Switch	-----
RR Abandoned	-----
RR Dismantled	-----

RIGHT OF WAY & PROJECT CONTROL:

Secondary Horiz and Vert Control Point	◆
Primary Horiz Control Point	◇
Primary Horiz and Vert Control Point	⬢
Exist Permanent Easment Pin and Cap	◇
New Permanent Easement Pin and Cap	◆
Vertical Benchmark	⊠
Existing Right of Way Marker	△
Existing Right of Way Line	-----
New Right of Way Line	-----
New Right of Way Line with Pin and Cap	-----
New Right of Way Line with Concrete or Granite RW Marker	-----
New Control of Access Line with Concrete CA Marker	-----
Existing Control of Access	-----
New Control of Access	-----
Existing Easement Line	-----
New Temporary Construction Easement	-----
New Temporary Drainage Easement	-----
New Permanent Drainage Easement	-----
New Permanent Drainage / Utility Easement	-----
New Permanent Utility Easement	-----
New Temporary Utility Easement	-----
New Aerial Utility Easement	-----

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	-----
Existing Curb	-----
Proposed Slope Stakes Cut	-----
Proposed Slope Stakes Fill	-----
Proposed Curb Ramp	-----
Existing Metal Guardrail	-----
Proposed Guardrail	-----
Existing Cable Guiderail	-----
Proposed Cable Guiderail	-----
Equality Symbol	⊕
Pavement Removal	-----

VEGETATION:

Single Tree	⊗
Single Shrub	⊗

Hedge	-----
Woods Line	-----
Orchard	-----
Vineyard	-----

EXISTING STRUCTURES:

MAJOR:	-----
Bridge, Tunnel or Box Culvert	-----
Bridge Wing Wall, Head Wall and End Wall	-----
MINOR:	-----
Head and End Wall	-----
Pipe Culvert	-----
Footbridge	-----
Drainage Box: Catch Basin, DI or JB	-----
Paved Ditch Gutter	-----
Storm Sewer Manhole	-----
Storm Sewer	-----

UTILITIES:

POWER:	-----
Existing Power Pole	-----
Proposed Power Pole	-----
Existing Joint Use Pole	-----
Proposed Joint Use Pole	-----
Power Manhole	-----
Power Line Tower	-----
Power Transformer	-----
U/G Power Cable Hand Hole	-----
H-Frame Pole	-----
U/G Power Line LOS B (S.U.E.*)	-----
U/G Power Line LOS C (S.U.E.*)	-----
U/G Power Line LOS D (S.U.E.*)	-----

TELEPHONE:

Existing Telephone Pole	-----
Proposed Telephone Pole	-----
Telephone Manhole	-----
Telephone Pedestal	-----
Telephone Cell Tower	-----
U/G Telephone Cable Hand Hole	-----
U/G Telephone Cable LOS B (S.U.E.*)	-----
U/G Telephone Cable LOS C (S.U.E.*)	-----
U/G Telephone Cable LOS D (S.U.E.*)	-----
U/G Telephone Conduit LOS B (S.U.E.*)	-----
U/G Telephone Conduit LOS C (S.U.E.*)	-----
U/G Telephone Conduit LOS D (S.U.E.*)	-----
U/G Fiber Optics Cable LOS B (S.U.E.*)	-----
U/G Fiber Optics Cable LOS C (S.U.E.*)	-----
U/G Fiber Optics Cable LOS D (S.U.E.*)	-----

WATER:

Water Manhole	-----
Water Meter	-----
Water Valve	-----
Water Hydrant	-----
U/G Water Line LOS B (S.U.E.*)	-----
U/G Water Line LOS C (S.U.E.*)	-----
U/G Water Line LOS D (S.U.E.*)	-----
Above Ground Water Line	-----

TV:

TV Pedestal	-----
TV Tower	-----
U/G TV Cable Hand Hole	-----
U/G TV Cable LOS B (S.U.E.*)	-----
U/G TV Cable LOS C (S.U.E.*)	-----
U/G TV Cable LOS D (S.U.E.*)	-----
U/G Fiber Optic Cable LOS B (S.U.E.*)	-----
U/G Fiber Optic Cable LOS C (S.U.E.*)	-----
U/G Fiber Optic Cable LOS D (S.U.E.*)	-----

GAS:

Gas Valve	-----
Gas Meter	-----
U/G Gas Line LOS B (S.U.E.*)	-----
U/G Gas Line LOS C (S.U.E.*)	-----
U/G Gas Line LOS D (S.U.E.*)	-----
Above Ground Gas Line	-----

SANITARY SEWER:

Sanitary Sewer Manhole	-----
Sanitary Sewer Cleanout	-----
U/G Sanitary Sewer Line	-----
Above Ground Sanitary Sewer	-----
SS Forced Main Line LOS B (S.U.E.*)	-----
SS Forced Main Line LOS C (S.U.E.*)	-----
SS Forced Main Line LOS D (S.U.E.*)	-----

MISCELLANEOUS:

Utility Pole	-----
Utility Pole with Base	-----
Utility Located Object	-----
Utility Traffic Signal Box	-----
Utility Unknown U/G Line LOS B (S.U.E.*)	-----
U/G Tank; Water, Gas, Oil	-----
Underground Storage Tank, Approx. Loc.	-----
A/G Tank; Water, Gas, Oil	-----
Geoenvironmental Boring	-----
U/G Test Hole LOS A (S.U.E.*)	-----
Abandoned According to Utility Records	-----
End of Information	-----

DUNCKLEE & DUNHAM
ENVIRONMENTAL GEOLOGISTS & ENGINEERS

511 Keisler Drive Suite 102
Cary, North Carolina 27518
www.dunckleedunham.com
NC Eng. License No. C-3559
(919) 858-9898

Legend for Plan Sheet Figures	
NCDOT Parcel 85 Beaufort County, North Carolina	
Drawn By: SBM	Checked By: EDB
Project Number: R-2511	Date: 5/3/2019
Layers: N/A	References: NCDOT PLAN SHEET SYMBOLOLOGY, Microstation Cell, 12/2/2016
Scale: N/A	Filename: R:\Projects\9 (1)\1040300 (Duncklee and Dunham R-2511 NCDOT Geophysics)\ CAD\R2511_Geo_Legend_N5

Appendix A

PHOTOGRAPHIC LOG

Client Name:

NCDOT-GeoEnvironmental

Site Location:

R-2511 Parcel 85; Beaufort County, North Carolina

Project No.

201939

Photo No.

1

Date:

4/8/19

Direction of Photo:

Southwest

Description:

Soil borings B-10 through B-12 were advanced near the foundations of the former fuel dispensers. West Bear Grass Road is in the background.




Photo No.

2

Date:


4/8/19

Direction of Photo:

Southeast

Description:

Soil borings B-13 through B-15 were advanced near the former location of the UST pit. U.S Highway 17 is in the background, and Ben Troxler of Troxler Geologic is pictured.



Appendix B

Boring/Well Construction Log



**DUNCKLEE
& DUNHAM**

I. D. Number	B-10	Purpose	Soil Boring
Project Name	Beaufort & Martin Co. - Site 8	Contractor	Troxler geologic
Project No.	201939	Registration No.	2511
Geologist	Alec Dziwanowski	Driller	Ben Troxler
Start Date	4/3/19	Complete Date	4/3/19
		Equipment	Geoprobe

Drilling Method: direct-push
 Comments: WT at 3.25' b/s noted
 Petroleum odor observed at 3.25'-8' b/s

Well Construction Information		Depth From - To (ft.)	Lithology	FID / PID (ppm) @ Depth (ft.)
Borehole Diameter	WT @ 3.25'	0-3.5	dark gray, sandy, silty CLAY ← bag 1	0.3 @ 1.5'
Riser Type		3.5-4	black, sandy, silty CLAY	NA
Diameter		4-7	dark gray, silty CLAY with sand	0.6 @ 6'
Screen Type		7-8	light gray, sandy CLAY	NA
Diameter				
Riser Interval				
Screen Interval				
Slot Size				
Grout Type				
Interval				
Bentonite Type				
Interval				
Filter Pack				
Interval				
Total Depth				
R.P. Elevation				
Datum				
Water Level Information				
Date	W.L. Below R.P.			

Petroleum odor?
 bag 2:
 2.4 @ 2.5'
 no
 yes

R.P. = Reference Point W.L. = Water Level TBM = Temporary Benchmark MSL = Mean Sea Level

Boring/Well Construction Log



**DUNCKLEE
& DUNHAM**

I. D. Number	B-11	Purpose	Soil boring
Project Name	Beaufort & Martin Co. - Site 8	Contractor	Troxler Geologic
Project No.	201939	Registration No.	2511
Geologist	Alec DeWanowski	Driller	Ben Troxler
Start Date	4/8/19	Complete Date	4/8/19
		Equipment	Geoprobe

Drilling Method: direct - push
 Comments: WT at 3.25
 No petroleum odors/stains

Well Construction Information		Depth From - To (ft.)	Lithology	FID / PID (ppm) @ Depth (ft.)
Borehole Diameter		0-4	dark gray, sandy, silty CLAY	1.1 @ 1'
Riser Type				0.5 @ 2'
Diameter				
Screen Type				
Diameter				
Riser Interval				
Screen Interval				
Slot Size				
Grout Type				
Interval				
Bentonite Type				
Interval				
Filter Pack				
Interval				
Total Depth				
R.P. Elevation				
Datum				
Water Level Information				
Date	W.L. Below R.P.			

Petroleum odor?
no
no

R.P. = Reference Point W.L. = Water Level TBM = Temporary Benchmark MSL = Mean Sea Level

Boring/Well Construction Log



**DUNCKLEE
& DUNHAM**

I. D. Number	B-12	Purpose	Soil boring
Project Name	Beaufort & Martin Co. - Site 8	Contractor	Troxler Geologic
Project No.	201939	Registration No.	2511
Geologist	Alec Dzwianowski	Driller	Ben Troxler
Start Date	4/8/19	Complete Date	4/8/19
		Equipment	Geoprobe

Drilling Method: direct-push
 Comments: WT at 3.25'
 No petroleum odors/stains

Well Construction Information	Depth From - To (ft.)	Lithology	FID / PID (ppm) @ Depth (ft.)
Borehole Diameter	0. - 4	dark gray, sandy, silty CLAY	0.2 @ 1.5'
Riser Type			0.5 @ 2.5'
Diameter			
Screen Type			
Diameter			
Riser Interval			
Screen Interval			
Slot Size			
Grout Type			
Interval			
Bentonite Type			
Interval			
Filter Pack			
Interval			
Total Depth			
R.P. Elevation			
Datum			
Water Level Information			
Date	W.L. Below R.P.		

Petroleum
 odor?
 no
 no

R.P. = Reference Point W.L. = Water Level TBM = Temporary Benchmark MSL = Mean Sea Level

Boring/Well Construction Log



**DUNCKLEE
& DUNHAM**

I. D. Number	B-13	Purpose	Soil boring
Project Name	Beaufort & Martin Co. - Site 8	Contractor	Troxler Geologic
Project No.	201939	Registration No.	2511
Geologist	Alec Dzwonawski	Driller	Ben Troxler
Start Date	4/8/19	Complete Date	4/8/19
		Equipment	Geoprobe

Drilling Method *direct-push*
 Comments *WT at 3.25' w/ perched WT near land surface
 Petroleum odor/staining not observed*

Well Construction Information	Depth From - To (ft.)	Lithology	FID / PID (ppm) @ Depth (ft.)
Borehole Diameter	0-3.5	dark gray, sandy, silty CLAY	0.6 @ 1'
Riser Type	3.5-4	black, sandy, silty CLAY	5.2 @ 4'
Diameter			
Screen Type			
Diameter			
Riser Interval			
Screen Interval			
Slot Size			
Grout Type			
Interval			
Bentonite Type			
Interval			
Filter Pack			
Interval			
Total Depth			
R.P. Elevation			
Datum			
Water Level Information			
Date	W.L. Below R.P.		

Petroleum odor?
bag 1: 0.6 @ 1'
bag 2: 0.2 @ 2.5'
no

R.P. = Reference Point W.L. = Water Level TBM = Temporary Benchmark MSL = Mean Sea Level

Boring/Well Construction Log



**DUNCKLEE
& DUNHAM**

I. D. Number	B-14	Purpose	Soil boring
Project Name	Beaufort & Martin Co. - Site 8	Contractor	Ben Troxler
Project No.	201939	Registration No.	2511
Geologist	Alec Dziwanowski	Driller	Troxler Geologic
Start Date	4/8/19	Equipment	Geoprobe
Complete Date	4/8/19		

Drilling Method direct-push
 Comments WT at 3.25' b/s
Petroleum odor noted from 3.5 - 4' b/s

Well Construction Information	Depth From - To (ft.)	Lithology	FID / PID (ppm) @ Depth (ft.)
Borehole Diameter	0 - 3.5	dark gray, sandy, silty CLAY → bag 1:	0.2 @ 1.5'
Riser Type	3.5 - 4	black, sandy, silty CLAY	72.6 @ 4'
Diameter			
Screen Type			
Diameter			
Riser Interval			
Screen Interval			
Slot Size			
Grout Type			
Interval			
Bentonite Type			
Interval			
Filter Pack			
Interval			
Total Depth			
R.P. Elevation			
Datum			
Water Level Information			
Date	W.L. Below R.P.		

Petroleum odor?
 bag 2:
 2.6 @ 2.5'
 no
 yes

R.P. = Reference Point W.L. = Water Level TBM = Temporary Benchmark MSL = Mean Sea Level

Boring/Well Construction Log



**DUNCKLEE
& DUNHAM**

I. D. Number	B-15 / TW-2	Purpose	Soil boring / GW sampling
Project Name	Beaufort & Martin Co. - Site 8	Contractor	Troxler Geologic
Project No.	201939	Registration No.	2511
Geologist	Alec Dziwanowski	Driller	Ben Troxler
Start Date	4/8/19	Complete Date	4/8/19
		Equipment	Geoprobe

Drilling Method direct push, well type - gw sampling rods (screen point 16)
Comments WT @ 3.25' b/s
 petroleum odor noted from 3.5 - 4' b/s
 Collected soil from 2.5' at 1800
 Collected gw sample at -4' at 1800

Well Construction Information	Depth From - To (ft.)	Lithology	FID / PID (ppm) @ Depth (ft.)	Petroleum odor?
Borehole Diameter	2.75"	0-3.5	dark gray, sandy, silty CLAY → bag 1: 1.1 @ 1'	no
Riser Type	Sampling rod		↓ bag 2: 5.2 @ 2.5'	no
Diameter	1.25"	3.5-4	black, sandy, silty CLAY	yes
Screen Type	Sampling rod			
Diameter	1.25"			
Riser Interval	NA		*Water had odor during sampling	
Screen Interval	0-4' b/s			
Slot Size	0.0025			
Grout Type	↑			
Interval				
Bentonite Type	NA			
Interval	↓			
Filter Pack				
Interval				
Total Depth	4' b/s			
R.P. Elevation	0' b/s			
Datum	Land Surface			
Water Level Information				
Date	W.L. Below R.P.			
4/8/19	2.25'			

R.P. = Reference Point W.L. = Water Level TBM = Temporary Benchmark MSL = Mean Sea Level

Appendix C



May 9, 2019

Richard A. Kolb, L.G.
Duncklee & Dunham, P.C.
511 Keisler Drive, Suite 102
Cary, North Carolina 27518

Reference: **REPORT ON GEOPHYSICAL SERVICES
FOR PARCEL 85, NORMA E. ROBERSON**
8889 US 17 North, Washington, North Carolina
ESP Project No. HO40.300

TIP Number: R-2511
WBS Number: 35494.1.1
County: Beaufort and Martin
Description: US 17 North of NC 171 to Multi-lanes South of Williamston in Beaufort
 and Martin Counties

Dear Mr. Kolb:

ESP Associates, Inc. (ESP) is pleased to present this report to Duncklee & Dunham, P.C. (Duncklee & Dunham) on the geophysical services we provided for the referenced project. This work was performed under our subcontractor agreement dated January 28, 2019, as authorized by the Work Authorization dated March 26, 2019, and in accordance with our cost proposal to you dated March 13, 2019. The purpose of the work was to help identify possible underground storage tanks (USTs).

1.0 GEOPHYSICAL DATA COLLECTION

On April 3 and 5, 2019, ESP performed geophysical studies at Parcel 85, located on the west side of US 17, north of Washington, North Carolina. The work consisted of metal detection using a Geonics EM61 MK2 instrument, obtaining the approximate locations of relevant site features using a DGPS instrument and collecting ground-penetrating radar (GPR) data over selected EM61 anomalies.

The limits of the study area were based on NCDOT field staking and on the NCDOT MicroStation file provided by Duncklee & Dunham, and extended from the edge of the current roadway to the proposed right-of-way (ROW)/easement. Representative photographs of the geophysical study area are provided on Figure 1.

The EM61 data were collected over the accessible areas of the study area using a line spacing of approximately 3 feet. We used a Hemisphere XF101 differential GPS instrument (DGPS) connected to an Archer field computer to provide approximate locations of the EM61 data in real time. The DGPS instrument was also used to obtain the approximate location of site features that could affect the EM61 readings.

We compared the location of the EM61 responses to the location of site features and noted several anomalies that did not correspond to known features. We collected GPR data in four areas using a Sensors and Software Noggin GPR system with a 250 MHz antenna.

2.0 DATA ANALYSIS AND PRESENTATION

The EM61 data were gridded and contoured in Surfer to produce plan view contour maps of the early time gate response (Figure 2) and the differential response (Figure 3). The differential response is calculated by subtracting the response of the bottom coil from the response of the top coil of the EM61. Typically, the differential response diminishes the response from smaller, near-surface metallic objects, thus emphasizing the response from deeper and larger metallic objects, such as USTs. The DGPS locations of observed site features were superimposed on the EM61 contour maps so that anomalies caused by site features such as metal objects on the ground surface could be recognized. Figures 2 and 3 show the EM61 data and the site features that we observed and mapped in the field with DGPS; these figures do not necessarily show all existing site features.

The GPR data were collected over four areas and were reviewed in the field. The metallic anomaly along the southern building wall was attributed to the metal siding and a buried metal pipe located parallel to the building. The GPR data did not indicate the presence of abandoned USTs on site.

The EM61 early time gate response and differential response were exported from Surfer as geo-referenced images and attached to the NCDOT plan sheet in MicroStation (Figures 4 and 5). The legend for the NCDOT line types and symbols is shown on Figure 6.

4.0 SUMMARY AND CONCLUSIONS

Our review of the geophysical data collected for this project does not indicate the presence of USTs within the proposed ROW/easement of Parcel 85.

5.0 LIMITATIONS

These services have been provided to Duncklee & Dunham in accordance with generally accepted guidelines for performing geophysical surveys. It is recognized that the results of geophysical surveys are non-unique and subject to interpretation. Further, the locations of data and features included in this report are approximate and were collected using a DGPS instrument. ESP makes no guarantee as to the accuracy of these locations.

Thank you for the opportunity to be of service on this project. Please contact us if you have any questions or need further information.

Sincerely,

ESP Associates, Inc.



Edward D. Billington, PG
Senior Geophysicist

SBM/EDB

Attachments: Figures 1 – 6




A. Photograph showing a portion of Parcel 85 survey area, looking north.





B. Front of former gas station building, photograph taken looking west. Note relic concrete pads on porch from former dispenser locations.



C. Close-up view of old dispenser pedestal locations on the front of the building.

PROJECT NO. HO40.300	FIGURE 1 - PARCEL 85, NORMA E. ROBERTSON SITE PHOTOGRAPHS	NCDOT PROJECT R-2511, US 17 NORTH OF NC 171 TO MULTI-LANES SOUTH OF WILLIAMSTON BEAUFORT AND MARTIN COUNTIES, NORTH CAROLINA	 ESP Associates, Inc. 7011 Albert Pick Rd., Suite E Greensboro, NC 27409 336.334.7724 www.espassociates.com
SCALE N/A			
DATE 4/11/19			
BY SBM/EDB			



EXPLANATION	
◇	Miscellaneous metal object (pipe, debris, etc.)
□	Utility Box (water meter, electrical outlet, etc.)
▣	Storm drain
●	Utility pole
+	Guy wire anchor
●	Sign pole, other pole
○	UST Valve Cover or Fill Port
- -	Buried utility line (marked by others)
▭ (orange outline)	Existing Building (per NCDOT file)
▭ (grey fill)	EM61 Data Collection Areas
▭ (dashed purple outline)	GPR Data Collection Areas
▭ (black outline)	Underground Storage Tank



Note: Locations of data and features are approximate and were collected using a DGPS instrument. ESP make no guarantees as to the accuracy of these locations. Coordinates on the axes of the maps are approximate and provided for general reference only.

PROJECT NO.	HO40.300
SCALE	AS SHOWN
DATE	4/11/19
BY	SBM/EDB

FIGURE 2 - PARCEL 85, NORMA E. ROBERTSON
EM61 EARLY TIME GATE DATA
NCDOT PROJECT R-2511, US 17 NORTH OF NC 171 TO
MULTI-LANES SOUTH OF WILLIAMSTON
BEAUFORT AND MARTIN COUNTIES, NORTH CAROLINA



ESP Associates, Inc.
 7011 Albert Pick Rd.,
 Suite E
 Greensboro, NC 27409
 336.334.7724
 www.espassociates.com



EXPLANATION	
	Miscellaneous metal object (pipe, debris, etc.)
	Utility Box (water meter, electrical outlet, etc.)
	Storm drain
	Utility pole
	Guy wire anchor
	Sign pole, other pole
	UST Valve Cover or Fill Port
	Buried utility line (marked by others)
	Existing Building (per NCDOT file)
	EM61 Data Collection Areas
	GPR Data Collection Areas
	Underground Storage Tank



Note: Locations of data and features are approximate and were collected using a DGPS instrument. ESP make no guarantees as to the accuracy of these locations. Coordinates on the axes of the maps are approximate and provided for general reference only.

PROJECT NO.	HO40.300
SCALE	AS SHOWN
DATE	4/11/19
BY	SBM/EDB

FIGURE 2 - PARCEL 85, NORMA E. ROBERTSON
EM61 EARLY TIME GATE DATA
NCDOT PROJECT R-2511, US 17 NORTH OF NC 171 TO
MULTI-LANES SOUTH OF WILLIAMSTON
BEAUFORT AND MARTIN COUNTIES, NORTH CAROLINA



ESP Associates, Inc.
 7011 Albert Pick Rd.,
 Suite E
 Greensboro, NC 27409
 336.334.7724
 www.espassociates.com



See Figure 6 for explanation of symbols and line types

List of NCDOT reference files

- R2511_Geo_Env.dgn
- R2511_NCDOT_FS.dgn
- R2511_Rdy_row.dgn




PROJECT NO.	HO40.300
SCALE	1" = 30'
DATE	4/11/19
BY	SBM/EDB

**FIGURE 4 – PARCEL 85, NORMA E. ROBERTSON
EM61 EARLY TIME GATE DATA ON PLAN SHEET, SHOP**


**NCDOT PROJECT R-2511, US 17 NORTH OF NC 171 TO
MULTI-LANES SOUTH OF WILLIAMSTON
BEAUFORT AND MARTIN COUNTIES, NORTH CAROLINA**



ESP Associates, Inc.
7011 Albert Pick Rd.,
Suite E
Greensboro, NC 27409
336.334.7724
www.espassociates.com




APPROXIMATE NORTH



See Figure 6 for explanation of symbols and line types

List of NCDOT reference files

- R2511_Geo_Env.dgn
- R2511_NCDOT_FS.dgn
- R2511_Rdy_row.dgn



PROJECT NO.	HO40.300
SCALE	1" = 30'
DATE	4/11/19
BY	SBM/EDB

**FIGURE 5 – PARCEL 85, NORMA E. ROBERTSON
EM61 DIFFERENTIAL DATA ON PLAN SHEET, SHOP**

**NCDOT PROJECT R-2511, US 17 NORTH OF NC 171 TO
MULTI-LANES SOUTH OF WILLIAMSTON
BEAUFORT AND MARTIN COUNTIES, NORTH CAROLINA**



ESP Associates, Inc.
7011 Albert Pick Rd.,
Suite E
Greensboro, NC 27409
336.334.7724
www.espassociates.com

STATE OF NORTH CAROLINA, DIVISION OF HIGHWAYS CONVENTIONAL PLAN SHEET SYMBOLS

*Note: Not to Scale *S.U.E. = Subsurface Utility Engineering*

BOUNDARIES AND PROPERTY:

State Line	—————
County Line	—————
Township Line	—————
City Line	—————
Reservation Line	—————
Property Line	—————
Existing Iron Pin	○
Property Corner	⊕
Property Monument	⊕
Parcel/Sequence Number	⊕
Existing Fence Line	—x—x—x—
Proposed Woven Wire Fence	—•—•—•—
Proposed Chain Link Fence	—□—□—□—
Proposed Barbed Wire Fence	—◇—◇—◇—
Existing Wetland Boundary	—w—w—w—
Proposed Wetland Boundary	—w—w—w—
Existing Endangered Animal Boundary	—a—
Existing Endangered Plant Boundary	—p—
Existing Historic Property Boundary	—h—
Known Contamination Area: Soil	—s—
Potential Contamination Area: Soil	—s—
Known Contamination Area: Water	—w—
Potential Contamination Area: Water	—w—
Contaminated Site: Known or Potential	—c—

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	○
Sign	⊕
Well	⊕
Small Mine	⊕
Foundation	⊕
Area Outline	⊕
Cemetery	⊕
Building	⊕
School	⊕
Church	⊕
Dam	⊕

HYDROLOGY:

Stream or Body of Water	—————
Hydro, Pool or Reservoir	—————
Jurisdictional Stream	—JS—
Buffer Zone 1	—BZ 1—
Buffer Zone 2	—BZ 2—
Flow Arrow	—————
Disappearing Stream	—————
Spring	—————
Wetland	—————
Proposed Lateral, Tail, Head Ditch	—————
False Sump	—————

RAILROADS:

Standard Gauge	—————
RR Signal Milepost	—————
Switch	—————
RR Abandoned	—————
RR Dismantled	—————

RIGHT OF WAY:

Baseline Control Point	—————
Existing Right of Way Marker	—————
Existing Right of Way Line	—————
Proposed Right of Way Line	—————
Proposed Right of Way Line with Iron Pin and Cap Marker	—————
Proposed Right of Way Line with Concrete or Granite RW Marker	—————
Proposed Control of Access Line with Concrete CA Marker	—————
Existing Control of Access	—————
Proposed Control of Access	—————
Existing Easement Line	—————
Proposed Temporary Construction Easement	—————
Proposed Temporary Drainage Easement	—————
Proposed Permanent Drainage Easement	—————
Proposed Permanent Drainage / Utility Easement	—————
Proposed Permanent Utility Easement	—————
Proposed Temporary Utility Easement	—————
Proposed Aerial Utility Easement	—————
Proposed Permanent Easement with Iron Pin and Cap Marker	—————

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	—————
Existing Curb	—————
Proposed Slope Stakes Cut	—————
Proposed Slope Stakes Fill	—————
Proposed Curb Ramp	—————
Existing Metal Guardrail	—————
Proposed Guardrail	—————
Existing Cable Guiderail	—————
Proposed Cable Guiderail	—————
Equality Symbol	—————
Pavement Removal	—————

VEGETATION:

Single Tree	—————
Single Shrub	—————
Hedge	—————
Woods Line	—————

Orchard	—————
Vineyard	—————

EXISTING STRUCTURES:

MAJOR:	—————
Bridge, Tunnel or Box Culvert	—————
Bridge Wing Wall, Head Wall and End Wall	—————
MINOR:	—————
Head and End Wall	—————
Pipe Culvert	—————
Footbridge	—————
Drainage Box: Catch Basin, DI or JB	—————
Paved Ditch Gutter	—————
Storm Sewer Manhole	—————
Storm Sewer	—————

UTILITIES:

POWER:	—————
Existing Power Pole	—————
Proposed Power Pole	—————
Existing Joint Use Pole	—————
Proposed Joint Use Pole	—————
Power Manhole	—————
Power Line Tower	—————
Power Transformer	—————
U/G Power Cable Hand Hole	—————
H-Frame Pole	—————
U/G Power Line LOS B (S.U.E.*)	—————
U/G Power Line LOS C (S.U.E.*)	—————
U/G Power Line LOS D (S.U.E.*)	—————

TELEPHONE:

Existing Telephone Pole	—————
Proposed Telephone Pole	—————
Telephone Manhole	—————
Telephone Pedestal	—————
Telephone Cell Tower	—————
U/G Telephone Cable Hand Hole	—————
U/G Telephone Cable LOS B (S.U.E.*)	—————
U/G Telephone Cable LOS C (S.U.E.*)	—————
U/G Telephone Cable LOS D (S.U.E.*)	—————
U/G Telephone Conduit LOS B (S.U.E.*)	—————
U/G Telephone Conduit LOS C (S.U.E.*)	—————
U/G Telephone Conduit LOS D (S.U.E.*)	—————
U/G Fiber Optics Cable LOS B (S.U.E.*)	—————
U/G Fiber Optics Cable LOS C (S.U.E.*)	—————
U/G Fiber Optics Cable LOS D (S.U.E.*)	—————

WATER:

Water Manhole	—————
Water Meter	—————
Water Valve	—————
Water Hydrant	—————
U/G Water Line LOS B (S.U.E.*)	—————
U/G Water Line LOS C (S.U.E.*)	—————
U/G Water Line LOS D (S.U.E.*)	—————
Above Ground Water Line	—————

TV:

TV Pedestal	—————
TV Tower	—————
U/G TV Cable Hand Hole	—————
U/G TV Cable LOS B (S.U.E.*)	—————
U/G TV Cable LOS C (S.U.E.*)	—————
U/G TV Cable LOS D (S.U.E.*)	—————
U/G Fiber Optic Cable LOS B (S.U.E.*)	—————
U/G Fiber Optic Cable LOS C (S.U.E.*)	—————
U/G Fiber Optic Cable LOS D (S.U.E.*)	—————

GAS:

Gas Valve	—————
Gas Meter	—————
U/G Gas Line LOS B (S.U.E.*)	—————
U/G Gas Line LOS C (S.U.E.*)	—————
U/G Gas Line LOS D (S.U.E.*)	—————
Above Ground Gas Line	—————

SANITARY SEWER:

Sanitary Sewer Manhole	—————
Sanitary Sewer Cleanout	—————
U/G Sanitary Sewer Line	—————
Above Ground Sanitary Sewer	—————
SS Forced Main Line LOS B (S.U.E.*)	—————
SS Forced Main Line LOS C (S.U.E.*)	—————
SS Forced Main Line LOS D (S.U.E.*)	—————

MISCELLANEOUS:

Utility Pole	—————
Utility Pole with Base	—————
Utility Located Object	—————
Utility Traffic Signal Box	—————
Utility Unknown U/G Line LOS B (S.U.E.*)	—————
U/G Tank; Water, Gas, Oil	—————
Underground Storage Tank, Approx. Loc.	—————
A/G Tank; Water, Gas, Oil	—————
Geoenvironmental Boring	—————
U/G Test Hole LOS A (S.U.E.*)	—————
Abandoned According to Utility Records	AATUR
End of Information	E.O.I.

PROJECT NO.	HO40.300
SCALE	N/A
DATE	4/11/19
BY	SBM/EDB

FIGURE 6
LEGEND FOR PLAN SHEET FIGURES
NCDOT PROJECT R-2511, US 17 NORTH OF NC 171 TO
MULTI-LANES SOUTH OF WILLIAMSTON
BEAUFORT AND MARTIN COUNTIES, NORTH CAROLINA



ESP Associates, Inc.
7011 Albert Pick Rd.,
Suite E
Greensboro, NC 27409
336.334.7724
www.espassociates.com

Appendix D



Hydrocarbon Analysis Results

Client: DUNCKLEE AND DUNHAM
Address: 511 KEISLER DR STE 102
 CARY NC 27518

Samples taken Monday, April 08, 2019
Samples extracted Monday, April 08, 2019
Samples analysed Thursday, April 11, 2019

Contact: RICK KOLB

Operator JENN RYAN

Project: 201939

U04049

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	% Ratios			HC Fingerprint Match
										C5 - C10	C10 - C18	C18	
Soil	B - 15	25.0	<0.63	<0.63	1.8	1.8	0.91	0.04	0.001	0	79.7	20.3	V.Deg.PHC 75.1%,(FCM),(BO)

Initial Calibrator QC check **OK**

Final FCM QC Check **OK** 100.7%

Concentration values in mg/kg for soil samples and mg/L for water samples. Soil values uncorrected for moisture or stone content. Fingerprints provide a tentative hydrocarbon identification.

Abbreviations :- FCM = Results calculated using Fundamental Calibration Mode : % = confidence of hydrocarbon identification : (PFM) = Poor Fingerprint Match : (T) = Turbid : (P) = Particulate detected

B = Blank Drift : (SBS)/(LBS) = Site Specific or Library Background Subtraction applied to result : (BO) = Background Organics detected : (OCR) = Outside cal range : (M) = Modified Result.

% Ratios estimated aromatic carbon number proportions : HC = Hydrocarbon : PHC = Petroleum HC : FP = Fingerprint only. **Data generated by HC-1 Analyser**

Divider Page

April 25, 2019

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc

Duncklee and Dunham

Sample Delivery Group: L1088281
Samples Received: 04/11/2019
Project Number: 201939
Description: NCDOT R-2511 Beaufort and Martin Counties-Parcel 85


Report To: Rick Kolb
PO Box 639
Cary, NC 27512

Entire Report Reviewed By:












Heather J Wagner
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace National is performed per guidance provided in laboratory standard operating procedures: 060302, 060303, and 060304.





Cp: Cover Page	1	
Tc: Table of Contents	2	
Ss: Sample Summary	3	
Cn: Case Narrative	4	
Sr: Sample Results	5	
TW-2 L1088281-02	5	
Qc: Quality Control Summary	8	
Volatile Organic Compounds (GC/MS) by Method 6200B-2011	8	
Semi Volatile Organic Compounds (GC/MS) by Method 625.1	13	
Gl: Glossary of Terms	18	
Al: Accreditations & Locations	19	
Sc: Sample Chain of Custody	20	
		

SAMPLE SUMMARY



TW-2 L1088281-02 GW

Collected by: Alec Dziwanowski
 Collected date/time: 04/08/19 18:00
 Received date/time: 04/11/19 09:00

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Volatile Organic Compounds (GC/MS) by Method 6200B-2011	WG1265185	25	04/12/19 23:04	04/12/19 23:04	GLN	Mt. Juliet, TN
Volatile Organic Compounds (GC/MS) by Method 6200B-2011	WG1267331	200	04/17/19 12:27	04/17/19 12:27	GLN	Mt. Juliet, TN
Semi Volatile Organic Compounds (GC/MS) by Method 625.1	WG1264757	1	04/12/19 16:46	04/13/19 13:12	LEA	Mt. Juliet, TN

¹ Cp

² Tc

³ Ss

⁴ Cn

⁵ Sr

⁶ Qc

⁷ Gl

⁸ Al

⁹ Sc



All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.

Heather J Wagner
Project Manager

Project Narrative

Sample TW-2 is reported separately per client request. All samples listed on the attached COC have been reported individually under SDG number L1088281 based on their Parcel ID.

- 1 Cp
- 2 Tc
- 3 Ss
- 4 Cn
- 5 Sr
- 6 Qc
- 7 Gl
- 8 Al
- 9 Sc



Collected date/time: 04/08/19 18:00

L1088281

Volatile Organic Compounds (GC/MS) by Method 6200B-2011

Analyte	Result	Qualifier	MDL	RDL	Dilution	Analysis	Batch
	ug/l		ug/l	ug/l		date / time	
Acetone	U		250	1250	25	04/12/2019 23:04	WG1265185
Acrolein	U		222	1250	25	04/12/2019 23:04	WG1265185
Acrylonitrile	U		46.8	250	25	04/12/2019 23:04	WG1265185
Benzene	1770		8.28	25.0	25	04/12/2019 23:04	WG1265185
Bromobenzene	U		8.80	25.0	25	04/12/2019 23:04	WG1265185
Bromodichloromethane	U		9.50	25.0	25	04/12/2019 23:04	WG1265185
Bromoform	U		11.7	25.0	25	04/12/2019 23:04	WG1265185
Bromomethane	U		21.6	125	25	04/12/2019 23:04	WG1265185
n-Butylbenzene	36.2		9.02	25.0	25	04/12/2019 23:04	WG1265185
sec-Butylbenzene	21.9	J	9.12	25.0	25	04/12/2019 23:04	WG1265185
tert-Butylbenzene	U		9.98	25.0	25	04/12/2019 23:04	WG1265185
Carbon tetrachloride	U		9.48	25.0	25	04/12/2019 23:04	WG1265185
Chlorobenzene	U		8.70	25.0	25	04/12/2019 23:04	WG1265185
Chlorodibromomethane	U		8.18	25.0	25	04/12/2019 23:04	WG1265185
Chloroethane	U		11.3	125	25	04/12/2019 23:04	WG1265185
Chloroform	U		8.10	125	25	04/12/2019 23:04	WG1265185
Chloromethane	U		6.90	62.5	25	04/12/2019 23:04	WG1265185
2-Chlorotoluene	U		9.38	25.0	25	04/12/2019 23:04	WG1265185
4-Chlorotoluene	U		8.78	25.0	25	04/12/2019 23:04	WG1265185
1,2-Dibromo-3-Chloropropane	U		33.2	125	25	04/12/2019 23:04	WG1265185
1,2-Dibromoethane	U		9.52	25.0	25	04/12/2019 23:04	WG1265185
Dibromomethane	U		8.65	25.0	25	04/12/2019 23:04	WG1265185
1,2-Dichlorobenzene	U		8.72	25.0	25	04/12/2019 23:04	WG1265185
1,3-Dichlorobenzene	U		5.50	25.0	25	04/12/2019 23:04	WG1265185
1,4-Dichlorobenzene	U		6.85	25.0	25	04/12/2019 23:04	WG1265185
Dichlorodifluoromethane	U		13.8	125	25	04/12/2019 23:04	WG1265185
1,1-Dichloroethane	U		6.48	25.0	25	04/12/2019 23:04	WG1265185
1,2-Dichloroethane	U		9.02	25.0	25	04/12/2019 23:04	WG1265185
1,1-Dichloroethene	U		9.95	25.0	25	04/12/2019 23:04	WG1265185
cis-1,2-Dichloroethene	U		6.50	25.0	25	04/12/2019 23:04	WG1265185
trans-1,2-Dichloroethene	U		9.90	25.0	25	04/12/2019 23:04	WG1265185
1,2-Dichloropropane	U		7.65	25.0	25	04/12/2019 23:04	WG1265185
1,1-Dichloropropene	U		8.80	25.0	25	04/12/2019 23:04	WG1265185
1,3-Dichloropropane	U		9.15	25.0	25	04/12/2019 23:04	WG1265185
2,2-Dichloropropane	U		8.02	25.0	25	04/12/2019 23:04	WG1265185
Di-isopropyl ether	U		8.00	25.0	25	04/12/2019 23:04	WG1265185
Ethylbenzene	2060		9.60	25.0	25	04/12/2019 23:04	WG1265185
Hexachloro-1,3-butadiene	U		6.40	25.0	25	04/12/2019 23:04	WG1265185
Isopropylbenzene	106		8.15	25.0	25	04/12/2019 23:04	WG1265185
p-Isopropyltoluene	9.76	J	8.75	25.0	25	04/12/2019 23:04	WG1265185
2-Butanone (MEK)	U		98.2	250	25	04/12/2019 23:04	WG1265185
Methylene Chloride	U		25.0	125	25	04/12/2019 23:04	WG1265185
4-Methyl-2-pentanone (MIBK)	U		53.5	250	25	04/12/2019 23:04	WG1265185
Methyl tert-butyl ether	U		9.18	25.0	25	04/12/2019 23:04	WG1265185
Naphthalene	446		25.0	125	25	04/12/2019 23:04	WG1265185
n-Propylbenzene	319		8.72	25.0	25	04/12/2019 23:04	WG1265185
Styrene	U		7.68	25.0	25	04/12/2019 23:04	WG1265185
1,1,1,2-Tetrachloroethane	U		9.62	25.0	25	04/12/2019 23:04	WG1265185
1,1,2,2-Tetrachloroethane	U		3.25	25.0	25	04/12/2019 23:04	WG1265185
Tetrachloroethene	U		9.30	25.0	25	04/12/2019 23:04	WG1265185
Toluene	14000		82.4	200	200	04/17/2019 12:27	WG1267331
1,2,3-Trichlorobenzene	U		5.75	25.0	25	04/12/2019 23:04	WG1265185
1,2,4-Trichlorobenzene	U		8.88	25.0	25	04/12/2019 23:04	WG1265185
1,1,1-Trichloroethane	U		7.98	25.0	25	04/12/2019 23:04	WG1265185
1,1,2-Trichloroethane	U		9.58	25.0	25	04/12/2019 23:04	WG1265185
Trichloroethene	U		9.95	25.0	25	04/12/2019 23:04	WG1265185

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc



Collected date/time: 04/08/19 18:00

L1088281

Volatile Organic Compounds (GC/MS) by Method 6200B-2011

Analyte	Result ug/l	Qualifier	MDL ug/l	RDL ug/l	Dilution	Analysis date / time	Batch
Trichlorofluoromethane	U		30.0	125	25	04/12/2019 23:04	WG1265185
1,2,3-Trichloropropane	U		20.2	62.5	25	04/12/2019 23:04	WG1265185
1,2,4-Trimethylbenzene	2260		9.32	25.0	25	04/12/2019 23:04	WG1265185
1,3,5-Trimethylbenzene	551		9.68	25.0	25	04/12/2019 23:04	WG1265185
Vinyl chloride	U		6.48	25.0	25	04/12/2019 23:04	WG1265185
Xylenes, Total	9490		26.5	75.0	25	04/12/2019 23:04	WG1265185
(S) Toluene-d8	99.6			80.0-120		04/12/2019 23:04	WG1265185
(S) Toluene-d8	98.2			80.0-120		04/17/2019 12:27	WG1267331
(S) a,a,a-Trifluorotoluene	97.1			80.0-120		04/12/2019 23:04	WG1265185
(S) a,a,a-Trifluorotoluene	96.1			80.0-120		04/17/2019 12:27	WG1267331
(S) 4-Bromofluorobenzene	101			77.0-126		04/12/2019 23:04	WG1265185
(S) 4-Bromofluorobenzene	97.4			77.0-126		04/17/2019 12:27	WG1267331
(S) 1,2-Dichloroethane-d4	94.4			70.0-130		04/12/2019 23:04	WG1265185
(S) 1,2-Dichloroethane-d4	94.0			70.0-130		04/17/2019 12:27	WG1267331

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc

Semi Volatile Organic Compounds (GC/MS) by Method 625.1

Analyte	Result ug/l	Qualifier	MDL ug/l	RDL ug/l	Dilution	Analysis date / time	Batch
Acenaphthene	U		0.316	1.00	1	04/13/2019 13:12	WG1264757
Acenaphthylene	U		0.309	1.00	1	04/13/2019 13:12	WG1264757
Anthracene	U		0.291	1.00	1	04/13/2019 13:12	WG1264757
Benzidine	U		4.32	10.0	1	04/13/2019 13:12	WG1264757
Benzo(a)anthracene	U		0.0975	1.00	1	04/13/2019 13:12	WG1264757
Benzo(b)fluoranthene	U		0.0896	1.00	1	04/13/2019 13:12	WG1264757
Benzo(k)fluoranthene	U		0.355	1.00	1	04/13/2019 13:12	WG1264757
Benzo(g,h,i)perylene	U		0.161	1.00	1	04/13/2019 13:12	WG1264757
Benzo(a)pyrene	U		0.340	1.00	1	04/13/2019 13:12	WG1264757
Bis(2-chloroethoxy)methane	U		0.329	10.0	1	04/13/2019 13:12	WG1264757
Bis(2-chloroethyl)ether	U		1.62	10.0	1	04/13/2019 13:12	WG1264757
Bis(2-chloroisopropyl)ether	U		0.445	10.0	1	04/13/2019 13:12	WG1264757
4-Bromophenyl-phenylether	U		0.335	10.0	1	04/13/2019 13:12	WG1264757
2-Chloronaphthalene	U	J4	0.330	1.00	1	04/13/2019 13:12	WG1264757
4-Chlorophenyl-phenylether	U		0.303	10.0	1	04/13/2019 13:12	WG1264757
Chrysene	U		0.332	1.00	1	04/13/2019 13:12	WG1264757
Dibenz(a,h)anthracene	U		0.279	1.00	1	04/13/2019 13:12	WG1264757
3,3-Dichlorobenzidine	U		2.02	10.0	1	04/13/2019 13:12	WG1264757
2,4-Dinitrotoluene	U		1.65	10.0	1	04/13/2019 13:12	WG1264757
2,6-Dinitrotoluene	U		0.279	10.0	1	04/13/2019 13:12	WG1264757
Fluoranthene	U		0.310	1.00	1	04/13/2019 13:12	WG1264757
Fluorene	U		0.323	1.00	1	04/13/2019 13:12	WG1264757
Hexachlorobenzene	U		0.341	1.00	1	04/13/2019 13:12	WG1264757
Hexachloro-1,3-butadiene	U		0.329	10.0	1	04/13/2019 13:12	WG1264757
Hexachlorocyclopentadiene	U		2.33	10.0	1	04/13/2019 13:12	WG1264757
Hexachloroethane	U	J4	0.365	10.0	1	04/13/2019 13:12	WG1264757
Indeno(1,2,3-cd)pyrene	U		0.279	1.00	1	04/13/2019 13:12	WG1264757
Isophorone	U		0.272	10.0	1	04/13/2019 13:12	WG1264757
Naphthalene	124		0.372	1.00	1	04/13/2019 13:12	WG1264757
Nitrobenzene	U		0.367	10.0	1	04/13/2019 13:12	WG1264757
n-Nitrosodimethylamine	U		1.26	10.0	1	04/13/2019 13:12	WG1264757
n-Nitrosodiphenylamine	U		1.19	10.0	1	04/13/2019 13:12	WG1264757
n-Nitrosodi-n-propylamine	U		0.403	10.0	1	04/13/2019 13:12	WG1264757
Phenanthrene	U		0.366	1.00	1	04/13/2019 13:12	WG1264757
Benzylbutyl phthalate	U		0.275	3.00	1	04/13/2019 13:12	WG1264757
Bis(2-ethylhexyl)phthalate	U		0.709	3.00	1	04/13/2019 13:12	WG1264757
Di-n-butyl phthalate	U		0.266	3.00	1	04/13/2019 13:12	WG1264757
Diethyl phthalate	14.6		0.282	3.00	1	04/13/2019 13:12	WG1264757



Collected date/time: 04/08/19 18:00

L1088281

Semi Volatile Organic Compounds (GC/MS) by Method 625.1

Analyte	Result ug/l	Qualifier	MDL ug/l	RDL ug/l	Dilution	Analysis date / time	Batch
Dimethyl phthalate	U		0.283	3.00	1	04/13/2019 13:12	WG1264757
Di-n-octyl phthalate	U		0.278	3.00	1	04/13/2019 13:12	WG1264757
Pyrene	U		0.330	1.00	1	04/13/2019 13:12	WG1264757
1,2,4-Trichlorobenzene	U	J4	0.355	10.0	1	04/13/2019 13:12	WG1264757
4-Chloro-3-methylphenol	U		0.263	10.0	1	04/13/2019 13:12	WG1264757
2-Chlorophenol	U		0.283	10.0	1	04/13/2019 13:12	WG1264757
2,4-Dichlorophenol	U		0.284	10.0	1	04/13/2019 13:12	WG1264757
2,4-Dimethylphenol	U		0.624	10.0	1	04/13/2019 13:12	WG1264757
4,6-Dinitro-2-methylphenol	U		2.62	10.0	1	04/13/2019 13:12	WG1264757
2,4-Dinitrophenol	U		3.25	10.0	1	04/13/2019 13:12	WG1264757
2-Nitrophenol	U		0.320	10.0	1	04/13/2019 13:12	WG1264757
4-Nitrophenol	U		2.01	10.0	1	04/13/2019 13:12	WG1264757
Pentachlorophenol	U		0.313	10.0	1	04/13/2019 13:12	WG1264757
Phenol	2.63	J	0.334	10.0	1	04/13/2019 13:12	WG1264757
2,4,6-Trichlorophenol	U		0.297	10.0	1	04/13/2019 13:12	WG1264757
(S) Nitrobenzene-d5	36.3			15.0-314		04/13/2019 13:12	WG1264757
(S) 2-Fluorobiphenyl	34.9			22.0-127		04/13/2019 13:12	WG1264757
(S) p-Terphenyl-d14	58.4			29.0-141		04/13/2019 13:12	WG1264757
(S) Phenol-d5	20.7			8.00-424		04/13/2019 13:12	WG1264757
(S) 2-Fluorophenol	22.6			10.0-120		04/13/2019 13:12	WG1264757
(S) 2,4,6-Tribromophenol	63.7			10.0-153		04/13/2019 13:12	WG1264757

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc



Method Blank (MB)

(MB) R3402078-3 04/12/19 15:56

Analyte	MB Result ug/l	MB Qualifier	MB MDL ug/l	MB RDL ug/l
Acetone	U		10.0	50.0
Acrolein	U		8.87	50.0
Acrylonitrile	U		1.87	10.0
Benzene	U		0.331	1.00
Bromobenzene	U		0.352	1.00
Bromodichloromethane	U		0.380	1.00
Bromoform	U		0.469	1.00
Bromomethane	U		0.866	5.00
n-Butylbenzene	U		0.361	1.00
sec-Butylbenzene	U		0.365	1.00
tert-Butylbenzene	U		0.399	1.00
Carbon tetrachloride	U		0.379	1.00
Chlorobenzene	U		0.348	1.00
Chlorodibromomethane	U		0.327	1.00
Chloroethane	U		0.453	5.00
Chloroform	U		0.324	5.00
Chloromethane	U		0.276	2.50
2-Chlorotoluene	U		0.375	1.00
4-Chlorotoluene	U		0.351	1.00
1,2-Dibromo-3-Chloropropane	U		1.33	5.00
1,2-Dibromoethane	U		0.381	1.00
Dibromomethane	U		0.346	1.00
1,2-Dichlorobenzene	U		0.349	1.00
1,3-Dichlorobenzene	U		0.220	1.00
1,4-Dichlorobenzene	U		0.274	1.00
Dichlorodifluoromethane	U		0.551	5.00
1,1-Dichloroethane	U		0.259	1.00
1,2-Dichloroethane	U		0.361	1.00
1,1-Dichloroethene	U		0.398	1.00
cis-1,2-Dichloroethene	U		0.260	1.00
trans-1,2-Dichloroethene	U		0.396	1.00
1,2-Dichloropropane	U		0.306	1.00
1,1-Dichloropropene	U		0.352	1.00
1,3-Dichloropropane	U		0.366	1.00
2,2-Dichloropropane	U		0.321	1.00
Di-isopropyl ether	U		0.320	1.00
Ethylbenzene	U		0.384	1.00
Hexachloro-1,3-butadiene	U		0.256	1.00
Isopropylbenzene	U		0.326	1.00
p-Isopropyltoluene	U		0.350	1.00

¹ Cp

² Tc

³ Ss

⁴ Cn

⁵ Sr

⁶ Qc

⁷ Gl

⁸ Al

⁹ Sc



Method Blank (MB)

(MB) R3402078-3 04/12/19 15:56

Analyte	MB Result	MB Qualifier	MB MDL	MB RDL
	ug/l		ug/l	ug/l
2-Butanone (MEK)	U		3.93	10.0
Methylene Chloride	U		1.00	5.00
4-Methyl-2-pentanone (MIBK)	U		2.14	10.0
Methyl tert-butyl ether	U		0.367	1.00
Naphthalene	U		1.00	5.00
n-Propylbenzene	U		0.349	1.00
Styrene	U		0.307	1.00
1,1,1,2-Tetrachloroethane	U		0.385	1.00
1,1,2,2-Tetrachloroethane	U		0.130	1.00
Tetrachloroethene	U		0.372	1.00
1,2,3-Trichlorobenzene	U		0.230	1.00
1,2,4-Trichlorobenzene	U		0.355	1.00
1,1,1-Trichloroethane	U		0.319	1.00
1,1,2-Trichloroethane	U		0.383	1.00
Trichloroethene	U		0.398	1.00
Trichlorofluoromethane	U		1.20	5.00
1,2,3-Trichloropropane	U		0.807	2.50
1,2,4-Trimethylbenzene	U		0.373	1.00
1,3,5-Trimethylbenzene	U		0.387	1.00
Vinyl chloride	U		0.259	1.00
Xylenes, Total	U		1.06	3.00
(S) Toluene-d8	102			80.0-120
(S) a,a,a-Trifluorotoluene	98.5			80.0-120
(S) 4-Bromofluorobenzene	98.7			77.0-126
(S) 1,2-Dichloroethane-d4	94.4			70.0-130

¹ Cp

² Tc

³ Ss

⁴ Cn

⁵ Sr

⁶ Qc

⁷ Gl

⁸ Al

⁹ Sc

Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3402078-1 04/12/19 14:53 • (LCSD) R3402078-2 04/12/19 15:14

Analyte	Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits	LCS Qualifier	LCSD Qualifier	RPD	RPD Limits
	ug/l	ug/l	ug/l	%	%	%			%	%
Acetone	125	134	142	107	114	19.0-160			5.73	27
Acrolein	125	126	131	101	105	10.0-160			3.94	26
Acrylonitrile	125	128	136	103	109	55.0-149			5.92	20
Benzene	25.0	24.7	25.6	98.7	102	70.0-123			3.67	20
Bromobenzene	25.0	23.0	24.0	92.0	96.0	73.0-121			4.31	20
Bromodichloromethane	25.0	25.2	26.1	101	104	75.0-120			3.49	20
Bromoform	25.0	24.9	26.0	99.5	104	68.0-132			4.55	20
Bromomethane	25.0	28.2	30.3	113	121	10.0-160			7.10	25



Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3402078-1 04/12/19 14:53 • (LCSD) R3402078-2 04/12/19 15:14

Analyte	Spike Amount ug/l	LCS Result ug/l	LCSD Result ug/l	LCS Rec. %	LCSD Rec. %	Rec. Limits %	<u>LCS Qualifier</u>	<u>LCSD Qualifier</u>	RPD %	RPD Limits %
n-Butylbenzene	25.0	24.7	25.8	99.0	103	73.0-125			4.17	20
sec-Butylbenzene	25.0	25.5	26.2	102	105	75.0-125			3.00	20
tert-Butylbenzene	25.0	25.6	26.8	102	107	76.0-124			4.56	20
Carbon tetrachloride	25.0	26.2	27.4	105	109	68.0-126			4.27	20
Chlorobenzene	25.0	24.7	25.7	99.0	103	80.0-121			3.79	20
Chlorodibromomethane	25.0	25.2	25.9	101	104	77.0-125			2.85	20
Chloroethane	25.0	25.4	27.1	101	108	47.0-150			6.49	20
Chloroform	25.0	25.5	26.9	102	107	73.0-120			5.06	20
Chloromethane	25.0	24.9	27.6	99.4	111	41.0-142			10.6	20
2-Chlorotoluene	25.0	25.2	26.7	101	107	76.0-123			5.62	20
4-Chlorotoluene	25.0	24.9	26.0	99.7	104	75.0-122			4.00	20
1,2-Dibromo-3-Chloropropane	25.0	24.8	26.2	99.2	105	58.0-134			5.54	20
1,2-Dibromoethane	25.0	25.9	26.4	103	106	80.0-122			2.19	20
Dibromomethane	25.0	25.0	26.0	99.8	104	80.0-120			4.01	20
1,2-Dichlorobenzene	25.0	25.1	26.5	101	106	79.0-121			5.48	20
1,3-Dichlorobenzene	25.0	25.6	26.6	102	107	79.0-120			3.94	20
1,4-Dichlorobenzene	25.0	23.5	24.5	94.1	98.1	79.0-120			4.24	20
Dichlorodifluoromethane	25.0	22.4	23.5	89.8	94.1	51.0-149			4.75	20
1,1-Dichloroethane	25.0	24.3	26.1	97.0	104	70.0-126			7.21	20
1,2-Dichloroethane	25.0	22.7	23.8	90.8	95.0	70.0-128			4.53	20
1,1-Dichloroethene	25.0	24.9	26.3	99.4	105	71.0-124			5.72	20
cis-1,2-Dichloroethene	25.0	24.8	26.4	99.2	106	73.0-120			6.26	20
trans-1,2-Dichloroethene	25.0	27.8	28.7	111	115	73.0-120			3.33	20
1,2-Dichloropropane	25.0	25.1	25.6	101	102	77.0-125			1.73	20
1,1-Dichloropropene	25.0	25.9	26.8	104	107	74.0-126			3.40	20
1,3-Dichloropropane	25.0	26.5	26.8	106	107	80.0-120			0.930	20
2,2-Dichloropropane	25.0	19.0	19.4	76.1	77.7	58.0-130			2.04	20
Di-isopropyl ether	25.0	24.2	25.4	96.8	101	58.0-138			4.71	20
Ethylbenzene	25.0	26.7	26.9	107	108	79.0-123			1.07	20
Hexachloro-1,3-butadiene	25.0	24.2	25.0	96.9	99.8	54.0-138			2.92	20
Isopropylbenzene	25.0	25.4	26.4	102	106	76.0-127			3.98	20
p-Isopropyltoluene	25.0	24.8	26.2	99.2	105	76.0-125			5.50	20
2-Butanone (MEK)	125	119	124	95.6	99.0	44.0-160			3.57	20
Methylene Chloride	25.0	23.5	24.2	94.0	96.7	67.0-120			2.84	20
4-Methyl-2-pentanone (MIBK)	125	128	129	102	103	68.0-142			0.817	20
Methyl tert-butyl ether	25.0	25.0	25.4	100	102	68.0-125			1.46	20
Naphthalene	25.0	24.2	26.2	97.0	105	54.0-135			7.92	20
n-Propylbenzene	25.0	24.7	25.9	99.0	103	77.0-124			4.45	20
Styrene	25.0	27.4	28.3	110	113	73.0-130			3.30	20
1,1,1,2-Tetrachloroethane	25.0	25.0	25.7	100	103	75.0-125			2.52	20

¹ Cp

² Tc

³ Ss

⁴ Cn

⁵ Sr

⁶ Qc

⁷ Gl

⁸ Al

⁹ Sc



Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3402078-1 04/12/19 14:53 • (LCSD) R3402078-2 04/12/19 15:14

Analyte	Spike Amount ug/l	LCS Result ug/l	LCSD Result ug/l	LCS Rec. %	LCSD Rec. %	Rec. Limits %	<u>LCS Qualifier</u>	<u>LCSD Qualifier</u>	RPD %	RPD Limits %
1,1,2,2-Tetrachloroethane	25.0	24.0	24.8	95.9	99.2	65.0-130			3.46	20
Tetrachloroethene	25.0	25.6	26.5	102	106	72.0-132			3.76	20
1,2,3-Trichlorobenzene	25.0	25.5	27.9	102	112	50.0-138			9.02	20
1,2,4-Trichlorobenzene	25.0	25.4	27.0	102	108	57.0-137			6.03	20
1,1,1-Trichloroethane	25.0	25.1	26.4	101	105	73.0-124			4.80	20
1,1,2-Trichloroethane	25.0	24.6	25.2	98.5	101	80.0-120			2.16	20
Trichloroethene	25.0	28.8	29.4	115	118	78.0-124			2.18	20
Trichlorofluoromethane	25.0	27.2	28.1	109	112	59.0-147			3.12	20
1,2,3-Trichloropropane	25.0	25.4	27.1	102	108	73.0-130			6.33	20
1,2,4-Trimethylbenzene	25.0	25.9	27.1	103	108	76.0-121			4.53	20
1,3,5-Trimethylbenzene	25.0	24.1	25.3	96.2	101	76.0-122			4.99	20
Vinyl chloride	25.0	25.8	27.7	103	111	67.0-131			7.31	20
Xylenes, Total	75.0	78.2	80.0	104	107	79.0-123			2.28	20
<i>(S) Toluene-d8</i>				98.1	98.7	80.0-120				
<i>(S) a,a,a-Trifluorotoluene</i>				97.1	101	80.0-120				
<i>(S) 4-Bromofluorobenzene</i>				101	103	77.0-126				
<i>(S) 1,2-Dichloroethane-d4</i>				107	106	70.0-130				

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc



Method Blank (MB)

(MB) R3402560-4 04/17/19 10:08

Analyte	MB Result	MB Qualifier	MB MDL	MB RDL
	ug/l		ug/l	ug/l
Toluene	U		0.412	1.00
(S) Toluene-d8	97.7			80.0-120
(S) a,a,a-Trifluorotoluene	98.0			80.0-120
(S) 4-Bromofluorobenzene	95.9			77.0-126
(S) 1,2-Dichloroethane-d4	94.8			70.0-130

Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3402560-1 04/17/19 08:50 • (LCSD) R3402560-2 04/17/19 09:09

Analyte	Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits	LCS Qualifier	LCSD Qualifier	RPD	RPD Limits
	ug/l	ug/l	ug/l	%	%	%			%	%
Toluene	25.0	24.9	25.5	99.8	102	79.0-120			2.30	20
(S) Toluene-d8				94.9	96.1	80.0-120				
(S) a,a,a-Trifluorotoluene				97.7	98.6	80.0-120				
(S) 4-Bromofluorobenzene				101	96.5	77.0-126				
(S) 1,2-Dichloroethane-d4				93.9	92.4	70.0-130				

¹ Cp

² Tc

³ Ss

⁴ Cn

⁵ Sr

⁶ Qc

⁷ Gl

⁸ Al

⁹ Sc



Method Blank (MB)

(MB) R3401482-3 04/13/19 12:08

Analyte	MB Result ug/l	MB Qualifier	MB MDL ug/l	MB RDL ug/l
Acenaphthene	U		0.316	1.00
Acenaphthylene	U		0.309	1.00
Anthracene	U		0.291	1.00
Benzidine	U		4.32	10.0
Benzo(a)anthracene	U		0.0975	1.00
Benzo(b)fluoranthene	U		0.0896	1.00
Benzo(k)fluoranthene	U		0.355	1.00
Benzo(g,h,i)perylene	U		0.161	1.00
Benzo(a)pyrene	U		0.340	1.00
Bis(2-chlorethoxy)methane	U		0.329	10.0
Bis(2-chloroethyl)ether	U		1.62	10.0
Bis(2-chloroisopropyl)ether	U		0.445	10.0
4-Bromophenyl-phenylether	U		0.335	10.0
2-Chloronaphthalene	U		0.330	1.00
4-Chlorophenyl-phenylether	U		0.303	10.0
Chrysene	U		0.332	1.00
Dibenz(a,h)anthracene	U		0.279	1.00
3,3-Dichlorobenzidine	U		2.02	10.0
2,4-Dinitrotoluene	U		1.65	10.0
2,6-Dinitrotoluene	U		0.279	10.0
Fluoranthene	U		0.310	1.00
Fluorene	U		0.323	1.00
Hexachlorobenzene	U		0.341	1.00
Hexachloro-1,3-butadiene	U		0.329	10.0
Hexachlorocyclopentadiene	U		2.33	10.0
Hexachloroethane	U		0.365	10.0
Indeno(1,2,3-cd)pyrene	U		0.279	1.00
Isophorone	U		0.272	10.0
Naphthalene	U		0.372	1.00
Nitrobenzene	U		0.367	10.0
n-Nitrosodimethylamine	U		1.26	10.0
n-Nitrosodiphenylamine	U		1.19	10.0
n-Nitrosodi-n-propylamine	U		0.403	10.0
Phenanthrene	U		0.366	1.00
Benzylbutyl phthalate	U		0.275	3.00
Bis(2-ethylhexyl)phthalate	U		0.709	3.00
Di-n-butyl phthalate	U		0.266	3.00
Diethyl phthalate	U		0.282	3.00
Dimethyl phthalate	U		0.283	3.00
Di-n-octyl phthalate	U		0.278	3.00

¹ Cp

² Tc

³ Ss

⁴ Cn

⁵ Sr

⁶ Qc

⁷ Gl

⁸ Al

⁹ Sc



Method Blank (MB)

(MB) R3401482-3 04/13/19 12:08

Analyte	MB Result	MB Qualifier	MB MDL	MB RDL
	ug/l		ug/l	ug/l
Pyrene	U		0.330	1.00
1,2,4-Trichlorobenzene	U		0.355	10.0
4-Chloro-3-methylphenol	U		0.263	10.0
2-Chlorophenol	U		0.283	10.0
2,4-Dichlorophenol	U		0.284	10.0
2,4-Dimethylphenol	U		0.624	10.0
4,6-Dinitro-2-methylphenol	U		2.62	10.0
2,4-Dinitrophenol	U		3.25	10.0
2-Nitrophenol	U		0.320	10.0
4-Nitrophenol	U		2.01	10.0
Pentachlorophenol	U		0.313	10.0
Phenol	U		0.334	10.0
2,4,6-Trichlorophenol	U		0.297	10.0
<i>(S) Nitrobenzene-d5</i>	49.5			15.0-314
<i>(S) 2-Fluorobiphenyl</i>	48.0			22.0-127
<i>(S) p-Terphenyl-d14</i>	63.6			29.0-141
<i>(S) Phenol-d5</i>	24.1			8.00-424
<i>(S) 2-Fluorophenol</i>	37.8			10.0-120
<i>(S) 2,4,6-Tribromophenol</i>	51.0			10.0-153

- 1 Cp
- 2 Tc
- 3 Ss
- 4 Cn
- 5 Sr
- 6 Qc
- 7 Gl
- 8 Al
- 9 Sc

Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3401482-1 04/13/19 11:27 • (LCSD) R3401482-2 04/13/19 11:47

Analyte	Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.	Rec. Limits	LCS Qualifier	LCSD Qualifier	RPD	RPD Limits
	ug/l	ug/l	ug/l	%	%	%			%	%
Acenaphthene	50.0	32.8	31.7	65.6	63.4	47.0-145			3.41	48
Acenaphthylene	50.0	31.5	30.7	63.0	61.4	33.0-145			2.57	74
Anthracene	50.0	36.0	35.5	72.0	71.0	27.0-133			1.40	66
Benzidine	100	34.7	40.5	34.7	40.5	1.00-120			15.4	36
Benzo(a)anthracene	50.0	37.0	36.6	74.0	73.2	33.0-143			1.09	53
Benzo(b)fluoranthene	50.0	36.0	35.9	72.0	71.8	24.0-159			0.278	71
Benzo(k)fluoranthene	50.0	36.9	35.9	73.8	71.8	11.0-162			2.75	63
Benzo(g,h,i)perylene	50.0	35.4	35.0	70.8	70.0	1.00-219			1.14	97
Benzo(a)pyrene	50.0	35.0	34.4	70.0	68.8	17.0-163			1.73	72
Bis(2-chlorethoxy)methane	50.0	30.1	29.2	60.2	58.4	1.00-219			3.04	54
Bis(2-chloroethyl)ether	50.0	30.0	28.5	60.0	57.0	33.0-185			5.13	108
Bis(2-chloroisopropyl)ether	50.0	29.9	28.7	59.8	57.4	36.0-166			4.10	76
4-Bromophenyl-phenylether	50.0	37.0	35.7	74.0	71.4	53.0-127			3.58	43
2-Chloronaphthalene	50.0	29.7	28.3	59.4	56.6	60.0-120	<u>J4</u>	<u>J4</u>	4.83	24



Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3401482-1 04/13/19 11:27 • (LCSD) R3401482-2 04/13/19 11:47

Analyte	Spike Amount ug/l	LCS Result ug/l	LCSD Result ug/l	LCS Rec. %	LCSD Rec. %	Rec. Limits %	LCS Qualifier	LCSD Qualifier	RPD %	RPD Limits %
4-Chlorophenyl-phenylether	50.0	33.7	33.2	67.4	66.4	25.0-158			1.49	61
Chrysene	50.0	37.6	36.9	75.2	73.8	17.0-168			1.88	87
Dibenz(a,h)anthracene	50.0	35.7	35.2	71.4	70.4	1.00-227			1.41	126
3,3-Dichlorobenzidine	100	73.2	72.0	73.2	72.0	1.00-262			1.65	108
2,4-Dinitrotoluene	50.0	37.4	37.7	74.8	75.4	39.0-139			0.799	42
2,6-Dinitrotoluene	50.0	34.9	34.4	69.8	68.8	50.0-158			1.44	48
Fluoranthene	50.0	38.3	38.2	76.6	76.4	26.0-137			0.261	66
Fluorene	50.0	33.9	33.4	67.8	66.8	59.0-121			1.49	38
Hexachlorobenzene	50.0	36.4	35.3	72.8	70.6	1.00-152			3.07	55
Hexachloro-1,3-butadiene	50.0	21.0	18.9	42.0	37.8	24.0-120			10.5	62
Hexachlorocyclopentadiene	50.0	21.4	20.0	42.8	40.0	10.0-120			6.76	31
Hexachloroethane	50.0	19.0	17.4	38.0	34.8	40.0-120	J4	J4	8.79	52
Indeno(1,2,3-cd)pyrene	50.0	33.8	34.2	67.6	68.4	1.00-171			1.18	99
Isophorone	50.0	31.2	30.0	62.4	60.0	21.0-196			3.92	93
Naphthalene	50.0	26.0	24.4	52.0	48.8	21.0-133			6.35	65
Nitrobenzene	50.0	27.6	26.8	55.2	53.6	35.0-180			2.94	62
n-Nitrosodimethylamine	50.0	21.5	20.8	43.0	41.6	10.0-120			3.31	34
n-Nitrosodiphenylamine	50.0	35.0	35.0	70.0	70.0	44.0-120			0.000	21
n-Nitrosodi-n-propylamine	50.0	34.5	33.4	69.0	66.8	1.00-230			3.24	87
Phenanthrene	50.0	36.1	35.4	72.2	70.8	54.0-120			1.96	39
Benzylbutyl phthalate	50.0	37.6	37.4	75.2	74.8	1.00-152			0.533	60
Bis(2-ethylhexyl)phthalate	50.0	38.4	37.6	76.8	75.2	8.00-158			2.11	82
Di-n-butyl phthalate	50.0	39.2	39.3	78.4	78.6	1.00-120			0.255	47
Diethyl phthalate	50.0	35.5	35.3	71.0	70.6	1.00-120			0.565	100
Dimethyl phthalate	50.0	34.9	34.3	69.8	68.6	1.00-120			1.73	183
Di-n-octyl phthalate	50.0	38.9	38.9	77.8	77.8	4.00-146			0.000	69
Pyrene	50.0	37.2	36.7	74.4	73.4	52.0-120			1.35	49
1,2,4-Trichlorobenzene	50.0	23.0	21.2	46.0	42.4	44.0-142		J4	8.14	50
4-Chloro-3-methylphenol	50.0	33.5	33.6	67.0	67.2	22.0-147			0.298	73
2-Chlorophenol	50.0	29.1	28.0	58.2	56.0	23.0-134			3.85	61
2,4-Dichlorophenol	50.0	29.4	28.4	58.8	56.8	39.0-135			3.46	50
2,4-Dimethylphenol	50.0	29.4	28.6	58.8	57.2	32.0-120			2.76	58
4,6-Dinitro-2-methylphenol	50.0	39.7	40.2	79.4	80.4	1.00-181			1.25	203
2,4-Dinitrophenol	50.0	30.0	29.8	60.0	59.6	1.00-191			0.669	132
2-Nitrophenol	50.0	31.1	30.4	62.2	60.8	29.0-182			2.28	55
4-Nitrophenol	50.0	17.6	17.9	35.2	35.8	1.00-132			1.69	131
Pentachlorophenol	50.0	30.4	30.5	60.8	61.0	14.0-176			0.328	86
Phenol	50.0	15.4	15.2	30.8	30.4	5.00-120			1.31	64
2,4,6-Trichlorophenol	50.0	31.3	30.5	62.6	61.0	37.0-144			2.59	58
(S) Nitrobenzene-d5				56.3	53.7	15.0-314				

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc



Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3401482-1 04/13/19 11:27 • (LCSD) R3401482-2 04/13/19 11:47

Analyte	Spike Amount ug/l	LCS Result ug/l	LCSD Result ug/l	LCS Rec. %	LCSD Rec. %	Rec. Limits %	<u>LCS Qualifier</u>	<u>LCSD Qualifier</u>	RPD %	RPD Limits %
(S) 2-Fluorobiphenyl				60.1	58.1	22.0-127				
(S) p-Terphenyl-d14				72.1	70.2	29.0-141				
(S) Phenol-d5				28.4	27.8	8.00-424				
(S) 2-Fluorophenol				43.3	41.7	10.0-120				
(S) 2,4,6-Tribromophenol				66.0	66.0	10.0-153				

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

L1087068-01 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1087068-01 04/13/19 14:47 • (MS) R3401475-1 04/13/19 15:11 • (MSD) R3401475-2 04/13/19 15:34

Analyte	Spike Amount ug/l	Original Result ug/l	MS Result ug/l	MSD Result ug/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	<u>MS Qualifier</u>	<u>MSD Qualifier</u>	RPD %	RPD Limits %
Acenaphthene	50.0	U	26.4	30.2	52.8	60.4	1	47.0-145			13.4	48
Acenaphthylene	50.0	U	24.8	28.6	49.6	57.2	1	33.0-145			14.2	74
Anthracene	50.0	U	31.2	35.7	62.4	71.4	1	27.0-133			13.5	66
Benzo(a)anthracene	50.0	U	33.9	37.0	67.8	74.0	1	33.0-143			8.74	53
Benzo(b)fluoranthene	50.0	0.0164	31.3	33.8	62.6	67.6	1	24.0-159			7.68	71
Benzo(k)fluoranthene	50.0	U	32.5	34.3	65.0	68.6	1	11.0-162			5.39	63
Benzo(g,h,i)perylene	50.0	U	33.3	36.1	66.6	72.2	1	1.00-219			8.07	97
Benzo(a)pyrene	50.0	U	31.0	33.2	62.0	66.4	1	17.0-163			6.85	72
Bis(2-chlorethoxy)methane	50.0	U	21.2	23.8	42.4	47.6	1	33.0-184			11.6	54
Bis(2-chloroethyl)ether	50.0	U	18.9	22.7	37.8	45.4	1	12.0-158			18.3	108
Bis(2-chloroisopropyl)ether	50.0	U	22.7	27.5	45.4	55.0	1	36.0-166			19.1	76
4-Bromophenyl-phenylether	50.0	U	30.4	33.3	60.8	66.6	1	53.0-127			9.11	43
2-Chloronaphthalene	50.0	U	22.9	26.6	45.8	53.2	1	60.0-120	J6	J6	14.9	24
4-Chlorophenyl-phenylether	50.0	U	27.6	31.1	55.2	62.2	1	25.0-158			11.9	61
Chrysene	50.0	U	31.4	34.1	62.8	68.2	1	17.0-168			8.24	87
Dibenz(a,h)anthracene	50.0	U	32.7	35.2	65.4	70.4	1	1.00-227			7.36	126
3,3-Dichlorobenzidine	100	U	38.9	50.5	38.9	50.5	1	1.00-262			26.0	108
2,4-Dinitrotoluene	50.0	U	33.7	38.7	67.4	77.4	1	39.0-139			13.8	42
2,6-Dinitrotoluene	50.0	U	29.2	33.2	58.4	66.4	1	50.0-158			12.8	48
Benzdine	100	U	ND	4.71	0.000	4.71	1	1.00-120	J6	J3	200	40
Fluoranthene	50.0	U	36.0	39.4	72.0	78.8	1	26.0-137			9.02	66
Fluorene	50.0	U	28.6	32.7	57.2	65.4	1	59.0-121	J6		13.4	38
Hexachlorobenzene	50.0	U	29.5	32.9	59.0	65.8	1	1.00-152			10.9	55
Hexachloro-1,3-butadiene	50.0	U	18.2	21.3	36.4	42.6	1	24.0-120			15.7	62
Hexachlorocyclopentadiene	50.0	U	17.1	20.3	34.2	40.6	1	10.0-146			17.1	34
Hexachloroethane	50.0	U	15.7	18.4	31.4	36.8	1	40.0-120	J6	J6	15.8	52
Indeno(1,2,3-cd)pyrene	50.0	U	32.0	34.8	64.0	69.6	1	1.00-171			8.38	99
Isophorone	50.0	U	22.0	24.6	44.0	49.2	1	21.0-196			11.2	93

6 Qc

7 Gl

8 Al

9 Sc



L1087068-01 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1087068-01 04/13/19 14:47 • (MS) R3401475-1 04/13/19 15:11 • (MSD) R3401475-2 04/13/19 15:34

Analyte	Spike Amount ug/l	Original Result ug/l	MS Result ug/l	MSD Result ug/l	MS Rec. %	MSD Rec. %	Dilution	Rec. Limits %	MS Qualifier	MSD Qualifier	RPD %	RPD Limits %
Naphthalene	50.0	U	20.9	24.0	41.8	48.0	1	21.0-133			13.8	65
Nitrobenzene	50.0	0.827	21.3	25.2	40.9	48.7	1	35.0-180			16.8	62
n-Nitrosodimethylamine	50.0	U	19.6	24.1	39.2	48.2	1	10.0-120			20.6	40
n-Nitrosodiphenylamine	50.0	U	31.1	35.5	62.2	71.0	1	16.0-160			13.2	28
n-Nitrosodi-n-propylamine	50.0	U	23.1	27.2	46.2	54.4	1	1.00-230			16.3	87
Phenanthrene	50.0	U	31.9	34.9	63.8	69.8	1	54.0-120			8.98	39
Benzylbutyl phthalate	50.0	U	37.4	40.2	74.8	80.4	1	1.00-152			7.22	60
Bis(2-ethylhexyl)phthalate	50.0	0.772	38.4	41.5	75.3	81.5	1	8.00-158			7.76	82
Di-n-butyl phthalate	50.0	U	38.9	43.0	77.8	86.0	1	1.00-120			10.0	47
Diethyl phthalate	50.0	U	33.2	36.8	66.4	73.6	1	1.00-120			10.3	100
Dimethyl phthalate	50.0	U	30.0	33.5	60.0	67.0	1	1.00-120			11.0	183
Di-n-octyl phthalate	50.0	0.420	40.9	44.6	81.0	88.4	1	4.00-146			8.65	69
Pyrene	50.0	U	31.1	34.2	62.2	68.4	1	52.0-120			9.49	49
1,2,4-Trichlorobenzene	50.0	U	18.7	21.3	37.4	42.6	1	44.0-142	J6	J6	13.0	50
4-Chloro-3-methylphenol	50.0	U	30.1	34.3	60.2	68.6	1	22.0-147			13.0	73
2-Chlorophenol	50.0	U	22.0	25.8	44.0	51.6	1	23.0-134			15.9	61
2,4-Dichlorophenol	50.0	U	26.9	31.8	53.8	63.6	1	39.0-135			16.7	50
2,4-Dimethylphenol	50.0	U	26.1	29.3	52.2	58.6	1	32.0-120			11.6	58
4,6-Dinitro-2-methylphenol	50.0	U	42.7	49.2	85.4	98.4	1	1.00-181			14.1	203
2,4-Dinitrophenol	50.0	U	28.9	33.6	57.8	67.2	1	1.00-191			15.0	132
2-Nitrophenol	50.0	U	28.7	33.1	57.4	66.2	1	29.0-182			14.2	55
4-Nitrophenol	50.0	U	16.2	18.4	32.4	36.8	1	1.00-132			12.7	131
Pentachlorophenol	50.0	U	29.8	32.8	59.6	65.6	1	14.0-176			9.58	86
Phenol	50.0	U	11.1	13.7	22.2	27.4	1	5.00-120			21.0	64
2,4,6-Trichlorophenol	50.0	U	27.5	32.2	55.0	64.4	1	37.0-144			15.7	58
(S) Nitrobenzene-d5					44.0	50.0		15.0-314				
(S) 2-Fluorobiphenyl					47.6	54.3		22.0-127				
(S) p-Terphenyl-d14					60.3	65.4		29.0-141				
(S) Phenol-d5					19.9	22.0		8.00-424				
(S) 2-Fluorophenol					32.5	38.3		10.0-120				
(S) 2,4,6-Tribromophenol					65.0	72.0		10.0-153				

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc



Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Abbreviations and Definitions

MDL	Method Detection Limit.
ND	Not detected at the Reporting Limit (or MDL where applicable).
RDL	Reported Detection Limit.
Rec.	Recovery.
RPD	Relative Percent Difference.
SDG	Sample Delivery Group.
(S)	Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media.
U	Not detected at the Reporting Limit (or MDL where applicable).
Analyte	The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported.
Dilution	If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor.
Limits	These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges.
Original Sample	The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG.
Qualifier	This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable.
Result	The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state "ND" (Not Detected) or "BDL" (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte.
Uncertainty (Radiochemistry)	Confidence level of 2 sigma.
Case Narrative (Cn)	A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report.
Quality Control Summary (Qc)	This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material.
Sample Chain of Custody (Sc)	This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis.
Sample Results (Sr)	This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported.
Sample Summary (Ss)	This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis.

Qualifier Description

J	The identification of the analyte is acceptable; the reported value is an estimate.
J3	The associated batch QC was outside the established quality control range for precision.
J4	The associated batch QC was outside the established quality control range for accuracy.
J6	The sample matrix interfered with the ability to make any accurate determination; spike value is low.

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 GI

8 AI

9 Sc



Pace National is the only environmental laboratory accredited/certified to support your work nationwide from one location. One phone call, one point of contact, one laboratory. No other lab is as accessible or prepared to handle your needs throughout the country. Our capacity and capability from our single location laboratory is comparable to the collective totals of the network laboratories in our industry. The most significant benefit to our one location design is the design of our laboratory campus. The model is conducive to accelerated productivity, decreasing turn-around time, and preventing cross contamination, thus protecting sample integrity. Our focus on premium quality and prompt service allows us to be YOUR LAB OF CHOICE.

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.
 * Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace National.

State Accreditations

Alabama	40660	Nebraska	NE-OS-15-05
Alaska	17-026	Nevada	TN-03-2002-34
Arizona	AZ0612	New Hampshire	2975
Arkansas	88-0469	New Jersey-NELAP	TN002
California	2932	New Mexico ¹	n/a
Colorado	TN00003	New York	11742
Connecticut	PH-0197	North Carolina	Env375
Florida	E87487	North Carolina ¹	DW21704
Georgia	NELAP	North Carolina ³	41
Georgia ¹	923	North Dakota	R-140
Idaho	TN00003	Ohio-VAP	CL0069
Illinois	200008	Oklahoma	9915
Indiana	C-TN-01	Oregon	TN200002
Iowa	364	Pennsylvania	68-02979
Kansas	E-10277	Rhode Island	LA000356
Kentucky ^{1,6}	90010	South Carolina	84004
Kentucky ²	16	South Dakota	n/a
Louisiana	AI30792	Tennessee ^{1,4}	2006
Louisiana ¹	LA180010	Texas	T104704245-18-15
Maine	TN0002	Texas ⁵	LAB0152
Maryland	324	Utah	TN00003
Massachusetts	M-TN003	Vermont	VT2006
Michigan	9958	Virginia	460132
Minnesota	047-999-395	Washington	C847
Mississippi	TN00003	West Virginia	233
Missouri	340	Wisconsin	9980939910
Montana	CERT0086	Wyoming	A2LA


Third Party Federal Accreditations

A2LA – ISO 17025	1461.01	AIHA-LAP,LLC EMLAP	100789
A2LA – ISO 17025 ⁵	1461.02	DOD	1461.01
Canada	1461.01	USDA	P330-15-00234
EPA-Crypto	TN00003		

¹ Drinking Water ² Underground Storage Tanks ³ Aquatic Toxicity ⁴ Chemical/Microbiological ⁵ Mold ⁶ Wastewater n/a Accreditation not applicable

Our Locations

Pace National has sixty-four client support centers that provide sample pickup and/or the delivery of sampling supplies. If you would like assistance from one of our support offices, please contact our main office. Pace National performs all testing at our central laboratory.



1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc

Dunckle and Dunham
 PO Box 639
 Cary, NC 27512

Billing Information:
Project Manager
 511 Keisler Drive, Suite 102
 Cary, NC 27518

Report to:
Rick Kolb

Email To: rkolb@dunckleedunham.com

City/State Collected: *Washington and Williamston / NC*

Project Description: **NCDOT R-2511 Beaufort and Martin Countie**

Phone: **919-858-9898**
 Fax: **919-858-9899**

Client Project # *201939*

Lab Project # **DUNDUNNC-NCDOT R2511**

Collected by (print): *Alec Dziwanowski*

Site/Facility ID # *D&D standard*

Collected by (signature): *Alec Dziwanowski*

Immediately Packed on Ice N Y

Rush? (Lab MUST Be Notified)
 Same Day Five Day
 Next Day 5 Day (Rad Only)
 Two Day 10 Day (Rad Only)
 Three Day

Date Results Needed

No. of Cntrs

Analysis / Container / Preservative

Chain of Custody Page ___ of ___

Pace Analytical
 National Center for Testing & Innovation

12065 Lebanon Rd
 Mount Juliet, TN 37122
 Phone: 615-758-5858
 Phone: 800-767-5859
 Fax: 615-758-5859

L# *L1088281*

F078

Accnum: **DUNDUNNC**

Template: **T147651**

Prelogin: **P699279**

TSR: **873 - Heather J Wagner**

PB:

Shipped Via: **FedEX Ground**

Sample ID	Comp/Grab	Matrix *	Depth	Date	Time	No. of Cntrs	Pres	Container	Preservative	Remarks	Sample # (lab only)
TW-1	Grab	GW	NA	4/8/19	1450	5	X	X			01
TW-2	↓	GW	↓	4/8/19	1800	5	X	X			-02
TW-3	↓	GW	↓	4/9/19	1655	5	X	X			-03
TW-4	↓	GW	↓	4/10/19	1120	5	X	X			-04
TW-5	↓	GW	↓	4/10/19	1215	5	X	X			
		GW				5	X	X			

RAD SCREEN: <0.5 mR/hr

* Matrix:
 SS - Soil AIR - Air F - Filter
 GW - Groundwater B - Bioassay
 WW - WasteWater
 DW - Drinking Water
 OT - Other

Remarks: **HOLD TW-5** → we will contact the lab when we know if we need it tested

Samples returned via:
 UPS FedEx Courier

Tracking # *487 1088281 6390*

Relinquished by: (Signature) *Alec Dziwanowski* Date: *4/10/19* Time: *1541*

Received by: (Signature) *[Signature]* Trip Blank Received: Yes/No HCL/MeOH TBR

Relinquished by: (Signature) *[Signature]* Date: *4/22/19* Time: *1559*

Received by: (Signature) *[Signature]* Temp: °C *2.5-0.1=2.4* Bottles Received: *25*

Relinquished by: (Signature) *[Signature]* Date: *4/11/19* Time: *0900*

Received for lab by: (Signature) *[Signature]* Date: *4/11/19* Time: *0900*

Sample Receipt Checklist

COC Seal Present/Intact: NP Y N

COC Signed/Accurate: Y N

Bottles arrive intact: Y N

Correct bottles used: Y N

Sufficient volume sent: Y N

If Applicable

VOA Zero Headpace: Y N

Preservation Correct/Checked: Y N

If preservation required by Login: Date/Time

Condition: **03-0237** NCF / OK

Divider Page

April 26, 2019

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc

Duncklee and Dunham

Sample Delivery Group: L1091336
Samples Received: 04/11/2019
Project Number: 201939
Description: NCDOT R-2511 Beaufort and Martin Counties-Parcel 85


Report To: Rick Kolb
PO Box 639
Cary, NC 27512

Entire Report Reviewed By:



Heather J Wagner
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace National is performed per guidance provided in laboratory standard operating procedures: 060302, 060303, and 060304.





Cp: Cover Page	1	1 Cp
Tc: Table of Contents	2	2 Tc
Ss: Sample Summary	3	3 Ss
Cn: Case Narrative	4	4 Cn
Sr: Sample Results	5	5 Sr
TW-2 L1091336-02	5	5 Sr
Qc: Quality Control Summary	6	6 Qc
Volatile Petroleum Hydrocarbons by Method MADEPV	6	6 Sr
Gl: Glossary of Terms	7	7 Gl
Al: Accreditations & Locations	8	8 Al
Sc: Sample Chain of Custody	9	9 Sc

SAMPLE SUMMARY



TW-2 L1091336-02 GW

Collected by Alec Dziwanowski
 Collected date/time 04/08/19 18:00
 Received date/time 04/11/19 09:00

Method	Batch	Dilution	Preparation date/time	Analysis date/time	Analyst	Location
Volatile Petroleum Hydrocarbons by Method MADEPV	WG1270096	20	04/22/19 19:16	04/22/19 19:16	ACG	Mt. Juliet, TN

¹ Cp

² Tc

³ Ss

⁴ Cn

⁵ Sr

⁶ Qc

⁷ Gl

⁸ Al

⁹ Sc



All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.

Heather J Wagner
Project Manager

Project Narrative

Sample TW-2 is reported separately per client request. All samples listed on the attached COC have been reported individually under SDG number L1091336 based on their Parcel ID.

- 1 Cp
- 2 Tc
- 3 Ss
- 4 Cn
- 5 Sr
- 6 Qc
- 7 Gl
- 8 Al
- 9 Sc



Volatile Petroleum Hydrocarbons by Method MADEPV

Analyte	Result ug/l	Qualifier	MDL ug/l	RDL ug/l	Dilution	Analysis date / time	Batch
Unadjusted C5-C8 Aliphatics	42200		666	2000	20	04/22/2019 19:16	WG1270096
Unadjusted C9-C12 Aliphatics	25200		666	2000	20	04/22/2019 19:16	WG1270096
Unadjusted C9-C10 Aromatics	10100		666	2000	20	04/22/2019 19:16	WG1270096
Total VPH	77500		666	2000	20	04/22/2019 19:16	WG1270096
(S) 2,5-Dibromotoluene(FID)	100			70.0-130		04/22/2019 19:16	WG1270096
(S) 2,5-Dibromotoluene(PID)	93.1			70.0-130		04/22/2019 19:16	WG1270096

1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc



Method Blank (MB)

(MB) R3404446-3 04/22/19 17:38

Analyte	MB Result ug/l	MB Qualifier	MB MDL ug/l	MB RDL ug/l
Unadjusted C5-C8 Aliphatics	U		33.3	100
Unadjusted C9-C12 Aliphatics	U		33.3	100
Unadjusted C9-C10 Aromatics	U		33.3	100
Total VPH	U		33.3	100
(S) 2,5-Dibromotoluene(FID)	96.7			70.0-130
(S) 2,5-Dibromotoluene(PID)	91.2			70.0-130

¹ Cp

² Tc

³ Ss

⁴ Cn

⁵ Sr

Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3404446-1 04/22/19 15:28 • (LCSD) R3404446-2 04/22/19 15:59

Analyte	Spike Amount ug/l	LCS Result ug/l	LCSD Result ug/l	LCS Rec. %	LCSD Rec. %	Rec. Limits %	LCS Qualifier	LCSD Qualifier	RPD %	RPD Limits %
Unadjusted C5-C8 Aliphatics	1200	1030	1030	86.0	86.2	70.0-130			0.289	25
Unadjusted C9-C12 Aliphatics	1400	1280	1290	91.5	92.1	70.0-130			0.700	25
Unadjusted C9-C10 Aromatics	200	159	160	79.5	79.9	70.0-130			0.510	25
Total VPH	2800	2470	2480	88.2	88.6	70.0-130			0.445	25
(S) 2,5-Dibromotoluene(FID)				95.5	99.0	70.0-130				
(S) 2,5-Dibromotoluene(PID)				90.8	92.8	70.0-130				

⁶ Qc

⁷ Gl

⁸ Al

⁹ Sc



Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Abbreviations and Definitions

MDL	Method Detection Limit.
RDL	Reported Detection Limit.
Rec.	Recovery.
RPD	Relative Percent Difference.
SDG	Sample Delivery Group.
(S)	Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media.
U	Not detected at the Reporting Limit (or MDL where applicable).
Analyte	The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported.
Dilution	If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor.
Limits	These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges.
Qualifier	This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable.
Result	The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state "ND" (Not Detected) or "BDL" (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte.
Uncertainty (Radiochemistry)	Confidence level of 2 sigma.
Case Narrative (Cn)	A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report.
Quality Control Summary (Qc)	This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material.
Sample Chain of Custody (Sc)	This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis.
Sample Results (Sr)	This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported.
Sample Summary (Ss)	This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis.

- 1 Cp
- 2 Tc
- 3 Ss
- 4 Cn
- 5 Sr
- 6 Qc
- 7 Gl
- 8 Al
- 9 Sc

Qualifier Description

The remainder of this page intentionally left blank, there are no qualifiers applied to this SDG.



Pace National is the only environmental laboratory accredited/certified to support your work nationwide from one location. One phone call, one point of contact, one laboratory. No other lab is as accessible or prepared to handle your needs throughout the country. Our capacity and capability from our single location laboratory is comparable to the collective totals of the network laboratories in our industry. The most significant benefit to our one location design is the design of our laboratory campus. The model is conducive to accelerated productivity, decreasing turn-around time, and preventing cross contamination, thus protecting sample integrity. Our focus on premium quality and prompt service allows us to be YOUR LAB OF CHOICE.

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.
 * Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace National.

State Accreditations

Alabama	40660	Nebraska	NE-OS-15-05
Alaska	17-026	Nevada	TN-03-2002-34
Arizona	AZ0612	New Hampshire	2975
Arkansas	88-0469	New Jersey-NELAP	TN002
California	2932	New Mexico ¹	n/a
Colorado	TN00003	New York	11742
Connecticut	PH-0197	North Carolina	Env375
Florida	E87487	North Carolina ¹	DW21704
Georgia	NELAP	North Carolina ³	41
Georgia ¹	923	North Dakota	R-140
Idaho	TN00003	Ohio-VAP	CL0069
Illinois	200008	Oklahoma	9915
Indiana	C-TN-01	Oregon	TN200002
Iowa	364	Pennsylvania	68-02979
Kansas	E-10277	Rhode Island	LA000356
Kentucky ^{1,6}	90010	South Carolina	84004
Kentucky ²	16	South Dakota	n/a
Louisiana	AI30792	Tennessee ^{1,4}	2006
Louisiana ¹	LA180010	Texas	T104704245-18-15
Maine	TN0002	Texas ⁵	LAB0152
Maryland	324	Utah	TN00003
Massachusetts	M-TN003	Vermont	VT2006
Michigan	9958	Virginia	460132
Minnesota	047-999-395	Washington	C847
Mississippi	TN00003	West Virginia	233
Missouri	340	Wisconsin	9980939910
Montana	CERT0086	Wyoming	A2LA


Third Party Federal Accreditations

A2LA – ISO 17025	1461.01	AIHA-LAP,LLC EMLAP	100789
A2LA – ISO 17025 ⁵	1461.02	DOD	1461.01
Canada	1461.01	USDA	P330-15-00234
EPA-Crypto	TN00003		

¹ Drinking Water ² Underground Storage Tanks ³ Aquatic Toxicity ⁴ Chemical/Microbiological ⁵ Mold ⁶ Wastewater n/a Accreditation not applicable

Our Locations

Pace National has sixty-four client support centers that provide sample pickup and/or the delivery of sampling supplies. If you would like assistance from one of our support offices, please contact our main office. Pace National performs all testing at our central laboratory.



1 Cp

2 Tc

3 Ss

4 Cn

5 Sr

6 Qc

7 Gl

8 Al

9 Sc

Dunckle and Dunham

PO Box 639
Cary, NC 27512

Billing Information:
Project Manager
511 Keisler Drive, Suite 102
Cary, NC 27518

Pres
Chk

Analysis / Container / Preservative

Chain of Custody Page of



12065 Lebanon Rd
Mount Juliet, TN 37122
Phone: 615-758-5858
Phone: 800-767-5859
Fax: 615-758-5859



Report to:
Rick Kolb

Email To: rkolb@dunckleandunham.com

Project Description: NCDOT R-2511 Beaufort and Martin Counties

City/State Collected: Washington and Williamston / NC

Phone: 919-858-9898
Fax: 919-858-9899

Client Project #
201939

Lab Project #
DUNDUNNC-NCDOT R2511

Collected by (print):
Alec Dawanowski

Site/Facility ID #
D&D standard

P.O. #

Collected by (signature):
Alec Dawanowski
Immediately
Packed on Ice: N Y

Rush? (Lab MUST Be Notified)
 Same Day Five Day
 Next Day 5 Day (Rad Only)
 Two Day 10 Day (Rad Only)
 Three Day

Quote #
Date Results Needed

No. of
Cntrs

100ml Amb NoPres
 40ml Amb-HCl
 625
 620

L# L1094281
F078
L1091336

NJ
4/2/19

Acctnum: DUNDUNNC
Template: T147651
Prelogin: P699279
TSR: 873 - Heather J Wagner
PB:

Shipped Via: **FedEX Ground**

Sample ID	Comp/Grab	Matrix *	Depth	Date	Time	No. of Cntrs												
TW-1	Grab	GW	NA	4/8/19	1450	5	X	X										
TW-2	↓	GW	↓	4/8/19	1800	5	X	X										
TW-3	↓	GW	↓	4/9/19	1655	5	X	X										
TW-4	↓	GW	↓	4/10/19	1120	5	X	X										
TW-5	↓	GW	↓	4/10/19	1215	5	X	X										
		GW				5	X	X										

Remarks Sample # (lab only)

01
02
03
04

RAD SCREEN: <0.5 mR/hr

* Matrix:
SS - Soil AIR - Air F - Filter
GW - Groundwater B - Bioassay
WW - Waste Water
DW - Drinking Water
OT - Other

Remarks: HOLD TW-5 → we will contact the lab when we know if we need it tested

pH Temp
Flow Other

Samples returned via:
 UPS FedEx Courier

Tracking # 487 1094281 6390

Sample Receipt Checklist	
COC Seal Present/Intact:	<u> </u> NP <u> </u> Y <u> </u> N
COC Signed/Accurate:	<u> </u> Y <u> </u> N
Bottles arrive intact:	<u> </u> Y <u> </u> N
Correct bottles used:	<u> </u> Y <u> </u> N
Sufficient volume sent:	<u> </u> Y <u> </u> N
If Applicable	
VOA Zero Headspace:	<u> </u> Y <u> </u> N
Preservation Correct/Checked:	<u> </u> Y <u> </u> N

Relinquished by: (Signature)
Alec Dawanowski

Date: 4/10/19
Time: 1541

Date: 4/10/19
Time: 1555

Received by: (Signature)
[Signature]

Trip Blank Received: Yes/No
 HCL/MeOH
 TBR

Relinquished by: (Signature)
[Signature]

Date: 4/11/19
Time: 0900

Received by: (Signature)
[Signature]

Temp: 2.5-0.1=2.4 °C
Bottles Received: 25

If preservation required by Login: Date/Time

Relinquished by: (Signature)
[Signature]

Date: 4/11/19
Time: 0900

Received for lab by: (Signature)
[Signature]

Date: 4/11/19
Time: 0900

Field: 03-0237 Condition: NCF / OK

Andy Vann

From: Heather Wagner
Sent: Monday, April 22, 2019 9:09 AM
To: Login
Subject: L1088281 - relog for VPH - expires today

Please relog L1088281-01, -02, -03 and -04 for VPHNC. -01 and -02 go out of hold today. R5 due 4/29

Thanks,

Heather Wagner
Project Manager

Pace Analytical National Center for Testing & Innovation
12065 Lebanon Road | Mt. Juliet, TN 37122
Office 615.773.9686 | Cell 615.289.9801
hwagner@pacenational.com | pacenational.com

ESC Lab Sciences is now Pace Analytical National Center for Testing & Innovation! Please make note of my new email address and website.