PROJECT NO.	SHEET NO.	TOTAL NO.
I-5831A	6	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0318000000-E FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	0320000000-E FOUNDATION CONDITIONING GEO-TEXTILE	2407000000-N STL FRAME W/2 GTR, STD 840.37	2473000000-N GENERIC DRAINAGE ITEM, REMOVE AND REPLACE CONCRETE APRON	2473000000-N GENERIC DRAINAGE ITEM DRAINAGE STRUCTURE CLEANOUT	2473000000-N GENERIC DRAINAGE ITEM MASONRY DRAINAGE STRUCTURE (REPAIR)	2752000000-E GENERIC PAVING ITEM REMOVE AND REPLACE CONCRETE EXPRESSWAY GUTTER	4600000000-N GENERIC TRAFFIC CONTROL ITEM, WORK ZONE DIGITAL SPEED LIMIT SIGNS	4600000000-N GENERIC TRAFFIC CONTROL ITEM, RAMP/LOOP CLOSURE	4600000000-N GENERIC TRAFFIC CONTROL ITEM, SINGLE LANE CLOSURE	6000000000-E TEMPORARY SILT FENCE	6012000000-E SEDIMENT CONTROL STONE	6029000000-E SAFEY FENCE	6042000000-E 1/4" HARDWARE CLOTH	6084000000-E SEEDING & MULTCHING	6117500000-N CONCRETE WASHOUT STRUCTURE
										MI	FT	TON	SY	EA	EA	EA	EA	LF	EA	EA	EA	LF	TON	LF	LF	ACR	EA
I-5831A	Madison	1	I-26 WEST BOUND	FROM EXIT 9 TO TENNESSEE LINE (MP 0.00 - MP 9.05)	N/A	3	MD	NO	NO	9	60	5	13	50	4	20.00	50	510	2	6	30	30	5	50	60	0.25	1
TOTAL FOR MAP NO. 1										**9**		**5**	**13**	**50**	**4**	**20.00**	**50**	**510**	**2**	**6**	**30**	**30**	**5**	**50**	**60**	**0**	**1**
I-5831A	Madison	2	I-26 EAST BOUND	FROM THE TENNESSEE LINE TO EXIT 9 (MP 0.00 - MP 9.05)	N/A	3	MD	NO	NO	9	53	5	12	54	2	20.00	54	580	2	6	29	30	5	50	60	0.25	1
TOTAL FOR MAP NO. 2										**9**		**5**	**12**	**54**	**2**	**20.00**	**54**	**580**	**2**	**6**	**29**	**30**	**5**	**50**	**60**	**0**	**1**
I-5831A	Madison	3	EXIT 9 ON RAMP (RMP-3517)	FROM US 19 TO I-26 (WEST BOUND) (MP 0.00 - MP 0.23)	N/A	1	2WU	NO	NO	0.23	30			2			2	20									
TOTAL FOR MAP NO. 3										**0.23**				**2**			**2**	**20**									
I-5831A	Madison	4	I-26 REST AREA (RST-5017) (W/B)	FROM I-26 TO I-26 (MP 0.00 - MP 0.53)	N/A	1	2WD	NO	NO	0.45	30			2	1		2	10									
TOTAL FOR MAP NO. 4										**0.45**				**2**	**1**		**2**	**10**									
I-5831A	Madison	5	EXIT 3 OFF RAMP (RMP-5860)	FROM I-26 TO SR 1346 (MP0.00 - MP 0.26)	N/A	1	2WU	NO	NO	0.26	30			3			3	30									
TOTAL FOR MAP NO. 5										**0.26**				**3**			**3**	**30**									
I-5831A	Madison	6	EXIT 3 ON RAMP (RMP-5859) (W/B)	FROM SR 1346 TO I-26 (MP 0.00 - MP 0.34)	N/A	1	2WU	NO	NO	0.34	30			1			1	10									
TOTAL FOR MAP NO. 6										**0.34**				**1**			**1**	**10**									
I-5831A	Madison	7	EXIT 3 OFF RAMP (RMP-5857) (E/B)	FROM I-26 TO SR 1346 (MP 0.00 - MP 0.25)	N/A	1	2WU	NO	NO	0.25	30			1	1		1										
TOTAL FOR MAP NO. 7										**0.25**				**1**	**1**		**1**										
I-5831A	Madison	8	EXIT 3 ON RAMP (RMP-5858) (E/B)	FROM SR 1346 TO I-26 (MP 0.00 - MP 0.30)	N/A	1	2WU	NO	NO	0.3	30			1	1		1										
TOTAL FOR MAP NO. 8										**0.3**				**1**	**1**		**1**										
I-5831A	Madison	9	I-26 REST AREA (RST-5014) (E/B)	FROM I-26 TO I-26 (MP 0.00 - MP 0.70)	N/A	1	2WU	NO	NO	0.7	30			1	1		1										
TOTAL FOR MAP NO. 9										**0.7**				**1**	**1**		**1**										
TOTAL FOR PROJ NO. I-5831A										**20.53**		**10**	**25**	**115**	**10**	**40.00**	**115**	**1,160**	**4**	**12**	**59**	**60**	**10**	**100**	**120**	**0.50**	**2**
GRAND TOTAL										**20.53**		**10**	**25**	**115**	**10**	**40.00**	**115**	**1,160**	**4**	**12**	**59**	**60**	**10**	**100**	**120**	**0.50**	**2**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4400000000-E WORK ZONE SIGNS (STATIONARY)	4405000000-E WORK ZONE SIGNS (PORTABLE)	4415000000-N FLASHING ARROW BOARD	4420000000-N PORTABLE CHANGEABLE MESSAGE SIGN	4424000000-N WORK ZONE PRESENCE LIGHTING	4430000000-N DRUMS	4434000000-N SEQUENTIAL FLASHING WARNING LIGHTS	4445000000-E BARRICADES (TYPE III)	4480000000-N TMA	4890000000-E POLYUREA PAVEMENT MARKING LINES (4", 20 MILS) WHITE (STANDARD GLASS BEADS)
								MI	FT	SF	SF	EA	EA	EA	EA	EA	LF	EA	LF
I-5831A	Madison	1	26 WEST BOUN	FROM EXIT 9 TO TENNESSEE LINE (MP 3.57 - MP 12.62)	N/A	3	MD	9	60	215	112	1	2	8	130	8	32	1	50
TOTAL FOR MAP NO. 1								**9**		**215**	**112**	**1**	**2**	**8**	**130**	**8**	**32**	**1**	**50**
I-5831A	Madison	2	26 EAST BOUN	FROM THE TENNESSEE LINE TO EXIT 9 (MP 0.00 - MP 9.05)	N/A	3	MD	9	53	215	112	1	1	7	130	8	32	1	50
TOTAL FOR MAP NO. 2								**9**		**215**	**112**	**1**	**1**	**7**	**130**	**8**	**32**	**1**	**50**
I-5831A	Madison	3	N RAMP (RM	FROM US 19 TO I-26 (WEST BOUND) (MP 0.00 - MP 0.23)	N/A	1	2WU	0.23	30										
TOTAL FOR MAP NO. 3								**0.23**											
I-5831A	Madison	4	AREA (RST-50	FROM I-26 TO I-26	N/A	1	2WD	0.45	30										
TOTAL FOR MAP NO. 4								**0.45**											
I-5831A	Madison	5	FF RAMP (RM	FROM I-26 TO SR 1346 (MP0.00 - MP 0.26)	N/A	1	2WU	0.26	30										
TOTAL FOR MAP NO. 5								**0.26**											
I-5831A	Madison	6	RAMP (RMP-5	FROM SR 1346 TO I-26 (MP 0.00 - MP 0.34)	N/A	1	2WU	0.34	30										
TOTAL FOR MAP NO. 6								**0.34**											
I-5831A	Madison	7	RAMP (RMP-5	FROM I-26 TO SR 1346 (MP 0.00 - MP 0.25)	N/A	1	2WU	0.25	30										
TOTAL FOR MAP NO. 7								**0.25**											
I-5831A	Madison	8	RAMP (RMP-5	FROM SR 1346 TO I-26 (MP 0.00 - MP 0.30)	N/A	1	2WU	0.3	30										
TOTAL FOR MAP NO. 8								**0.3**											
I-5831A	Madison	9	AREA (RST-50	FROM I-26 TO I-26 (MP 0.00 - MP 0.70)	N/A	1	2WU	0.7	30										
TOTAL FOR MAP NO. 9								**0.7**											
TOTAL FOR PROJ NO. I-5831A								**20.53**		**430**	**224**	**2**	**3**	**15**	**260**	**16**	**64**	**2**	**100**
GRAND TOTAL								**20.53**		**430**	**224**	**2**	**3**	**15**	**260**	**16**	**64**	**2**	**100**