

AS-BUILT REPAIR QUANITY TABLE DECK SURFACE REPAIR - SPAN A ESTIMATE ACTUAL 0.0 SQ. YDS. CLASS II SURFACE PREPARATION LATEX MODIFIED CONCRETE-ES 8.2 CU. YDS. PLACING & FINISHING LMC-ES OVERLAY 131.0 SQ. YDS. SCARIFYING BRIDGE DECK 131.0 SQ. YDS. HYDRO-DEMOLITION OF BRIDGE DECK 131.0 SQ. YDS. 1087.0 SQ.FT. GROOVING BRIDGE FLOORS DECK SURFACE REPAIR - APPROACH SLAB ACTUAL ESTIMATE CLASS II SURFACE PREPARATION 0.0 SQ. YDS. LATEX MODIFIED CONCRETE-ES 4.6 CU. YDS. PLACING & FINISHING LMC-ES OVERLAY 73.0 SQ. YDS. 73.0 SQ. YDS. SCARIFYING BRIDGE DECK HYDRO-DEMOLITION OF BRIDGE DECK 73.0 SQ. YDS. GROOVING BRIDGE FLOORS 606.0 SQ.FT.

NOTES

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

PAYMENT FOR CLASS II SURFACE PREPARATION IS BASED ON THE SQUARE YARD OF ADDITIONAL DEMOLITION REQUIRED FOLLOWING HYDRO-DEMOLITION OF THE BRIDGE DECK. SEE SPECIAL PROVISIONS.

FOR SECTION A-A, SEE JOINT DETAILS, SHEET.

FOR LMC-ES OVERLAY, SEE SPECIAL PROVISION.

FOR BRIDGE JOINT DEMOLITION, SEE SPECIAL PROVISIONS.

FOR BRIDGE JOINT DEMOLITION QUANTITIES, SEE FOAM JOINT DETAIL SHEET.



CLASS II SURFACE REPAIR



BRIDGE JOINT DEMOLITION

PROJECT NO. I-5831A MADISON ____ COUNTY BRIDGE NO. 560550

SHEET 1 OF 3

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

DECK SURFACE REPAIR SPAN A

amber Male B04B5A4F2FAD484... 03/18/2022

SHEET NO REVISIONS S6-04 NO. BY: DATE: DATE: DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

3/18/2022 R:\Structures\FinalPlans\406_007_I5831_SMU_DSR_A_S6-04_560550.dgn