

TOTAL BILL OF MATERIAL															
BRIDGE NO.	INCIDENTAL MILLING	ASPHALT CONCRETE SURFACE COURSE TYPE S9.5B	ASPHALT BINDER FOR PLANT MIX	ASBESTOS ASSESSMENT	REINFORCED CONCRETE DECK SLAB	GROOVING BRIDGE FLOORS	APPROX. 22,518 LBS STRUCTURE STEEL	CLASSIC CONCRETE BRIDGE RAIL	CLASS II SURFACE PREPARATION	ELASTOMERIC BEARINGS	SHOTCRETE REPAIRS	EPOXY RESIN INJECTION	REMOVAL OF EXISTING STRUCTURE	FOAM JOINT SEALS FOR PRESERVATION	POURABLE SILICONE JOINT SEALANT
	SO. YD.	TON	TON	LUMP SUM	SO. FT.	SO. FT.	LUMP SUM	LIN. FT.	SO. YD.	LUMP SUM	CU. FT.	LIN. FT.	LUMP SUM	LIN. FT.	LIN. FT.
060016											3.3	4.0			48.0
060027											9.5				48.0
060028	404.4	40	5	LUMP SUM	1445	26,113.8	LUMP SUM	79.42	32.9	LUMP SUM	237.1	15.5	LUMP SUM		507.5
060077												31.0		640.0	
730127														330.0	
TOTAL	404.4	40	5	LUMP SUM	1445	26,113.8	LUMP SUM	79.42	32.9	LUMP SUM	249.9	50.5	LUMP SUM	970.0	603.5

TOTAL BILL OF MATERIAL										
BRIDGE NO.	POLYESTER POLYMER CONCRETE MATERIALS	EPOXY POLYMER CONCRETE MATERIALS (ALTERNATE)	ELASTOMERIC CONCRETE FOR PRESERVATION	EPOXY OVERLAY SYSTEM II	BRIDGE JOINT DEMOLITION	CONCRETE DECK REPAIR FOR POLYMER CONCRETE OVERLAY	PLACING AND FINISHING POLYMER CONCRETE OVERLAY	SCARIFYING BRIDGE DECK	SHOTBLASTING BRIDGE DECK	SILANE DECK TREATMENT
	CU. YD.	CU. YD.	CU. FT.	SO. FT.	SO. FT.	SO. YD.	SO. YD.	SO. YD.	SO. YD.	SO. YD.
060016				3520.0						
060027									577.8	577.8
060028	121.6	121.6				32.9	3,143.7	3,143.7	3,143.7	
060077			160.0		640.0				12,025.0	12,025.0
730127			82.5		330.0				6,704.0	6,704.0
TOTAL	121.6	121.6	242.5	3520.0	970.0	32.9	3,143.7	3,143.7	22,450.5	19,306.8

NOTES:

AT THE TIME OF PREPARATION OF THESE PLANS, IT WAS NOT ANTICIPATED THAT ITEMS SHOWN BELOW WOULD BE REQUIRED. HOWEVER, IT MAY BE DETERMINED IN THE FIELD THAT THESE ITEMS, OR OTHER WORK WILL BE NECESSARY TO PROPERLY COMPLETE THE INTENDED BRIDGE PRESERVATION/REHABILITATION WORK. THE CONTRACTOR SHALL BE PREPARED TO PERFORM SUCH WORK IN A TIMELY MANNER, AS DETERMINED IN THE FIELD. SUCH WORK SHALL BE CONSIDERED EXTRA WORK AND SHALL BE ADDRESSED AS PER ARTICLE 104-7 OF THE STANDARD SPECIFICATIONS. PROJECT SPECIAL PROVISIONS THAT OUTLINE REQUIREMENTS FOR THESE POTENTIAL ADDITIONAL WORK ITEMS HAVE BEEN PROVIDED IN PROJECT DOCUMENTS, BUT NO QUANTITIES HAVE BEEN LISTED. ACTUAL PAY ITEMS, QUANTITIES, AND COSTS WILL BE ESTABLISHED, AS REQUIRED, IF EXTRA WORK IS ENCOUNTERED.

UNANTICIPATED ITEMS:

ITEM NO.	DESCRIPTION	UNIT
1	CONCRETE DECK REPAIR FOR EPOXY OVERLAY	SO. FT.
2	CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT	SO. FT.
3	CLASS III SURFACE PREPARATION	SO. YD.
4	CONCRETE REPAIRS	CU. FT.

PROJECT NO. 15BPR.56
 BEAUFORT & PITT COUNTIES
 BRIDGE NO.: 060016
060027
060028
060077 &
730127



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 BILL OF MATERIAL

DRAWN BY : S. T. SANDOR DATE : 09/2021
 CHECKED BY : W. C. SMITH DATE : 09/2021

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-3
2			4			TOTAL SHEETS 5