

AS-BUILT REPAIR QUANTITY TABLE

DECK SURFACE REPAIRS - SPANS 1 THROUGH 3

	ESTIMATE	ACTUAL
SHOTBLASTING BRIDGE DECK	784.0 SQ. YDS.	
SILANE DECK TREATMENT	784.0 SQ. YDS.	
CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT	0.0 SQ. FT.	

DECK SURFACE REPAIRS - APPROACH SLAB 1

	ESTIMATE	ACTUAL
SHOTBLASTING BRIDGE DECK	87.1 SQ. YDS.	
SILANE DECK TREATMENT	87.1 SQ. YDS.	
CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT	0.0 SQ. FT.	

BARRIER RAIL REPAIRS

	ESTIMATE	ACTUAL
EPOXY RESIN INJECTION	31.0 LIN. FT.	

JOINT REPAIR

	ESTIMATE	ACTUAL
BRIDGE JOINT DEMOLITION	64.0 SQ. FT.	

NOTES




FOR SILANE DECK TREATMENT, SEE SPECIAL PROVISIONS.

FOR CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT, SEE SPECIAL PROVISIONS.

FOR SECTIONS A-A AND B-B, SEE "JOINT REPAIR DETAILS" SHEET.

FOR EPOXY RESIN INJECTION, SEE SPECIAL PROVISIONS.

FOR BRIDGE JOINT DEMOLITION, SEE SPECIAL PROVISIONS.

-  SHOTBLASTING AND SILANE DECK TREATMENT AREA
-  ERI - EPOXY RESIN INJECTION
-  BRIDGE JOINT DEMOLITION

PROJECT NO. 15BPR.56
BEAUFORT COUNTY
 BRIDGE NO. 060077

SHEET 1 OF 10



DocuSigned by:
 P. Corey Newton
 4FEE3D1431B407...
 01/27/2022


STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

SUPERSTRUCTURE PLAN OF SPANS AND APPROACH SLAB 1


REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S4-8
2			4			TOTAL SHEETS 17

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED



PLAN
 (APPROACH SLAB 1 AND SPANS 1 & 2)



PLAN
 (SPAN 3)

DRAWN BY : S. T. SANDOR DATE : 07/2021
 CHECKED BY : W. C. SMITH DATE : 12/2021