



| AS-BUILT REPAIR QUANTITY TABLE | | |
|--|------------------|--------|
| DECK SURFACE REPAIRS - SPANS 8 THROUGH 11 | | |
| | ESTIMATE | ACTUAL |
| SHOTBLASTING BRIDGE DECK | 1,187.6 SQ. YDS. | |
| SILANE DECK TREATMENT | 1,187.6 SQ. YDS. | |
| CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT | 0.0 SQ. FT. | |
| BARRIER RAIL REPAIRS | | |
| | ESTIMATE | ACTUAL |
| EPOXY RESIN INJECTION | 0.0 LIN. FT. | |
| JOINT REPAIR | | |
| | ESTIMATE | ACTUAL |
| BRIDGE JOINT DEMOLITION | 64.0 SQ. FT. | |

NOTES

- FOR SILANE DECK TREATMENT, SEE SPECIAL PROVISIONS.
- FOR CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT, SEE SPECIAL PROVISIONS.
- FOR SECTION B-B, SEE "JOINT REPAIR DETAILS" SHEET.
- FOR EPOXY RESIN INJECTION, SEE SPECIAL PROVISIONS.
- FOR BRIDGE JOINT DEMOLITION, SEE SPECIAL PROVISIONS.

- SHOTBLASTING AND SILANE DECK TREATMENT AREA
- ERI - EPOXY RESIN INJECTION
- BRIDGE JOINT DEMOLITION

PROJECT NO. 15BPR.56
BEAUFORT COUNTY
 BRIDGE NO. 060077

SHEET 3 OF 10



DocuSigned by:
P. Corey Newton
 4FFE9D1431B407...
 01/27/2022

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**SUPERSTRUCTURE
 PLAN OF SPANS**

DRAWN BY : S. T. SANDOR DATE : 07/2021
 CHECKED BY : W. C. SMITH DATE : 12/2021

| NO. | REVISIONS | | | NO. | REVISIONS | | | SHEET NO. |
|-----|-----------|-------|--|-----|-----------|-------|-----------------|-----------|
| | BY: | DATE: | | | BY: | DATE: | | |
| 1 | | | | 3 | | | S4-10 | |
| 2 | | | | 4 | | | TOTAL SHEETS 17 | |

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED