PROJECT REFERENCE NO.	SHEET NO.
B-5694	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	17+50	18+00	LT	25
4	-L-	18+00	19+86.1	LT	95
5	-L-	24+50	26+00	RT	65
				SUBTOTAL	185
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					7700
				TOTAL	7885
				SAY	7900

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	19+86.1	20+54.5	LT	20
6	-DET-	20+00	20+67.3	RT	20
				SUBTOTAL	40
		ADDITIONAL PSRM TO BE INSTALLED			0
				TOTAL	40
				SAY	50