

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
R-4705	X-1H

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt
Y5	(cu. yd.)	(cu. yd.)	Y11	(cu. yd.)	(cu. yd.)	Y17	(cu. yd.)	(cu. yd.)	Y25	(cu. yd.)	(cu. yd.)	RPD/LPD	(cu. yd.)	(cu. yd.)
13+95.30	29	6	10+16.00	0	0	15+00.00	24	4	12+94.30	0	0	13+87.14	0	0
			10+50.00	7	12	15+24.91	3	3	13+00.00	0	0	14+00.00	2	0
Station	Uncl. Exc.	Embt	11+00.00	17	26	Station	Uncl. Exc.	Embt	13+50.00	12	2	14+50.00	9	84
Y6	(cu. yd.)	(cu. yd.)	11+50.00	21	32	Station	Uncl. Exc.	Embt	14+00.00	21	3	14+86.66	4	122
			12+00.00	11	22	Y18	(cu. yd.)	(cu. yd.)	14+50.00	27	6			
12+89.43	0	0	12+41.43	12	8				15+00.00	20	6			
13+00.00	5	1				10+18.07	0	0	15+41.54	7	1			
13+50.00	53	11	Station	Uncl. Exc.	Embt	10+50.00	11	6						
14+00.00	70	8				11+00.00	38	13	Station	Uncl. Exc.	Embt			
14+50.00	69	4	Y12	(cu. yd.)	(cu. yd.)	11+50.00	68	10	Y26	(cu. yd.)	(cu. yd.)			
15+24.41	81	1	10+16.06	0	0	12+00.00	68	1						
			10+50.00	0	4	12+50.00	35	2	10+18.06	0	0			
Station	Uncl. Exc.	Embt	11+00.00	27	13	12+50.99	0	0	10+50.00	3	10			
Y7	(cu. yd.)	(cu. yd.)	11+50.00	45	11	Station	Uncl. Exc.	Embt	11+00.00	24	10			
			12+00.00	36	8	Station	Uncl. Exc.	Embt	11+50.00	52	9			
10+22.80	0	0	12+45.18	23	7	Y19	(cu. yd.)	(cu. yd.)	12+00.00	35	9			
10+50.00	0	34							12+50.76	4	2			
11+00.00	0	122	Station	Uncl. Exc.	Embt	12+60.68	0	0	Station	Uncl. Exc.	Embt			
11+50.00	0	138				13+00.00	79	8	Y27	(cu. yd.)	(cu. yd.)			
12+00.00	2	65	Y13	(cu. yd.)	(cu. yd.)	13+50.00	204	14						
12+50.00	10	28	13+38.78	0	0	14+00.00	238	23	11+44.87	0	0			
13+00.00	16	12	13+50.00	5	1	14+50.00	296	41	11+50.00	2	0			
			14+00.00	40	9	15+00.00	215	50	12+00.00	42	1			
Station	Uncl. Exc.	Embt	14+50.00	49	18	15+48.54	103	55	12+50.00	40	7			
Y8	(cu. yd.)	(cu. yd.)	15+00.00	31	22	Station	Uncl. Exc.	Embt	13+00.00	27	12			
			15+50.00	12	12	Y21	(cu. yd.)	(cu. yd.)	13+50.00	20	10			
13+06.92	0	0	15+67.53	1	3				13+76.24	7	3			
13+50.00	27	1				Station	Uncl. Exc.	Embt						
14+00.00	89	4	Station	Uncl. Exc.	Embt	10+18.00	0	0	Station	Uncl. Exc.	Embt			
14+50.00	121	8				10+50.00	17	0	Y28	(cu. yd.)	(cu. yd.)			
15+00.00	69	5	Y15	(cu. yd.)	(cu. yd.)	11+00.00	22	0						
15+30.34	6	0	13+14.93	0	0	11+50.00	14	1	10+18.03	0	0			
			13+50.00	17	0	12+00.00	9	1	10+50.00	19	3			
Station	Uncl. Exc.	Embt	14+00.00	47	3	12+43.95	3	0	11+00.00	51	6			
Y9	(cu. yd.)	(cu. yd.)	14+50.00	25	3	Station	Uncl. Exc.	Embt	11+50.00	52	10			
			15+00.00	4	20	Y23	(cu. yd.)	(cu. yd.)	12+00.00	26	8			
13+30.83	0	0	15+17.48	0	14				12+23.55	5	1			
13+50.00	1	0				Station	Uncl. Exc.	Embt						
14+00.00	7	1	Station	Uncl. Exc.	Embt	10+18.29	0	0	Station	Uncl. Exc.	Embt			
14+50.00	37	2				10+50.00	1	8	RPAL/LPA	(cu. yd.)	(cu. yd.)			
15+00.00	36	3	Y16	(cu. yd.)	(cu. yd.)	11+00.00	2	102						
15+55.55	6	3	10+16.00	0	0	11+50.00	2	236	12+25.00	0	0			
			10+50.00	54	0	12+00.00	2	141	12+50.00	6	0			
Station	Uncl. Exc.	Embt	10+97.57	98	0	Station	Uncl. Exc.	Embt	12+61.03	2	0			
Y10	(cu. yd.)	(cu. yd.)	Station	Uncl. Exc.	Embt	Y24	(cu. yd.)	(cu. yd.)	13+00.00	4	98			
									13+50.00	4	125			
10+22.00	0	0	Y17	(cu. yd.)	(cu. yd.)	11+17.58	0	0	13+94.83	4	0			
10+50.00	28	12	12+96.11	0	0	11+50.00	3	4						
11+00.00	43	19	13+00.00	2	0	12+00.00	3	8						
11+50.00	32	15	13+50.00	30	2	12+50.00	5	5						
12+00.00	31	8	14+00.00	40	6	13+00.00	14	3						
12+43.60	31	1	14+50.00	53	5	13+25.89	10	0						