
PROJECT REFERENCE NO.

R-5726A



SHEET NO.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

INDEX OF SHEETS

EC-1 THRU EC-26

SHEET NUMBER SHEET

1 TITLE SHEET

A INDEX OF SHEETS, STANDARDS AND GENERAL NOTES

EROSION CONTROL PLANS

1B CONVENTIONAL SYMBOLS

3B-1 SUMMARY OF BUILDING REMOVAL

3P-1 THRU 3P-2 PARCEL INDEX SHEETS

RW01 SURVEY CONTROL TITLE SHEET

RW02C-1 THRU RW02C-11 SURVEY CONTROL SHEETS

RW02D-1 PROPOSED ALIGNMENT CONTROL SHEET

RW03E-1 THRU RW03E-5 RIGHT OF WAY CONTROL SHEETS

RW04 THRU RW26 RIGHT OF WAY PLANS

TMP-1 THRU TMP-1A TRAFFIC MANAGEMENT PLANS

EFF. 01-16-2018 REV.

2018 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January, 2018 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO. TITLE
DIVISION 2 - EARTHWORK

200.03 Method of Clearing - Method III

GENERAL NOTES:

2018 SPECIFICATIONS
EFFECTIVE: 01-16-2018
REVISED:

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III. WHERE PUE EXISTS BEYOND THE LIMITS OF METHOD III, CLEARING WILL EXTEND TO THE OUTMOST LIMITS OF THE PUE.

SAFETY CLEARING:

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE AREAS IN THE PLANS DESIGNATED SAFETY CLEARING. THE LIMITS ARE AS SHOWN AND THE CLEARING AND GRUBBING IS CONSIDERED A PART OF THE LUMP SUM ITEM FOR "CLEARING AND GRUBBING".