SUMMARY OF QUANTITIES

PROJECT NO.	SHEET NO.	TOTAL NO.
I-6046 47995.3.1	13	32

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYPICAL SECTION NO.	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	0000400000-N CONSTRUCTION SURVEYING LS	0008000000-E SUPPLEMENTARY CLEARING & GRUBBING ACR	0022000000-E UNCLASSIFIED EXCAVATION CY	0156000000-E REMOVAL OF EXISTING ASPHALT PAVEMENT SY	0196000000-E GEOTEXTILE FOR SOIL STABILIZATION SY	0227000000-E CLEARING & GRUBBING FOR WIDENING ACR	1011000000-N FINE GRADING LS	1099500000-E SHALLOW UNDERCUT CY	1099700000-E CLASS IV SUBGRADE STABILIZATION TON	1220000000-E INCIDENTAL STONE BASE TON	1297000000-E MILLING ASPHALT PAVEMENT, 1.5" DEPTH SY	1297000000-E MILLING ASPHALT PAVEMENT, 2.25" DEPTH SY	1308000000-E MILLING ASPHALT PAVEMENT, 1.5" TO 5.25" SY	1308000000-E MILLING ASPHALT PAVEMENT, 2.25" TO 6" SY	1330000000-E INCIDENTAL MILLING SY	1491000000-E ASPHALT CONC BASE COURSE, TYPE B25.0C TON
I-6046 47995.3.1	NASH AND EDGECOMBE	3		US-64 (RAMP GORE) TO SR-1613	5	1		NO	NO	0.25	24											3,690					
				TOTAL FOR MAP 3						0.25												3,690					
		4		US-64 (LOOP GORE) TO SR-1613	6	1		NO	NO	0.16	VAR											3,470					
				TOTAL FOR MAP 4						0.16												3,470					
		5		US-64 (RAMP GORE) TO SR-1613	6	1		NO	NO		VAR											3,900					
				TOTAL FOR MAP 5																		3,900					
		6		US-64 (RAMP GORE) TO SR-1613	5	2	MD	NO	NO	0.18	30											3,200					
				TOTAL FOR MAP 6						0.18												3,200					
		7		US-64 (RAMP GORE) TO BRIDGE	5	2	MD	NO	NO	0.41	32											7,630					
				BRIDGE TO BRIDGE	BRIDGE	2				0.06	40																
				BRIDGE TO RESURFACE JOINT(US-64 BUS)	5	2	MD	NO	NO	0.19	32											3,680					
				TOTAL FOR MAP 7						0.66												11,310					
		8		US-64 (RAMP GORE) TO END C&G	6	1		NO	NO	0.09	24											1,300					
				END C&G TO BRIDGE	5	1		NO	NO	0.14	24											1,990					
				BRIDGE TO BRIDGE	BRIDGE					0.06	24																
				BRIDGE TO RESURFACE JOINT(US-64 BUS)	5	1		NO	NO	0.20	24											3,800					
				TOTAL FOR MAP 8						0.49												7,090					
		9		US-64 (RAMP GORE) TO RESURFACE JOINT(US-64 BUS)	5	1		NO	NO	0.34	24											4,650					
				TOTAL FOR MAP 9						0.34												4,650					
		10		US-64 (RAMP GORE) TO RESURFACE JOINT(US-64 BUS)	5	1		NO	NO	0.21	20											2,780					
				TOTAL FOR MAP 10						0.21												2,780					
		11		US-64 (RAMP GORE) TO RESURFACE JOINT FOR PROJECT U-3330 (US-301)	5	1		NO	NO	0.23	20											2,750					
				TOTAL FOR MAP 11						0.23												2,750					
		12		US-64 (LOOP GORE) TO RESURFACE JOINT FOR PROJECT U-3330 (US-301)	6	1		NO	NO	0.05	20											600					
				TOTAL FOR MAP 12						0.05												600					
		13		US-64 (RAMP GORE) TO RESURFACE JOINT FOR PROJECT U-3330 (US-301)	5	1		NO	NO	0.23	20											3,010					
				TOTAL FOR MAP 13						0.23												3,010					
		14		US-64 (RAMP GORE) TO RESURFACE JOINT FOR PROJECT U-3330 (US-301)	5	1		NO	NO	0.16	20											1,900					
				TOTAL FOR MAP 14						0.16												1,900					
		15		US-64 (RAMP GORE) TO NC-43	5	1		NO	NO	0.17	20											2,190					
				TOTAL FOR MAP 15						0.17												2,190					
		16		US-64 (LOOP GORE) TO NC-43	6	1		NO	NO	0.12	20											1,580					
				TOTAL FOR MAP 16						0.12												1,580					
		17		US-64 (LOOP GORE) TO NC-43	6	1		NO	NO	0.10	20											1,290					
				TOTAL FOR MAP 17						0.10												1,290					
		18		US-64 (RAMP GORE) TO NC-43	5	1		NO	NO	0.18	20											2,680					
				TOTAL FOR MAP 18						0.18												2,680					
		19		US-64 (RAMP GORE) TO US-301 BUS	5	1		NO	NO	0.26	20											3,130					
				TOTAL FOR MAP 19						0.26												3,130					
		20		US-64 (LOOP GORE) TO US-301 BUS	6	1		NO	NO	0.14	20											2,260					
				TOTAL FOR MAP 20						0.14												2,260					
		21		US-64 (RAMP GORE) TO US-301 BUS	5	1		NO	NO	0.35	20											4,680					
				TOTAL FOR MAP 21						0.35												4,680					
		22		US-64 (RAMP GORE) TO US-301 BUS	6	1		NO	NO	0.16	20											1,850					
				TOTAL FOR MAP 22						0.16												1,850					
		23		US-64 (RAMP GORE) TO NC-97	6	1		NO	NO	0.13	20											1,690					
				TOTAL FOR MAP 23						0.13												1,690					
		24		US-64 (LOOP GORE) TO NC-97	5	1		NO	NO	0.17	20											2,360					
				TOTAL FOR MAP 24						0.17												2,360					
		25		US-64 (LOOP GORE) TO NC-97	6	1		NO	NO	0.16	20											2,050					
				TOTAL FOR MAP 25						0.16												2,050					
		26		US-64 (RAMP GORE) TO NC-97	5	1		NO	NO	0.23	20											2,750					
				TOTAL FOR MAP 26						0.23												2,750					
		27		US-64 (RAMP GORE) TO US-64 A	5	1		NO	NO	0.25	20											3,000					
				TOTAL FOR MAP 27						0.25												3,000					
		28		US-64 (RAMP GORE) TO US-64 A	5	1		NO	NO	0.21	20											2,800					
				TOTAL FOR MAP 28						0.21												2,800					