SUMMARY OF QUANTITIES

PROJECT NO.	SHEET NO.	TOTAL NO.
I-6046 47995.3.1	27	32

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYPICAL SECTION NO.	8867000000-E SILICON JOINT REPLACEMENT (GREATER THAN 2" WIDE) LF	8881000000-E JOINT REPAIR USING ELASTOMETIC CONCRETE CY	8881000000-E ASPHALT JOINT REPAIR/REPLACEMENT (18"-24" WIDE, WITH PLATE) CY	8893000000-E CONCRETE DECK REPAIR (CLASS II) USING ELASTOMETIC CONCRETE SY
I-6046 47995.3.1	NASH AND EDGECOMBE	1	US-64 WBL	BEGIN SR-1225 EXIT RAMP TO GORE	2				
				GORE TO GORE	7				
				GORE TO END SR-1225 EXIT RAMP	2				
				END SR-1225 EXIT RAMP TO SR-1233 (THOMAS ROAD)	7				
				SR-1233 (THOMAS ROAD) TO BEGIN US64A EXIT RAMP	1				
				BEGIN US64A EXIT RAMP TO GORE	2				
				GORE TO GORE	1				
				GORE TO END US64A ENTRANCE RAMP	2				
				END US64A ENTRANCE RAMP TO BEGIN BRIDGE OVER SR-1243	1				
				BEGIN BRIDGE OVER SR-1243 TO END BRIDGE OVER SR-1243	BRIDGE	40	1.2		
				END BRIDGE OVER SR-1243 TO BEGIN NC97 EXIT RAMP	1				
				BEGIN NC97 EXIT RAMP TO BEGIN BRIDGE OVER TAR RIVER	2				
				BEGIN BRIDGE OVER TAR RIVER TO END BRIDGE OVER TAR RIVER (GORE)	BRIDGE	63	1.5		
				END BRIDGE OVER TAR RIVER (GORE) TO GORE	1				
				GORE TO BEGIN BRIDGE OVER NC-97 & END EXIT LOOP	2				
				BEGIN BRIDGE OVER NC-97 & END EXIT LOOP TO END BRIDGE OVER NC-97	BRIDGE	39	1.4		
				END BRIDGE OVER NC-97 TO BEGIN BRIDGE OVER RAILROAD	1				
				BEGIN BRIDGE OVER RAILROAD TO END BRIDGE OVER RAILROAD	BRIDGE	39	1.4		
				END BRIDGE OVER RAILROAD TO BEGIN BRIDGE OVER US-301BUS	1				
				BEGIN BRIDGE OVER US-301BUS TO END BRIDGE OVER US-301BUS	BRIDGE	39	1.4		
				END BRIDGE OVER US-301BUS TO BEGIN US-301BUS EXIT LOOP	1				
				BEGIN US-301BUS EXIT LOOP TO GORE	2				
				GORE TO GORE	1				
				GORE TO END US-301BUS ENTRANCE RAMP	2				
				END US-301BUS ENTRANCE RAMP TO BEGIN NC-43BUS EXIT RAMP	1				
				BEGIN NC-43BUS EXIT RAMP TO GORE	2				
				GORE TO GORE	1				
				GORE TO BEGIN BRIDGE OVER NC-43BUS	2				
				BEGIN BRIDGE OVER NC-43BUS TO END BRIDGE OVER NC-43BUS	BRIDGE	39	1.4		
				END BRIDGE OVER NC-43BUS TO END NC-43BUS ENTRANCE RAMP	2				
				END NC-43BUS ENTRANCE RAMP TO BEGIN US-301BYP EXIT LOOP	1				
				BEGIN US-301BYP EXIT LOOP TO BEGIN BRIDGE OVER US-301BYP	2				
				BEGIN BRIDGE OVER US-301BYP TO END BRIDGE OVER US-301BYP	BRIDGE	39	1.4		
				END BRIDGE OVER US-301BYP TO GORE	2				
				GORE TO GORE	1				
				GORE TO BEGIN BRIDGE OVER SR-1616	2				
				BEGIN BRIDGE OVER SR-1616 TO END BRIDGE OVER SR-1616	BRIDGE	17	1.2		
				END BRIDGE OVER SR-1616 TO END US-301BYP ENTRANCE RAMP	2				
				END US-301BYP ENTRANCE RAMP TO BEGIN US-64BUS EXIT LOOP	1				
				BEGIN US-64BUS EXIT LOOP TO GORE	2				
				GORE TO GORE	1				
				GORE TO END US-64BUS ENTRANCE RAMP	2				
				END US-64BUS ENTRANCE RAMP TO BEGIN TAPER 3-4 LANES	1				
				BEGIN TAPER 3-4 LANES TO END TAPER 3-4 LANES	1				
				END TAPER 3-4 LANES TO BEGIN SR-1613 EXIT LOOP	1				
				BEGIN SR-1613 EXIT LOOP TO GORE	2				
				GORE TO GORE	1				
				GORE TO END SR-1613 ENTRANCE RAMP	2				
				END SR-1613 ENTRANCE RAMP TO BEGIN TAPER FOR CD LANE	1			6	
				BEGIN TAPER FOR CD LANE TO CD LANE & BEGIN PAVED DITCH	4				
				CD LANE & BEGIN PAVED DITCH TO BEGIN BRIDGE OVER I-95	3				
				BEGIN BRIDGE OVER I-95 TO END BRIDGE OVER I-95	BRIDGE	93	2.7		
				END BRIDGE OVER I-95 TO CD LANE & END PAVED DITCH	3				
				CD LANE & END PAVED DITCH TO END TAPER FOR PAVED DITCH @ CD LANE	4				
				END TAPER FOR PAVED DITCH @ CD LANE TO END RESURFACING ON PROJECT U-5996	1				
				TOTAL FOR MAP 1		408	13.6	6	