Project No.	Sheet No.
I-6040	7

MAP 1 - EAST BOUND I-40 GUARDRAIL

MILE MARKER/ RANGE	SIDE OF RDWY. RT/LT	TL-3 END UNIT (EA)	REMOVE & RESET TL-3 * END UNIT (EA)	CAT-1 UNIT (EA)	REMOVE & RESET CAT-1 * UNIT (EA)	REMOVE & REPLACE TL-3 END UNIT (EA)	STEEL BEAM GR SHOP CURVED (LF)	REMOVE & REPLACE GR (LF)	STEEL BEAM GUARDRAIL (LF)	GUARDRAIL PRE-FAB ANCHOR POSTS (GENERIC)	REMOVE & RESET EXISTING GR (LF) *
390.07 - 390.08	LT	1							75		
390.13 - 390.14	LT			1					75		
390.44 - 390.57	RT	1	1		1			63			415
391.24 - 391.26	LT	1							80		
391.29 - 391.31	LT			1					95		
393.29 - 393.41	RT				1						554
393.28 - 393.29	LT		1						25		
393.41 - 393.42	LT				1				25		
395.71 - 395.72	LT		1						35		
395.75 - 395.76	LT				1				60		
397.08 - 397.16	RT		1		1					3	377
398.15 - 398.27	RT				1					12	590
398.26 - 396.27	LT		1						30		
398.31 - 398.32	LT				1				60		
398.69 - 398.72	RT				1						75
399.14 - 399.15	LT		1						30		
399.18 - 399.19	LT				1				55		
403.67 - 403.69	LT		1						75		
403.71 - 403.73	LT				1				95		
404.97 - 405.19	RT		1								455
405.37 - 405.38	LT		1						35		
405.41 - 405.42	LT				1				60		
MAP 1 - TOTAL		3	9	2	11	0	0	63	910	15	2466

* REMOVE and RESET guardrail end units are included in Remove and Reset Existing Guardrail LF on Sheet 11 and are not paid for as Each. This chart is just used for Mile Marker Range/location.