STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
B-5301	X-1

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
11+00.00	83	0
11+50.00	80	5
12+00.00	55	11
12+50.00	47	11
13+00.00	57	7
13+50.00	62	6
14+00.00	45	6
14+50.00	21	26
15+00.00	13	80
15+50.00	19	190
16+00.00	20	358
16+50.00	9	583
17+00.00	0	877
17+50.00	0	1219
18+00.00	0	1588
18+50.00	0	2034
19+00.00	0	2512
19+50.00	0	2962
20+00.00	0	3355
20+50.00	0	3781
21+00.00	0	4270
21+50.00	0	4641
22+00.00	0	4837
22+50.00	0	5009
23+00.00	0	5197
23+50.00	0	5369
24+00.00	0	5520
24+50.00	0	4926

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
27+50.00	0	0
28+00.00	0	2583
28+50.00	0	4280
29+00.00	0	4751
29+50.00	0	4618
30+00.00	0	4438
30+50.00	0	4191
31+00.00	0	3934
31+50.00	0	3639
32+00.00	0	3241
32+50.00	0	2824
33+00.00	0	2353
33+50.00	0	1829
34+00.00	0	1369
34+50.00	0	998
35+00.00	0	629
35+50.00	0	331
36+00.00	7	182
36+50.00	39	82
37+00.00	77	16

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
37+50.00	8	8
38+00.00	23	13
38+50.00	31	9
39+00.00	34	11
39+50.00	105	7
40+00.00	95	27
40+50.00	21	32
41+00.00	29	10
41+50.00	29	8
42+00.00	17	4

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00	0	0
11+50.00	32	4
12+00.00	50	4
12+50.00	49	10
13+00.00	51	22
13+50.00	25	26
14+00.00	11	19
14+50.00	39	15
15+00.00	101	8
15+50.00	189	2
16+00.00	264	0
16+50.00	386	0
17+00.00	514	0
17+50.00	596	0
18+00.00	739	0
18+50.00	885	0
19+00.00	1031	0
19+50.00	1200	0
20+00.00	1260	0
20+50.00	1229	0
21+00.00	1199	0
21+50.00	1171	0
22+00.00	1162	0
22+50.00	1169	0
23+00.00	1175	0
23+50.00	1153	0
24+00.00	910	0
24+50.00	349	0

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
26+00.00	0	0
26+50.00	830	30
27+00.00	773	35
27+50.00	663	44
28+00.00	566	55
28+50.00	511	59
29+00.00	494	47

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
29+50.00	501	31
30+00.00	507	16
30+50.00	520	3
31+00.00	512	0
31+50.00	467	0
32+00.00	456	0
32+50.00	458	0
33+00.00	400	0
33+50.00	295	0
34+00.00	189	0
34+50.00	119	0
35+00.00	56	0
35+50.00	10	11
36+00.00	0	25
36+50.00	1	31
37+00.00	5	24
37+50.00	13	11
38+00.00	17	7
38+50.00	15	12
39+00.00	15	18
39+50.00	14	19
40+00.00	6	14
40+50.00	15	19
41+00.00	28	28
41+50.00	24	21
42+00.00	11	9

Station Dr1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.000	0	0
10+75.000	14	11
11+00.000	10	1
11+10.000	2	0

Station Dr2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+25.000	0	0
10+50.000	5	0
10+75.000	8	3
11+00.000	9	3
11+25.000	13	1
11+50.000	23	0

Station L LT (DR2)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+50.000	0	0
15+00.000	21	1
15+50.000	16	7
16+00.000	16	9
16+50.000	34	4
17+00.000	59	1
17+50.000	47	0

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.000	0	0
10+75.000	21	85
11+00.000	41	31
11+25.000	42	12
11+50.000	22	5
11+60.000	0	0