

DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA

---



---

PROJECT REFERENCE NO.	SHEET NO.
<i>B-5772</i>	<i>EC-3B</i>
RW SHEET NO. HYDRAULICS ENGINEER	

# ***SOIL STABILIZATION TIMEFRAMES***

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
<i>PERIMETER DIKES, SWALES, DITCHES AND SLOPES</i>	<i>7 DAYS</i>	<i>NONE</i>
<i>HIGH QUALITY WATER (HQW) ZONES</i>	<i>7 DAYS</i>	<i>NONE</i>
<i>SLOPES STEEPER THAN 3:1</i>	<i>7 DAYS</i>	<i>IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.</i>
<i>SLOPES 3:1 OR FLATTER</i>	<i>14 DAYS</i>	<i>7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.</i>
<i>ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1</i>	<i>14 DAYS</i>	<i>NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.</i>