




ELAST	OMERIC CONCRETE					
END BENT NO.	ELASTOMERIC CONCRETE * (CU.FT.)					
1	5 <b>.</b> 5					
2	5 <b>.</b> 5					
TOTAL	11.0					

\* BASED ON THE MINIMUM BLOCKOUT SHOWN.









## PLAN VIEW

## TEMPORARY BERM AND SLOPE DRAIN DETAILS

(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)




SECTION A-A



SECTION B-B


## JOINT SEAL DETAILS @ END BENT

FOAM JOINT SEAL TO BE CUT, HEAT WELDED AND TURNED UP PARALLEL TO SLOPED FACE OF THE VERTICAL CONCRETE BARRIER RAIL. THE JOINT SHALL BE SAWED PRIOR TO THE CASTING OF THE VERTICAL CONCRETE BARRIER RAIL.



NOTE: IF THE APPROACH SLAB IS NOT CONSTRUCTED IMMEDIATELY AFTER THE BACKFILLING OF THE END BENT EXCAVATION, GRADE TO DRAIN TO THE BOTTOM OF THE SLOPE AND PROVIDE EROSION RESISTANT MATERIAL, SUCH AS FIBERGLASS ROVING OR AS DIRECTED BY THE ENGINEER TO PREVENT SOIL EROSION AND TO PROTECT THE AREA ADJACENT TO THE STRUCTURE. THE CONTRACTOR WILL BE REQUIRED TO REMOVE THESE MATERIALS PRIOR TO CONSTRUCTION OF THE APPROACH SLAB. TEMPORARY DRAINAGE DETAIL

> PROJECT NO. B-5772 ROWAN COUNTY STATION: 20+91.04 -EL-



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH STANDARD

> BRIDGE APPROACH SLAB DETAILS

	REVISIONS						SHEET NO.
OCUMENT NOT CONSIDERED	NO.	BY:	DATE:	NO.	BY:	DATE:	S-25
FINAL UNLESS ALL	1			3			TOTAL SHEETS
SIGNATURES COMPLETED	2			4			25

M.G.SHAIKH \_ DATE : <u>02/2021</u> DRAWN BY : \_ A. SORSENGINH \_ DATE : <u>05/2021</u> CHECKED BY : . DESIGN ENGINEER OF RECORD: A. SORSENGINH DATE: 05/2021

3/25/2022
I:\Structures\FinalPlans \ OBD\401\_051\_B5772\_SMU\_AS\_S25\_790066.dgn \ ksedai

STD. NO. BAS4 (SHT 1)