

DocuSign Envelope ID: 339A4862-092B-4CB6-9EA3-60F591A307B7

PROJECT REFERENCE NO. SHEET NO. B-3186 / B-5898 ITS-24



## **NOTES**

- 1. INSTALL A MINIMUM OF THREE (3) GROUNDING ELECTRODES SPACED A MINIMUM OF 10 FEET APART. ENSURE THAT EXISTING UNDERGROUND FACILITIES ARE NOT DAMAGED DURING INSTALLATION.
- 2. TEST GROUNDING SYSTEM USING AN APPROVED METHOD. SYSTEM SHOULD MEASURE TWENTY (20) OHMS OR LESS. ADDITIONAL GROUNDING ELECTRODES SHALL BE INSTALLED AS DIRECTED BY THE ENGINEER TO MEET THIS REQUIREMENT.
- 3. USE MECHANICAL CRIMP FOR ALL CONNECTIONS TO GROUND RODS.
- 4. INSTALL MARKER TAPE DIRECTLY ABOVE ALL GROUNDING ELECTRODES AND CONDUCTORS AT A DEPTH OF 12 INCHES.
- 5. REMOVE BONDING JUMPER IN EQUIPMENT CABINET IF INSTALLED BETWEEN AC NEUTRAL AND EQUIPMENT GROUND.
- 6. BOND ALL RIGID GALVANIZED STEEL CONDUITS ENTERING THE CABINET TO "EQUIPMENT GROUND".
- 7. INSTALL CONDUIT BETWEEN DISCONNECT AND CABINET.
- 8. ENSURE EQUIPMENT GROUND IS ELECTRICALLY BONDED TO CABINET.



HDR Engineering, Inc. of the Carolinas 555 Fayetteville St, Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116

DYNAMIC MESSAGE SIGN ELECTRICAL SERVICE AND GROUNDING TYPICAL DETAIL

<u> Division 14 \_ \_ Haywood County \_</u> PLAN DATE: APRIL 13, 2022 REVIEWED BY: C. BEARD PREPARED BY: T. MCHENRY APPROVED BY: M. VOLZ

REVISIONS INIT. DATE

SEAL 046589

DOCUMENT NOT CONSIDERED

FINAL UNLESS ALL

SIGNATURES COMPLETED

Watthew a. Vot 4/14/2022 CADD FILE NAME: B3186-B5898\_ITS\_LAYOUT.DCN