


NOTE: IF THE APPROACH SLAB IS NOT CONSTRUCTED IMMEDIATELY AFTER THE BACKFILLING OF THE END BENT EXCAVATION, GRADE TO DRAIN TO THE BOTTOM OF THE SLOPE AND PROVIDE EROSION RESISTANT MATERIAL, SUCH AS FIBERGLASS ROVING OR AS DIRECTED BY THE ENGINEER TO PREVENT SOIL EROSION AND TO PROTECT THE AREA ADJACENT TO THE STRUCTURE. THE CONTRACTOR WILL BE REQUIRED TO REMOVE THESE MATERIALS PRIOR TO CONSTRUCTION OF THE APPROACH SLAB.


TEMPORARY DRAINAGE DETAIL



NOTE: IMMEDIATELY AFTER THE CONSTRUCTION OF THE APPROACH SLAB, THE CONTRACTOR SHALL PROVIDE TEMPORARY BERM AND SLOPE DRAIN. CONTRACTOR SHALL GRADE TO PIPE INLET AND PROVIDE EROSION RESISTANT MATERIAL AS SHOWN. THE EROSION RESISTANT MATERIAL SHALL BE EITHER 1) ASPHALT PLANT MIX, TYPE 1 OR TYPE 2, MIN. 2" DEPTH, 2) EROSION CONTROL MAT, OR 3) CONCRETE, AS DIRECTED BY THE ENGINEER. THE SLOPE DRAIN SHALL CONSIST OF A NON-PERFORATED TEMPORARY DRAINAGE PIPE, 12 INCHES IN DIAMETER.

TEMPORARY BERM AND SLOPE DRAIN DETAILS


(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)



BILL OF MATERIAL						
APPROACH SLAB AT END BENT 1						
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	
*A1	17	#4	STR	39'-5"	448	
A2	18	#4	STR	39'-5"	474	
*B1	60	#5	STR	15'-3"	955	
B2	60	#6	STR	16'-5"	1480	
*B3	6	#5	STR	9'-3"	58	
B4	6	#6	STR	9'-7"	87	
REINFORCING STEEL					LBS.	2,041
* EPOXY COATED REINFORCING STEEL					LBS.	1,461
CLASS AA CONCRETE					C. Y.	29.4
APPROACH SLAB AT END BENT 2						
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	
*A1	17	#4	STR	38'-3"	435	
A2	18	#4	STR	38'-3"	460	
*B1	61	#5	STR	15'-3"	971	
B2	61	#6	STR	16'-5"	1505	
REINFORCING STEEL					LBS.	1,965
* EPOXY COATED REINFORCING STEEL					LBS.	1,406
CLASS AA CONCRETE					C. Y.	28.6

PROJECT NO. B-3186/B-5898
HAYWOOD COUNTY
 STATION: 68+65.75 ± -L-RT-

SHEET 3 OF 3



Eric Nolting 1/25/2022

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**BRIDGE APPROACH
 SLAB DETAILS**

REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1	--	--	3	--	--
2	--	--	4	--	--

SHEET NO. SO3R-49
 TOTAL SHEETS 61



DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

PLOT DRIVER: NCDOT_STRUCTURE_DEFAULT_PLOTTER.plt PENTABLE: NCDOT_STRUCTURE_DEFAULT_PEN.tbl
 USER: PPETERSO DATE: 1/24/2022 TIME: 2:45:49 PM
 FILE: ... \404.240.B5898B3186.SMU.AS.049.430107.dgn

DES BY: <u>F. CORDOVA</u>	DATE: <u>07/21</u>	DWG BY: <u>M. SELLS</u>	DATE: <u>07/21</u>
DES CHK: <u>G. MYERS</u>	DATE: <u>07/21</u>	CHK BY: <u>G. MYERS</u>	DATE: <u>07/21</u>