


See Sheet 1A For Index of Sheets
See Sheet 1B For Conventional Plan Sheet Symbols
See Sheet 1C-1 Through 1C-? For Survey Control Sheets

T.I.P. NO.	SHEET NO.
B-4786	UC-1

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TIP PROJECT: B-4786



VICINITY MAP



RIGHT OF WAY PLANS

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS


UTILITY CONSTRUCTION PLANS PITT COUNTY

LOCATION: REPLACE BRIDGE NO. 38 OVER THE TAR RIVER
ON US 13 IN GREENVILLE

TYPE OF WORK: WATER LINE RELOCATION



CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.
THIS PROJECT IS WITHIN THE MUNICIPAL BOUNDARIES OF GREENVILLE.



SHEET NO.	DESCRIPTION
UC-1	TITLE SHEET
UC-2	UTILITY SYMBOLOGY
UC-3	NOTES
UC-3A	DETAILS
UC-4 THRU UC-5	UTILITY CONSTRUCTION SHEETS
UC-6 THRU UC-8	PROFILE SHEETS

WATER AND SEWER OWNERS ON PROJECT

(A) GREENVILLE UTILITIES COMMISSION

PREPARED IN THE OFFICE OF:

HINDE ENGINEERING

License No. C-2639
401 Harrison Oaks Blvd., Suite 220 Cary, NC 27513
Ph. (919) 653-0001

Clint L. Stevens, P.E. UTILITIES PROJECT MANAGER
Corey D. Bousquet, P.E. UTILITIES PROJECT ENGINEER
Jordan K. Chapman UTILITIES PROJECT DESIGNER

SEAL

2/14/2022

DIVISION OF HIGHWAYS UTILITIES UNIT
1555 MAIL SERVICES CENTER
RALEIGH NC 27699-1555
PHONE (919) 707-6690
FAX (919) 250-4151

Nabil S. Hamdan UTILITIES REGIONAL ENGINEER
Stephen G. Sealy UTILITIES ENGINEER
Tanga N. Sampson UTILITIES AREA COORDINATOR
Larry M. James UTILITIES COORDINATOR

09-FEB-2022 14:03 S:\Server\Files\PROJECTS\2018\A2018302.00_NCDOT_B-4786\Design\Utilities\Engineering\UC\Proj\B4786_Ut_tsh_UC1.psh.dgn

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS



PROJECT REFERENCE NO. B-4786	SHEET NO. UC-2
---------------------------------	-------------------

UTILITIES PLAN SHEET SYMBOLS

PROPOSED WATER SYMBOLS

Water Line (Sized as Shown) 12" WL
11¼ Degree Bend ++
22½ Degree Bend +x
45 Degree Bend +X
90 Degree Bend +†
Plug
Tee ††
Cross †††
Reducer ▶
Gate Valve GV
Butterfly Valve BV
Tapping Valve TGV
Line Stop LS
Line Stop with Bypass LS/BP
Blow Off BO
Fire Hydrant PFH
Relocate Fire Hydrant RFH
Remove Fire Hydrant REM FH
Water Meter PWM
Relocate Water Meter RWM
Remove Water Meter REM WM
Water Pump Station PS(W)
RPZ Backflow Preventer PRPZ
DCV Backflow Preventer PBFP
Relocate RPZ Backflow Preventer RRPZ
Relocate DCV Backflow Preventer RBFP

PROPOSED SEWER SYMBOLS

Gravity Sewer Line (Sized as Shown) 12" SS
Force Main Sewer Line (Sized as Shown) 12" FSS
Manhole (Sized per Note) •
Sewer Pump Station PS(SS)

PROPOSED MISCELLANEOUS UTILITIES SYMBOLS

Power Pole 0
Telephone Pole -0-
Joint Use Pole -0-
Telephone Pedestal TEL PED
Utility Line by Others (Type as Shown) PROP O/H POW LINES
Trenchless Installation 12" TL INSTALL
Encasement by Open Cut 24" ENCAS. BY OC
Encasement 24" ENCASUREMENT

Thrust Block
Air Release Valve AR
Utility Vault UV
Concrete Pier CP
Steel Pier SP
Plan Note NOTE
Pay Item Note PAY ITEM


EXISTING UTILITIES SYMBOLS

Power Pole •	*Underground Power Line P
Telephone Pole •	*Underground Telephone Cable T
Joint Use Pole •	*Underground Telephone Conduit TC
Utility Pole •	*Underground Fiber Optics Telephone Cable T FO
Utility Pole with Base □	*Underground TV Cable TV
H-Frame Pole •—•	*Underground Fiber Optics TV Cable TV FO
Power Transmission Line Tower ☒	*Underground Gas Pipeline G
Water Manhole ⊗	Aboveground Gas Pipeline A/G Gas
Power Manhole ⊗	*Underground Water Line W
Telephone Manhole ⊗	Aboveground Water Line A/G Water
Sanitary Sewer Manhole ⊗	*Underground Gravity Sanitary Sewer Line SS
Hand Hole for Cable ☒	Aboveground Gravity Sanitary Sewer Line A/G Sanitary Sewer
Power Transformer ☒	*Underground SS Forced Main Line FSS
Telephone Pedestal ☒	Underground Unknown Utility Line ?UL
CATV Pedestal ☒	SUE Test Hole •
Gas Valve ◇	Water Meter ⊖
Gas Meter ◇	Water Valve ⊗
Located Miscellaneous Utility Object ⊖	Fire Hydrant ◇
Abandoned According to Utility Records AATUR	Sanitary Sewer Cleanout ⊗
End of Information E.O.I.		

*For Existing Utilities
 Utility Line Drawn from Record (Type as Shown) W
 Designated Utility Line (Type as Shown) W


8302.00 UC-2 2/1/2012 8:58 AM 8302.00 UC-2 2/1/2012 8:58 AM 8302.00 UC-2 2/1/2012 8:58 AM
 C:\Users\jgibson\Documents\Projects\B4786 UC-2\syms\UC2_psh.dgn

UTILITY CONSTRUCTION



License No. C-2639
401 Harrison Oaks Blvd., Suite 220 Cary, NC 27513

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

PROJECT REFERENCE NO.	SHEET NO.
B-4786	UC-3
DESIGNED BY: JKC	
DRAWN BY: JKC	
CHECKED BY: CLS	
APPROVED BY: CDB	
REVISED:	
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION UTILITIES ENGINEERING SEC. PHONE: (919) 707-6690 FAX: (919) 250-4151	
UTILITY CONSTRUCTION PLANS ONLY	

GENERAL NOTES:

1. THE PROPOSED UTILITY CONSTRUCTION SHALL MEET THE APPLICABLE REQUIREMENTS OF THE NC DEPARTMENT OF TRANSPORTATION'S "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" DATED JANUARY 2018.

2. THE EXISTING UTILITIES BELONG TO GREENVILLE UTILITIES COMMISSION. THE CONTRACTOR IS REQUIRED TO CONTACT SCOTT FARMER, PE, GUC - WATER RESOURCES SYSTEMS ENGINEER, AT (252)-551-1529 AT LEAST 2 WEEKS PRIOR TO ANY WATER LINE CONSTRUCTION.

3. ALL WATER LINES TO BE INSTALLED WITHIN COMPLIANCE OF THE RULES AND REGULATIONS OF THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENTAL QUALITY, DIVISION OF WATER RESOURCES, PUBLIC WATER SUPPLY SECTION. ALL SEWER LINES TO BE INSTALLED WITHIN COMPLIANCE OF THE RULES AND REGULATIONS OF THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT QUALITY, DIVISION OF WATER RESOURCES, WATER QUALITY SECTION. PERFORM ALL WORK IN ACCORDANCE WITH THE APPLICABLE PLUMBING CODES.

4. THE UTILITY OWNER OWNS THE EXISTING UTILITY FACILITIES AND WILL OWN THE NEW UTILITY FACILITIES AFTER ACCEPTANCE BY THE DEPARTMENT. THE DEPARTMENT OWNS THE CONSTRUCTION CONTRACT AND HAS ADMINISTRATIVE AUTHORITY. COMMUNICATIONS AND DECISIONS BETWEEN THE CONTRACTOR AND UTILITY OWNER ARE NOT BINDING UPON THE DEPARTMENT OR THIS CONTRACT UNLESS AUTHORIZED BY THE ENGINEER. AGREEMENTS BETWEEN THE UTILITY OWNER AND CONTRACTOR FOR THE WORK THAT IS NOT PART OF THIS CONTRACT OR IS SECONDARY TO THIS CONTRACT ARE ALLOWED, BUT ARE NOT BINDING UPON THE DEPARTMENT.

5. PROVIDE ACCESS FOR THE DEPARTMENT PERSONNEL AND THE OWNER'S REPRESENTATIVES TO ALL PHASES OF CONSTRUCTION. NOTIFY DEPARTMENT PERSONNEL AND THE UTILITY OWNER TWO WEEKS PRIOR TO COMMENCEMENT OF ANY WORK AND ONE WEEK PRIOR TO SERVICE INTERRUPTION. KEEP UTILITY OWNERS' REPRESENTATIVES INFORMED OF WORK PROGRESS AND PROVIDE OPPORTUNITY FOR INSPECTION OF CONSTRUCTION AND TESTING.

6. THE PLANS DEPICT THE BEST AVAILABLE INFORMATION FOR THE LOCATION, SIZE, AND TYPE OF MATERIAL FOR ALL EXISTING UTILITIES. MAKE INVESTIGATIONS FOR DETERMINING THE EXACT LOCATION, SIZE, AND TYPE MATERIAL OF THE EXISTING FACILITIES AS NECESSARY FOR THE CONSTRUCTION OF THE PROPOSED UTILITIES AND FOR AVOIDING DAMAGE TO EXISTING FACILITIES. REPAIR ANY DAMAGE INCURRED TO EXISTING FACILITIES TO THE ORIGINAL OR BETTER CONDITION AT NO ADDITIONAL COST TO THE DEPARTMENT.

7. MAKE FINAL CONNECTIONS OF THE NEW WORK TO THE EXISTING SYSTEM WHERE INDICATED ON THE PLANS, AS REQUIRED TO FIT THE ACTUAL CONDITIONS, OR AS DIRECTED.

8. MAKE CONNECTIONS BETWEEN EXISTING AND PROPOSED UTILITIES AT TIMES MOST CONVENIENT TO THE PUBLIC, WITHOUT ENDANGERING THE UTILITY SERVICE, AND IN ACCORDANCE WITH THE UTILITY OWNER'S REQUIREMENTS. MAKE CONNECTIONS ON WEEKENDS, AT NIGHT, AND ON HOLIDAYS IF NECESSARY.

9. ALL UTILITY MATERIALS SHALL BE APPROVED PRIOR TO DELIVERY TO THE PROJECT. SEE 1500-7, " SUBMITTALS AND RECORDS" IN SECTION 1500 OF THE STANDARD SPECIFICATIONS.

10. CONTRACTOR SHALL FIELD VERIFY THE VERTICAL AND HORIZONTAL ALIGNMENTS OF THE PROPOSED UTILITY TIE-IN POINTS SHOWN ON THE PLANS. ONCE THE TIE-IN POINTS AND GRADE OF PROPOSED UTILITY LINES ARE VERIFIED AS CORRECT, THE CONTRACTOR CAN BEGIN CONSTRUCTION ON THE PROPOSED UTILITY LINES.

PROJECT SPECIFIC NOTES:

1. USE DUCTILE IRON RESTRAINED JOINT PIPE FOR BOTH WATER LINE RELOCATIONS.

UTILITY CONSTRUCTION

2018\FEB-2022\4403\PROJECTS\2018\A2018302\00_NCDOT_B-4786\Design\Utilities\Engineering\UC\Proj\B-4786_Ut_notes_UC3_psh.dgn
 2018\FEB-2022\4403\PROJECTS\2018\A2018302\00_NCDOT_B-4786\Design\Utilities\Engineering\UC\Proj\B-4786_Ut_notes_UC3_psh.dgn

NOT TO SCALE


HINDE ENGINEERING
 License No. C-2639
 401 Harrison Oaks Blvd., Suite 220 Cary, NC 27513

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

PROJECT REFERENCE NO. B-4786	SHEET NO. UC-3A
DESIGNED BY: JKC	
DRAWN BY: JKC	
CHECKED BY: CLS	
APPROVED BY: CDB	
REVISED:	
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION UTILITIES ENGINEERING SEC. PHONE: (919) 707-6690 FAX: (919) 250-4151	


PROJECT TYPICAL DETAILS

UTILITY CONSTRUCTION



MAXIMUM TRENCH WIDTH AT TOP OF PIPE

NOMINAL PIPE SIZE (INCHES)	TRENCH WIDTH (INCHES)	NOMINAL PIPE SIZE (INCHES)	TRENCH WIDTH (INCHES)
4	28	20	44
6	30	24	48
8	32	30	54
10	34	36	60
12	36	42	66
14	38	48	72
16	40	54	78
18	42		



RESULTANT THRUST AT FITTING AT 150 PSI WATER PRESSURE

NOM. PIPE DIA.	TOTAL POUNDS				
	DEAD END	90° BEND	45° BEND	22-1/2° BEND	11-1/4° BEND
4"	2,700	3,800	2,100	1,100	530
6"	5,800	8,000	4,300	2,200	1,100
8"	9,700	13,800	7,400	3,800	1,900
10"	14,500	20,500	11,100	5,700	2,900
12"	20,500	29,000	15,700	8,000	4,000
14"	27,800	39,000	21,100	11,000	5,400
16"	35,700	50,400	27,300	14,000	7,000
18"	44,800	63,400	34,400	17,500	8,800
20"	55,000	77,000	42,100	21,500	10,800
24"	78,500	110,000	60,000	31,600	15,400
30"	120,600	170,800	92,300	47,100	23,800
36"	172,800	244,400	132,300	67,500	33,900
42"	233,300	330,000	178,600	91,000	45,700
48"	304,000	430,000	232,700	118,600	59,600
54"	384,100	543,200	294,000	149,000	75,300

SOIL BEARING LOAD (LB./SQ. FT.)

MUCK	0
SOFT CLAY	1,000
SILT	1,500
SANDY SILT	3,000
SAND	4,000
SANDY CLAY	6,000
HARD CLAY	9,000

POLYWRAP SHALL BE USED TO COVER FITTINGS AND BOLTS.

TO DETERMINE THE SIZE OF A CONCRETE THRUST BLOCK, DIVIDE THE TOTAL FORCE BY THE BEARING VALUES OF THE SOIL. THE QUOTIENT WILL BE THE SIZE OF THE BEARING AREA OF THE THRUST BLOCK IN SQUARE FEET. APPROXIMATE VALUES FOR VARIOUS TYPES OF SOIL ARE LISTED IN TABLE.

NO RESPONSIBILITY CAN BE ASSUMED FOR THE ACCURACY OF THE DATA IN THIS TABLE DUE TO THE WIDE VARIATION OF BEARING LOAD CAPABILITIES FOR EACH SOIL TYPE.

TYPES OF THRUST BLOCKING

ONLY USE THRUST BLOCKING AT WATER LINE TIE-IN POINTS

VALVE BOX DETAIL FOR VALVES 12" AND LARGER			GREENVILLE UTILITIES GREENVILLE, N.C.				NO.	DATE	DESCRIPTION
SHEET	DWG. NO. W-6	DWG. N. WOOTEN	WATER RESOURCES ENGINEERING GREENVILLE, N.C.						
1 OF 1	DATE 3-12-99	APP H. COREY							


THRUST BLOCKING DETAIL			GREENVILLE UTILITIES GREENVILLE, N.C.				NO.	DATE	DESCRIPTION
SHEET	DWG. NO. W-12	DWG. N. WOOTEN	WATER RESOURCES ENGINEERING GREENVILLE, N.C.						
1 OF 1	DATE 3-12-99	APP H. COREY							


2015 FEB-20 14:03 P:\PROJECTS\2018\AZ2018302\00_NCDOT_B-4786\Design\Utilities\Engineering\UC\Proj\B-4786_Ut_dtl_UC3A_psh.dgn

END TIP PROJECT B-4786
-L- POT Sta. 34 +50.00


HINDE ENGINEERING
License No. C-2639
401 Harrison Oaks Blvd., Suite 220 Cary, NC 27513

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

PROJECT REFERENCE NO. B-4786	SHEET NO. UC-5
DESIGNED BY: JKC	
DRAWN BY: JKC	
CHECKED BY: CLS	
APPROVED BY: CDB	
REVISED:	
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION UTILITIES ENGINEERING SEC. PHONE: (919) 707-6690 FAX: (919) 250-4151	
2/15/2022 UTILITY CONSTRUCTION PLANS ONLY	



UTILITY CONSTRUCTION



REMOVE 78' OF 12" CI WATER LINE

PROP. 53' OF 8" WATER LINE (RJ DI, PC 350)

SEE BRIDGE PLANS FOR 8" WATER LINE ATTACHMENT THE 8" WATER LINE WILL BE REMOVED ONCE THE PROPOSED 12" WATER LINE IS ACTIVATED

PROP. 414' OF 8" WATER LINE (RJ DI, PC 350)

PROP. 8" VALVE

SEE BRIDGE PLANS FOR 12" WATER LINE ATTACHMENT

PROP. 367' OF 12" WATER LINE (RJ DI, PC 350)

33' OF 12" WATER LINE (RJ DI, PC 350)

PROP. 72' OF 12" WATER LINE (RJ DI, PC 350)

PROP. 12" VALVE

ABANDON 450' OF 12" UTILITY PIPE

ABANDON 535' OF 8" UTILITY PIPE *

* AFTER THE NEW 12" WATER LINE IS ACTIVATED. THE REMOVAL OF THE 8" DI RJ WATER PIPE, PIPE HANGERS/RODS, LATERAL SUPPORTS AND EXPANSION JOINTS ARE INCIDENTAL TO THE ROADWAY PAY ITEM FOR ABANDON 535' OF 8" UTILITY PIPE. ALL MATERIALS REMOVED ARE TO BE STOCKPILE AT A LOCATION DETERMINED BY GUC.

NOTE:
THE ESTIMATED QUANTITY OF DUCTILE IRON WATER PIPE FITTINGS ON THIS PLAN SHEET IS 2500 POUNDS. THE ACTUAL QUANTITY AND TYPE OF FITTINGS WILL VARY BASED ON FIELD CONDITIONS.

REVISIONS


MATCHLINE -L- STA. 24+50.00
SEE SHEET UC-04

END CONSTRUCTION
-L- STA 38+12.09


15-FEB-2022 07:45
S:\5-15-2022\PROJECTS\2018\A2018302.00_NCDOT_B-4786\Design\Utilities\Engineering\UC-Proj\64786-Ut_rdy_05_UC5_psh.dgn

HINDE ENGINEERING
 License No. C-2639
 401 Harrison Oaks Blvd., Suite 220 Cary, NC 27513

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

PROJECT REFERENCE NO. B-4786	SHEET NO. UC-8
DESIGNED BY: JKC	
DRAWN BY: JKC	
CHECKED BY: CLS	
APPROVED BY: CDB	
REVISED:	
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION UTILITIES ENGINEERING SEC. PHONE: (919) 707-6690 FAX: (919) 250-4151	
UTILITY CONSTRUCTION PLANS ONLY	

UTILITY CONSTRUCTION



WATER LINE 2

2015 FEB 20 2022 14:04
 C:\Users\jfk\Documents\Projects\2018\A2018302\00_NC DOT_B-4786\Design\Utilities\Engineering\UC\Proj\B-4786_Ut_UC8.pfl_esh.dgn
 3335151711