PROJECT NO.	SHEET NO.
2022CPT.03.07.20101, Etc.	9

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	4457000000-N TEMPORARY TRAFFIC CONTROL	4720000000-E THERMO RXR 90 MILS	4810000000-E 4" WHITE PAINT	4810000000-E 4" YELLOW PAINT	4891000000-E GENERIC MARKING, 24" X 90 M WHITE THERMO	4900000000-N YELLOW & YELLOW MARKERS
								MI	FT	SF	LS	EA	LF	LF	LF	EA
2022CPT.03.07.20101	Brunswick	1	SR 1514 (MILL CREEK ROAD)	FROM US 17 HWY. (OCEAN HWY.) TO NC 87 HWY. (GEORGE II HWY.) [MP 0.05 - MP 2.60]	1	2	2WU	2.55	19				54,876	41,344		173
TOTAL FOR MAP NO. 1								**2.55**					**54,876**	**41,344**		**173**
2022CPT.03.07.20101	Brunswick	2	SR 1126 (MORGAN ROAD)	FROM SR 1130 (MT. PISGAH RD.) TO SR 1119 (STANLEY RD.) [MP 0.01 - MP 1.22]	1	2	2WU	1.21	20	80			26,039	19,500		82
TOTAL FOR MAP NO. 2								**1.21**		**80**	*		**26,039**	**19,500**		**82**
2022CPT.03.07.20101	Brunswick	3	SR 1128 (HEWETT ROAD)	FROM SR 1115 (STONE CHIMMEY RD. SW) TO SR 1119 (STANLEY RD. NW) [MP 0.00 - MP 1.24]	1	2	2WU	1.24	20				26,685	19,650		85
TOTAL FOR MAP NO. 3								**1.24**					**26,685**	**19,650**		**85**
2022CPT.03.07.20101	Brunswick	4	SR 1129 (TURNPIKE ROAD)	FROM SR 1115 (STONE CHIMNEY RD.) TO SR 1130 (MT. PISGAH RD.) [MP 0.01 - MP 1.59]	1	2	2WU	1.58	20				34,002	25,344		106
TOTAL FOR MAP NO. 4								**1.58**					**34,002**	**25,344**		**106**
TOTAL FOR PROJ NO. 2022CPT.03.07.20101								**6.58**		**80**	*		**141,602**	**105,838**		**446**
													247,440			**446**
2022CPT.03.07.20102	Brunswick	7	SR 1488 (NATIONAL AVE. NE)	FROM SR 1725 (LEXINGTON AVE. NE) TO SR 1607 (ECHO DR.NE) [MP 0.00 - MP 0.81]	2	2	2WU	0.81	21							
TOTAL FOR MAP NO. 7								**0.81**								
2022CPT.03.07.20102	Brunswick	8	SR 1489 (PARKWOOD DR. NE)	FROM SR 1437 (OLD FAYETTEVILLE RD. NE) TO SR 1488 (NATIONAL AVE. NE) [MP 0.01 - MP 0.32]	2	2	2WU	0.31	20							
TOTAL FOR MAP NO. 8								**0.31**								
2022CPT.03.07.20102	Brunswick	9	SR 1491 (WINSTON AVE. NE)	FROM SR 1437 (OLD FAYETTEVILLE RD. NE) TO SR 1488 (NATIONAL AVE. NE) [MP 0.00 - MP 0.07]	2	2	2WU	0.07	20							
TOTAL FOR MAP NO. 9								**0.07**								
2022CPT.03.07.20102	Brunswick	10	SR 1492 (DAVIDSON AVE. NE)	FROM SR 1488 (NATIONAL AVE. NE) TO SR 1488 (NATIONAL AVE. NE) [MP 0.01 - MP 0.20]	2	2	2WU	0.19	20							
TOTAL FOR MAP NO. 10								**0.19**								
2022CPT.03.07.20102	Brunswick	11	SR 1607 (ECHO DR. NE)	FROM SR 1488 (NATIONAL AVE. NE) TO SR 1608 (SALEM DR. NE) [MP 0.00 - MP 0.28]	2	2	2WU	0.28	21							
TOTAL FOR MAP NO. 11								**0.28**								
2022CPT.03.07.20102	Brunswick	12	SR 1608 (SALEM DR. NE)	FROM SR 1607 (ECHO DR. NE) TO 1725 (LEXINGTON AVE. NE) [MP 0.00 - MP 0.07]	2	2	2WU	0.07	20							
TOTAL FOR MAP NO. 12								**0.07**								
2022CPT.03.07.20102	Brunswick	13	SR 1724 (PADDINGTON AVE. NE)	FROM 1488 (NATIONAL AVE. NE) TO 1488 (NATIONAL AVE. NE) [MP 0.00 - MP 0.33]	2	2	2WU	0.33	20		*					
TOTAL FOR MAP NO. 13								**0.33**								
2022CPT.03.07.20102	Brunswick	14	SR 1725 (LEXINGTON AVE. NE)	FROM 1488 (NATIONAL AVE. NE) TO SR 1488 (NATIONAL AVE. NE) [MP 0.00 - MP 0.39]	2	2	2WU	0.39	20							
TOTAL FOR MAP NO. 14								**0.39**								
2022CPT.03.07.20102	Brunswick	15	SR 1712 (INDUSTRIAL BLVD. NE)	FROM SR 1426 (MT. MISERY RD. NE) TO END OF MAINTENANCE [MP 0.00 - MP 0.39]	2	2	2WU	0.39	21							
TOTAL FOR MAP NO. 15								**0.39**								
2022CPT.03.07.20102	Brunswick	16	SR 1713 (POPULAR ST. NE)	FROM US 74/76 (ANDREW JACKSON HWY.) TO END OF MAINTENANCE [MP 0.00 - MP 0.28]	2	2	2WU	0.28	22			2			25	
TOTAL FOR MAP NO. 16								**0.28**				**2**			**25**	
2022CPT.03.07.20102	Brunswick	17	SR 1714 (POPULAR ST. NE / ENTERPRISE DR. NE)	FROM US 74/76 (ANDREW JACKSON HWY.) TO END OF MAINTENANCE [MP 0.00 - MP 0.39]	2	2	2WU	0.39	23				4,000	2,400		26
TOTAL FOR MAP NO. 17								**0.39**					**4,000**	**2,400**		**26**
2022CPT.03.07.20102	Brunswick	18	SR 1440 (CHURCH RD. NE)	FROM SR 1437 (OLD FAYETTEVILLE RD.) TO END OF MAINTENANCE [MP 0.00 - MP 0.21]	2	2	2WU	0.21	21							
TOTAL FOR MAP NO. 18								**0.21**								
TOTAL FOR PROJ NO. 2022CPT.03.07.20102								**3.72**			*	**2**	**4,000**	**2,400**	**25**	**26**
													6,400			**26**
GRAND TOTAL								**10.3**		**80**	**1.00**	**2**	**145,602**	**108,238**	**25**	**472**
													253,840			**472**