

- CONCRETE REPAIR AREA

- SHOTCRETE REPAIR AREA

(B#) BEAM NUMBER

(W) WEB PLATING REPAIR

(S) STIFFENER REPAIR (F) BOTTOM FLANGE PLATING REPAIR

REPAIR QUANTITY TABLE					
UNDERSIDE OF DECK	QUANTITIES				
REPAIRS - SPAN B	ESTIMATE		ACTUAL		
SHOTCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF	
UNDERSIDE OF DECK	0.0	0.0			
CONCRETE BENT DIAPHRAGM	12.2	4.1			
OVERHANG	1.9	0.7			
CONCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF	
UNDERSIDE OF DECK	0.0	0.0			
CONCRETE BENT DIAPHRAGM	0.0	0.0			
OVERHANG	0.0	0.0			

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MIN. OF 1"BEHIND REBAR AND MIN. 2"CL TO SAWCUT. SEE REPAIR DETAILS.

NOTES:

THE LOCATIONS AND DIMENSIONS OF THE AREAS FOR REPAIR ARE BASED ON THE BEST INFORMATION AVAILABLE. THE CONTRACTOR, IN CONJUNCTION WITH THE ENGINEER, SHALL VERIFY THE LOCATION AND EXTENT OF REPAIR AREAS PRIOR TO STEEL FABRICATION. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATION AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE REPAIR QUANTITY TABLE.

FOR ADDITIONAL NOTES, SEE SHEET 1 OF 6.

STEEL REPAIR LOCATIONS							
REPAIR	SPAN	BEAM	LOCATION	DIM. "A"	DIM. "B"	DIM. ''C''	DIM. "D"
W	В	1	BENT 1	-	-	7"	60″
F	В	1	BENT 1	51/4"	-	-	60"
S	В	5	BENT 1	3"	-	-	-
S	В	7	BENT 1	4"	-	-	-
S	В	8	BENT 1	4"	-	-	-
W	В	1	BENT 2	-	-	5″	60"
F	В	1	BENT 2	5 ¹ / ₄ "	-	-	36"
W	В	2	BENT 2	5″	48"	-	-
F	В	2	BENT 2	51/4"	48"	-	-
S	В	2	BENT 2	5″	-	-	-
W	В	4	BENT 2	11"	12"	6″	25"
S	В	4	BENT 2	34"	-	-	-
W	В	6	BENT 2	10"	10"	-	-
F	В	6	BENT 2	5″	24"	-	-
S	В	6	BENT 2	10"	-	-	-

(SEE SHEETS S1-27 AND S1-28 FOR BEAM REPAIR DETAILS AND DIMENSIONS.)

PROJECT NO. 15BPR.47 EDGECOMBE COUNTY BRIDGE NO. 320051

SHEET 2 OF 6

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

UNDERSIDE DECK REPAIRS SPAN B

BEAM END CUT-OUT

LBS.

0

ACTUAL

LBS.

3.2

545.5

106.4

SEAL O30024

Uster Ubralia 05/26/2022		
	NO.	BY:
DOCUMENT NOT CONSIDERED	110.	D.,
FINAL UNLESS ALL	1	
SIGNATURES COMPLETED	9	

03/20/2022		
DOCUMENT NOT CONSIDERED	NO.	BY:
FINAL UNLESS ALL	1	
SIGNATURES COMPLETED	2	

SHEET NO REVISIONS NO. BY: S1-11 DATE: DATE:

5/26/2022 R:\Structures\Plans\320051\401_021_15BPR.47_SMU_UD2_S1-11_320051.dgn

A. Y. GODFREY

G. AYES

DRAWN BY : _

CHECKED BY :

__ DATE : <u>01/2022</u>

DATE : 02/2022