

DIVISION OF HIGHWAYS
 STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK
 IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
PHASE II LEFT					
-L- SBL 518+00.00 TO 548+00.00	1,398		10,905	9,507	
-L- SBL 548+00.00 TO 575+43.00	4,645		9,708	5,063	
-L- SBL 596+52.00 TO 600+00.00	114		1,091	977	
-L- SBL 633+61.00 TO 643+00.00	855		2,675	1,820	
-Y4- 13+00.00 TO 22+00.00	82		11,104	11,022	
-Y4DR1- 10+12.74 TO 11+00.00	7		616	609	
-Y4DR2- 10+12.74 TO 11+00.00	9		120	111	
-Y5- RT 29+50.00 TO 39+51.18	314		390	76	
-Y5- LT 29+50.00 TO 38+63.19	68		1,839	1,771	
-Y5RPB- 10+00.00 TO 27+14.40	1,698	104	16,146	14,552	208
-SR4- 74+00.00 TO 81+77.38	434		5,468	5,034	
-SR4DR1- 10+15.00 TO 10+88.00	7		133	126	
SUBTOTAL	9,631	104	60,195	50,668	208
PHASE II RIGHT					
-L- NBL 561+00.00 TO 573+50.00	3,323		645		2,678
-L- NBL 599+00.00 TO 611+00.00	1,063		25,215	24,152	
-L- NBL 619+00.00 TO 627+30.00	27		57,795	57,768	
-L- NBL 627+30.00 TO 650+00.00	1,026		25,814	24,788	
-Y4- 28+00.00 TO 38+02.70	262		17,439	17,177	
-Y5- RT 41+47.80 TO 48+54.36	806		310		496
-Y5- LT 41+10.00 TO 48+54.36	131		1,094	963	
-Y5RPC- 16+31.15 TO 25+86.38	1,166		13,148	11,982	
-Y5RPD- 14+72.31 TO 25+33.54	3,039		66,969	65,923	1,993
-SR5- 10+12.07 TO 16+00.00	10		14,161	14,151	
-L- NBL 785+00.00 TO 797+00.00	1,625	2,047	15,020	13,395	2,047
-L- NBL 808+60.00 TO 838+50.00	17,487		14,425	1,995	8,119
-L- NBL 838+50.00 TO 868+50.00	8,158		7,125		1,033
-L- NBL 868+50.00 TO 898+50.00	14,021		4,239		9,782
-L- NBL 898+50.00 TO 915+00.00	4,193	2,768	6,238	2,045	2,768
SUBTOTAL	56,337	4,815	269,637	234,339	28,916
PHASE II MEDIAN					
-L- MED 650+00.00 TO 680+00.00	178		38,515	38,337	
-L- MED 680+00.00 TO 710+00.00	472		8,223	7,751	
-L- MED 710+00.00 TO 740+00.00	255		16,151	15,896	
-L- MED 740+00.00 TO 755+00.00	17		16,589	16,572	
-L- MED 755+00.00 TO 785+00.00	357		10,350	9,993	
SUBTOTAL	1,279	0	89,828	88,549	0
PHASE III LEFT					
-L- SBL 643+00.00 TO 650+00.00	449		1,610	1,161	
-L- SBL 650+00.00 TO 689+00.00	2,623		10,996	8,373	
-L- SBL 689+00.00 TO 694+33.00	3		655	652	
-L- SBL 694+33.00 TO 714+58.00	4,773		8,730	3,957	
-L- SBL 724+00.00 TO 755+00.00	1,526		1,153		373
-L- SBL 755+00.00 TO 774+50.00	2,385		1,548		837
SUBTOTAL	11,759	0	24,692	14,143	1,210