DocuSign Envelope ID: 3A273B2E-AE2C-4721-AC82-B9A3F6CEE731

6/2/99

REVISIONS

RIGHT OF WAY CONTROL SHEET

PROJECT REFERENCE NO.	SHEET NO.
I-5987B	RW03E-2

Location and Surveys

JoynerKeeny, PLLC
1051 N. Winstead Avenue
Rocky Mount, NC 27804
252-977-3124
North Carolina Firm Number P-0551

NORTH CAROLINA PROFESSIONAL SEAL L-3259 LAND SURVEYOR STEPHEN R. WOLFE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

I ,Stephen R. Wolfe, certify that the right of way and permanent easement monumentation for this project shown herein was completed under my direct and responsible charge from an actual survey made under my supervision; that all horizontal closures had a minimum ratio of precision of 1:10,000 (Class A). Field work was performed from 12JUL2021 to 04JAN2022, and all coordinates are based on NAD83/2011; That this survey was performed to meet the requirements of 21NCAC 56.1600 as applicable.

This 14th day of February, 2022.

DocuSigned by:
Stephen Wolfe
30B6875F3940446...

Professional Land Surveyor L-3259

ROW MARKER IRON PIN AND CAP-E

	ALIGN	STATION	OFFSET	NORTH	EAST
	Y4	13+00.00	-50.00	382311.1549	2001517.8749
	Y4	13+00.00	-30.00	382291.2308	2001516.1338
	Y4	13+00.00	30.00	382231.4586	2001510.9107
	Y4	13+00.00	55.00	382206.5535	2001508.7344
	Y4	16+05.00	65.00	382173.9454	2001813.7416
EXISTING MONUMENT	Y4	17+05.08	57.84	382175.4290	2001914.6030
	Y4	17+50.00	-70.00	382300.8703	2001965.8269
	Y4	18+50.00	-95.00	382321.5106	2002066.1062
	Y4	19+31.66	118.12	382105.5266	2002138.1120
	Y4	20+10.00	-120.00	382336.2718	2002235.7900
	Y4	30+55.00	-110.00	381897.9854	2003246.9975
	Y4	31+30.00	95.00	381697.2049	2003161.1787
	Y4	33+55.00	51.20	381562.0807	2003328.9817
	Y4	35+25.00	-53.00	381477.6610	2003509.0158
EXISTING MONUMENT	Y4	35+27.28	50.00	381419.4023	2003424.0445
	Y4	36+40.00	76.22	381310.7569	2003463.6146
	Y4	38+00.00	-30.00	381234.4837	2003639.8193
	Y4	38+00.00	-45.00	381242.6399	2003652.4079

ROW MARKER IRON PIN AND CAP-E

	ALIGN	STATION	OFFSET	NORTH	EAST
EXISTING MONUMENT	Y5	29+78.83	49.74	386849.2557	2003252.6230
	Y5	30+00.00	-40.00	386903.2607	2003327.3567
	Y5	30+00.00	-30.00	386895.6990	2003320.8131
EXISTING MONUMENT	Y5	30+39.14	49.85	386809.5810	2003298.5040
	Y5	31+40.00	-40.00	386813.5816	2003433.5829
	Y5	31+83.22	-72.39	386811.5804	2003487.2223
	Y5	32+32.96	-82.45	386788.6850	2003531.7639
	Y5	32+65.00	-43.65	386738.5896	2003532.5101
	Y5	33+80.00	-37.01	386663.3043	2003618.9923
	Y5	33+80.00	-50.00	386673.6119	2003626.8987
	Y5	34+88.58	-46.50	386604.7486	2003710.9220
	Y5	36+65.00	-48.31	386489.0345	2003848.6251
	Y5	36+65.00	-65.00	386501.4866	2003859.7388
	Y5	37+74.28	-65.00	386441.8005	2003936.9692
	Y5	38+38.00	70.05	386297.6658	2003914.9210
NOT SET, IN FENCE	Y5	38+98.00	91.76	386250.4925	2003930.9593

ROW MARKER IRON PIN AND CAP-E

ALIGN	STATION	OFFSET	NORTH	EAST
Y5RPB	11+25.00	-87.44	384730.4971	2003464.8417
Y5RPB	13+15.00	-85.00	384906.1802	2003519.5386
Y5RPB	13+17.63	-133.96	384920.8798	2003472.7683
Y5RPB	18+00.00	-75.00	385374.4711	2003615.7748
Y5RPB	19+00.00	-72.79	385475.3772	2003637.9231

ROW MARKER IRON PIN AND CAP-E

ALIGN	STATION	OFFSET	NORTH	EAST
Y5RPC	11+26.60	68.97	384617.8956	2003726.4522
Y5RPC	14+25.00	85.00	384887.0523	2003852.7367
Y5RPC	18+00.00	69.00	385223.0808	2003999.5760
Y5RPC	19+11.15	85.00	385310.6515	2004068.1523
Y5RPC	20+45.41	85.00	385426.8407	2004135.4221
Y5RPC	20+90.00	73.64	385473.9160	2004148.5367

ROW MARKER IRON PIN AND CAP-E

ALIGN	STATION	OFFSET	NORTH	EAST
Y5RPD	12+20.00	-84.00	387384.1260	2004610.8363
Y5RPD	17+85.00	-150.00	386811.0722	2004660.1464
Y5RPD	19+25.00	-150.00	386656.4060	2004634.8700
Y5RPD	20+30.00	-145.00	386544.5031	2004599.9573
Y5RPD	21+85.00	-130.00	386397.2089	2004533.5657
Y5RPD	24+61.20	-66.11	386170.4430	2004406.6300

ROW MARKER IRON PIN AND CAP-E

ALIGN	STATION	OFFSET	NORTH	EAST
Y6	14+50.00	-45.00	400742.4843	2008091.8756
Y6	14+50.00	-30.00	400733.4668	2008079.8888
Y6	15+45.00	-45.00	400666.5721	2008148.9831
Y6	21+50.00	-45.00	400195.2172	2008524.2135
Y6	23+20.00	-90.00	400096.0160	2008668.2032
Y6	23+65.00	-90.00	400062.3689	2008697.5319
Y6	24+00.00	-80.00	400029.6717	2008712.9331
Y6	25+07.57	-80.00	399949.8776	2008783.9063
Y6	34+00.00	-125.00	399294.0045	2009398.5360
Y6	38+60.00	-85.00	398902.8095	2009650.4548
Y6	44+40.00	-29.03	398416.3808	2009965.7246

ROW MARKER IRON PIN AND CAP-E

	ALIGN	STATION	OFFSET	NORTH	EAST
	Y7	18+00.00	55.00	411792.8401	2010346.2035
	Y7	18+00.00	30.00	411816.5557	2010354.1139
	Y7	18+00.00	-50.00	411892.4453	2010379.4272
	Y7	18+00.00	-30.00	411873.4729	2010373.0989
	Y7	19+12.98	55.00	411757.0902	2010453.3821
NOT SET, INSIDE FENCE W/DOG	Y7	20+11.43	-51.60	411825.2209	2010581.4464
	Y7	21+90.00	55.00	411660.3990	2010708.0931
	Y7	26+00.00	115.00	411440.0319	2011064.4226
	Y7	32+85.00	50.00	411280.9012	2011738.8020
	Y7	32+85.00	135.00	411200.2272	2011712.0305
	Y7	34+00.00	50.00	411244.6809	2011847.9491
	Y7	38+15.00	50.00	411113.9729	2012241.8278
	Y7	39+05.00	60.00	411076.1356	2012324.0977
	Y7	40+00.30	60.00	411046.1192	2012414.5498
	Y7	45+00.00	60.00	410922.0373	2012907.2469
	Y7	45+12.92	75.00	410905.0116	2012917.6842

NOTES:

1. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
2. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
3. RIGHT OF WAY MONUMENTATION ESTABLISHED 12JUL2021 TO 04JAN2022.

23-FEB-2022 07:29
23-FEB-2019 14:03
jmatthews
$$$$USER
$$$$DGN
$$$$CELL
$$$$PLOT
$$$$LEVEL
$$$$DATE
$$$$TIME
$$$$ATTR
$$$$PSCALE
$$$$PLOTDRV
$$$$PAPERSIZE
$$$$PENTABLE
$$$$ACTIVEZ
$$$$ACTIVEX
$$$$ACTIVEY